



**U.S. Army
Environmental
Center**

Feasibility Study for Functional Area II

Fort Devens, Massachusetts

January 1997
Contract No. DAAA15-90-D-0012
Delivery Order No. 0003

Prepared for:
Commander
U.S. Army Environmental Center
Aberdeen Proving Ground, Maryland 21010-5401

[DTIC QUALITY INSPECTED 3]

Prepared by:
 ecology and environment, inc.
1700 North Moore Street
Arlington, Virginia 22209

DISTRIBUTION STATEMENT A	
Approved for public release Distribution Unlimited	

Printed on Recycled Paper

Final

2&7RI1.PM4

FEASIBILITY STUDY
FOR
FUNCTIONAL AREA II
(AOC 32 AND AOC 43A)
FORT DEVENS, MASSACHUSETTS

Contract No. DAAA15-90-D-0012
Delivery Order No. 0003
ELIN A009

January 1997

Prepared for:

UNITED STATES ARMY ENVIRONMENTAL CENTER
Aberdeen Proving Ground, Maryland 21010-5401

Prepared by:

Ecology and Environment, Inc.
Arlington, Virginia 22209

19970820 141
DTIC QUALITY INSPECTED

Hussein Aldis
Hussein Aldis
E & E Project Manager, Feasibility Study

Lewis A. Welzel
Lewis A. Welzel
E & E Program Manager

Robert J. King
Robert J. King
E & E Project Manager

1

2

3

4

5

6

PREFACE

7

8

9

10

11

12

13

14

In 1991, the United States Department of the Army and the United States Environmental Protection Agency signed a Federal Facility Agreement (Inter-Agency Agreement) under Section 120 of the Comprehensive Environmental Response, Compensation, and Liability Act (CERCLA) for environmental investigations and remedial actions at Fort Devens. The agreement requires that Feasibility Studies (FSs) be undertaken at each Area of Contamination (AOC) to develop and analyze potential remedial alternatives leading to a Record of Decision.

15

16

17

18

19

20

21

22

23

24

25

26

27

In 1991, Fort Devens was identified for closure by July 1997, under Public Law 101-510, the Defense Base Closure and Realignment Act of 1990 (BRAC). This has resulted in accelerated schedules for the environmental investigations at Fort Devens. As a means of meeting the accelerated schedule, portions of the FSs were released for review as they were developed. This allowed reviewers to evaluate and agree upon decisions concerning which AOCs would qualify for a full FS. The first portion of the FS released was the draft Initial Screening of Alternatives, which was followed by the draft Detailed Analysis of Alternatives. After interagency reviews of these drafts, it was determined that the Functional Area I AOCs (AOCs 25, 26, and 27) be dropped from consideration for a full FS. Functional Area II AOCs, the Defense Reutilization and Marketing Office (DRMO) Yard (AOC 32) and the Petroleum, Oil, and Lubricants (POL) Storage Area (AOC 43A), were retained for a full FS.

1
2
3
4

5 TABLE OF CONTENTS 6 7

<u>Section</u>	<u>Page</u>
11 EXECUTIVE SUMMARY	1
13 1 INTRODUCTION	1-1
14 1.1 PURPOSE AND ORGANIZATION OF REPORT	1-1
15 1.2 SITE DESCRIPTIONS	1-1
16 1.2.1 Defense Reutilization and Marketing Office (DRMO) Yard - (AOC 32)	1-2
17 1.2.1.1 Site Description	1-2
18 1.2.1.2 Geology and Hydrology	1-3
19 1.2.1.3 Nature and Extent of Contamination	1-4
20 1.2.1.4 Human Health Risk Assessment Summary	1-10
21 1.2.1.5 Ecological Risk Assessment Summary	1-12
22 1.2.2 Petroleum, Oil, and Lubricants (POL) Storage Area - (AOC 43A)	1-13
23 1.2.2.1 Site Description	1-13
24 1.2.2.2 Geology and Hydrology	1-14
25 1.2.2.3 Nature and Extent of Contamination	1-15
26 1.2.2.4 Human Health Risk Assessment Summary	1-20
27 1.2.2.5 Ecological Risk Assessment Summary	1-23
28 1.3 RECOMMENDATIONS FROM THE REMEDIAL INVESTIGATION	1-24
30 2 REMEDIAL ACTION OBJECTIVES AND CLEANUP GOALS	2-1
31 2.1 INTRODUCTION	2-1
32 2.1.1 Applicable or Relevant and Appropriate Requirements (ARARs)	2-1
33 2.1.2 To Be Considered (TBC) Guidance	2-4
34 2.1.3 Site-Specific Risk Assessments	2-4
35 2.2 DEVELOPMENT OF REMEDIAL ACTION OBJECTIVES	2-5
36 2.3 APPROACH TO CLEANUP GOAL DETERMINATION	2-5
37 2.4 SOILS	2-6
38 2.4.1 ARARs	2-6
39 2.4.2 TBCs	2-6
40 2.4.2.1 RBCs	2-6
41 2.4.2.2 RCRA Corrective Action Levels	2-6
42 2.4.2.3 EPA Guidance on Soil Lead Concentrations	2-7

Table of Contents (Cont.)

<u>Section</u>		<u>Page</u>
1	2.4.2.4 Background Concentration	2-7
2	2.4.3 Site-Specific Human Health Risks	2-7
3	2.4.4 Selection of Cleanup Goals	2-8
4	2.5 GROUNDWATER REMEDIAL ACTION OBJECTIVES	2-8
5	2.5.1 Main Post Groundwater Cleanup Goals	2-8
6	2.5.1.1 ARARs	2-8
7	2.5.1.2 TBCs	2-9
8	2.5.1.3 Site-Specific Human Health Risks	2-9
9	2.5.1.4 Selection of Main Post Cleanup Goals	2-9
10	2.6 SURFACE WATER REMEDIAL ACTION OBJECTIVES	2-9
11	2.7 COMPARISON OF DATA TO CLEANUP GOALS	2-10
12	2.7.1 Definition of Operable Units	2-10
13	2.7.2 Areas Exceeding Cleanup Goals	2-10
14	2.7.2.1 UST 13 Soils	2-10
15	2.7.2.2 UST 13 Groundwater	2-11
16	2.7.2.3 DRMO Soils	2-11
17	2.7.2.4 DRMO Groundwater	2-12
18	2.7.2.5 DRMO Surface Water	2-12
19	2.7.2.6 POL Soils	2-12
20	2.7.2.7 POL Groundwater	2-12
21	2.7.3 ACTION-SPECIFIC AND LOCATION-SPECIFIC ARARs	2-13
22	2.7.4 CONCLUSIONS	2-14
23		
24	3 IDENTIFICATION AND SCREENING OF REMEDIAL ACTION TECHNOLOGIES AND MONITORING REQUIREMENTS	3-1
25	3.1 GENERAL RESPONSE ACTIONS	3-1
26	3.2 SOILS	3-1
27	3.2.1 No Further Action	3-1
28	3.2.2 Institutional Actions	3-2
29	3.2.3 Containment	3-2
30	3.2.3.1 Single-Layered Caps	3-2
31	3.2.3.2 Multi-Layered Caps	3-2
32	3.2.4 Excavation	3-3
33	3.2.5 Ex Situ Treatment	3-3
34	3.2.5.1 Thermal Oxidation/Incineration	3-3
35	3.2.5.2 Chemical Treatment	3-4
36	3.2.5.3 Physical Treatment	3-4
37	3.2.5.4 Biological Treatment	3-6
38	3.2.6 In Situ Treatment	3-6
39	3.2.6.1 Bioventing	3-7
40	3.2.6.2 Vapor Extraction	3-7
41	3.2.6.3 Soil Flushing	3-7
42		

Table of Contents (Cont.)

<u>Section</u>		<u>Page</u>
1	3.2.6.4	Vitrification 3-8
2	3.2.6.5	Steam Stripping 3-8
3	3.2.6.6	Radio Frequency Heating 3-8
4	3.2.6.7	Solution Mining 3-9
5	3.2.6.8	Stabilization and Solidification 3-9
6	3.2.7	Disposal 3-10
7	3.2.7.1	Off-Site Disposal 3-10
8	3.2.7.2	On-Site Disposal 3-10
9	3.2.8	Summary 3-10
10	3.3	GROUNDWATER REMEDIAL TECHNOLOGIES AND MONITORING 3-10
11	3.3.1	No Further Action 3-10
12	3.3.2	Institutional Actions 3-10
13	3.3.3	Intrinsic Remediation With Long-Term Monitoring 3-11
14	3.3.4	Containment 3-12
15	3.3.5	Collection 3-12
16	3.3.6	Ex Situ Treatment 3-13
17	3.3.6.1	Physical/Chemical Treatment 3-13
18	3.3.6.2	Biological Treatment 3-17
19	3.3.7	In Situ Treatment 3-18
20	3.3.7.1	Permeable Treatment Beds 3-18
21	3.3.7.2	Air Sparging 3-18
22	3.3.7.3	Biological Treatment 3-19
23	3.3.8	Disposal 3-19
24	3.3.8.1	Off-Site Disposal 3-19
25	3.3.8.2	On-Site Disposal 3-20
26	3.4	SUMMARY 3-20
27		
28		
29	4	DEVELOPMENT AND SCREENING OF REMEDIAL ALTERNATIVES AND MONITORING 4-1
30	4.1	DRMO YARD SOILS OPERABLE UNIT 4-1
31	4.1.1	Alternative A1: No Further Action 4-1
32	4.1.1.1	Description 4-1
33	4.1.1.2	Evaluation 4-2
34	4.1.2	Alternative A2: Institutional Actions 4-2
35	4.1.2.1	Description 4-2
36	4.1.2.2	Evaluation 4-2
37	4.1.3	Alternative A3: Containment via Capping 4-3
38	4.1.3.1	Description 4-3
39	4.1.3.2	Evaluation 4-3
40	4.1.4	Alternative A4: Excavation, Solidification, and On-Site Disposal 4-4
41		
42		

Table of Contents (Cont.)

<u>Section</u>		<u>Page</u>
1	4.1.4.1 Description	4-4
2	4.1.4.2 Evaluation	4-4
3	4.1.5 Alternative A5: Excavation, Solvent Extraction, Thermal Desorption, and Backfilling	4-5
4	4.1.5.1 Description	4-5
5	4.1.5.2 Evaluation	4-6
6	4.1.6 Alternative A6: Excavation and Off-Site Disposal	4-7
7	4.1.6.1 Description	4-7
8	4.1.6.2 Evaluation	4-8
9	4.1.7 Alternative A7: Excavation and Off-Site Incineration	4-8
10	4.1.7.1 Description	4-8
11	4.1.7.2 Evaluation	4-8
12	4.1.8 Selection of DRMO Yard Alternatives for Detailed Analysis	4-9
13		
14	4.2 UST 13 GROUNDWATER OPERABLE UNIT ALTERNATIVES	4-9
15	4.2.1 Alternative B1: No Further Action	4-9
16	4.2.1.1 Description	4-9
17	4.2.1.2 Evaluation	4-10
18	4.2.2 Alternative B2: Institutional Actions	4-10
19	4.2.2.1 Description	4-10
20	4.2.2.2 Evaluation	4-11
21	4.2.3 Alternative B3: Intrinsic Remediation (with long-term monitoring)	4-11
22	4.2.3.1 Description	4-11
23	4.2.3.2 Evaluation	4-11
24	4.2.4 Alternative B4: Containment via Capping	4-12
25	4.2.4.1 Description	4-12
26	4.2.4.2 Evaluation	4-13
27	4.2.5 Alternative B5: Groundwater Extraction with On-Site Treatment via Carbon Adsorption	4-13
28	4.2.5.1 Description	4-13
29	4.2.5.2 Evaluation	4-14
30	4.2.6 Alternative B6: In Situ Groundwater Bioremediation	4-15
31	4.2.6.1 Description	4-15
32	4.2.6.2 Evaluation	4-15
33	4.2.7 Selection of UST 13 Alternatives for Detailed Analysis	4-16
34		
35	4.3 POL STORAGE AREA/DRMO YARD GROUNDWATER OPERABLE UNIT ALTERNATIVES	4-16
36		
37	4.3.1 Alternative C1: No Further Action	4-16
38	4.3.1.1 Description	4-16
39	4.3.1.2 Evaluation	4-17
40	4.3.2 Alternative C2: Institutional Actions	4-17
41		
42		

Table of Contents (Cont.)

<u>Section</u>		<u>Page</u>
1	4.3.2.1 Description	4-17
2	4.3.2.2 Evaluation	4-18
3	4.3.3 Alternative C3: Intrinsic Remediation (With Long-Term	
4	Monitoring)	4-18
5	4.3.3.1 Description	4-18
6	4.3.3.2 Evaluation	4-19
7	4.3.4 Selection of POL Storage Area/DRMO Yard	
8	Groundwater	4-20
9		
10	5 DETAILED ANALYSIS OF REMEDIAL ALTERNATIVES	
11	AND MONITORING	5-1
12	5.1 DRMO SOILS OPERABLE UNIT (AOC 32)	5-2
13	5.1.1 Alternative A1: No Further Action	5-2
14	5.1.1.1 Detailed Description	5-2
15	5.1.1.2 Criteria Analysis	5-3
16	5.1.2 Alternative A2: Institutional Actions	5-4
17	5.1.2.1 Detailed Description	5-4
18	5.1.2.2 Criteria Analysis	5-5
19	5.1.3 Alternative A3: Containment via Capping	5-6
20	5.1.3.1 Detailed Description	5-6
21	5.1.3.2 Criteria Analysis	5-8
22	5.1.4 Alternative A4: Excavation, Solidification,	
23	and On-Site Disposal	5-10
24	5.1.4.1 Detailed Description	5-10
25	5.1.4.2 Criteria Analysis	5-13
26	5.1.5 Alternative A6: Excavation and Off-Site Disposal ..	5-15
27	5.1.5.1 Detailed Description	5-15
28	5.1.5.2 Criteria Analysis	5-15
29	5.1.6 Comparative Analysis of Alternatives	5-17
30	5.2 UST 13 GROUNDWATER OPERABLE UNIT (AOC 32) ..	5-19
31	5.2.1 Alternative B1: No Further Action	5-19
32	5.2.1.1 Detailed Description	5-19
33	5.2.1.2 Criteria Analysis	5-19
34	5.2.2 Alternative B2: Institutional Actions	5-21
35	5.2.2.1 Detailed Description	5-21
36	5.2.2.2 Criteria Analysis	5-21
37	5.2.3 Alternative B3: Intrinsic Remediation (with	
38	long-term monitoring)	5-22
39	5.2.3.1 Detailed Description	5-22
40	5.2.3.2 Criteria Analysis	5-23
41	5.2.4 Comparative Analysis of Alternatives	5-24

Feasibility Study: Fort Devens FA II
Section No.: Table of Contents
Revision No.: 2
Date: January 1997

Table of Contents (Cont.)

<u>Section</u>		<u>Page</u>
1	5.3 POL STORAGE AREA/DRMO YARD GROUNDWATER	
2	OPERABLE UNIT (AOC 32, 43A)	5-24
3	5.3.1 Alternative C1: No Further Action	5-25
4	5.3.1.1 Detailed Description	5-25
5	5.3.1.2 Criteria Analysis	5-25
6	5.3.2 Alternative C2: Institutional Actions	5-26
7	5.3.2.1 Detailed Description	5-26
8	5.3.2.2 Criteria Analysis	5-27
9	5.3.3 Alternative C3: Intrinsic Remediation (with	
10	long-term monitoring)	5-28
11	5.3.3.1 Detailed Description	5-28
12	5.3.3.2 Criteria Analysis	5-29
13	5.3.4 Comparative Analysis of Alternatives	5-30
14		
15	6 REFERENCES	6-1
16		
17		
18	APPENDIX A PARTICLE TRACKING SIMULATION RESULT FOR	
19	FORT DEVENS MAIN POST: FROM POL STORAGE YARD	
20	TO THE MACPHERSON WELL (PERFORMED BY	
21	ENGINEERING TECHNOLOGIES ASSOCIATES, INC.) . . .	A-1
22		
23	APPENDIX B BACK-UP COST CALCULATIONS	B-1
24		
25	APPENDIX C RESPONSE TO COMMENTS RECEIVED ON THE	
26	DRAFT AND FINAL FEASIBILITY STUDY	C-1
27		

1
2
3

4 **LIST OF TABLES**
5
6
7

8	<u>Table</u>	<u>Page</u>
9	2-1 Main Post Soil Cleanup Goal Determination	2-23
10	2-2 Main Post Groundwater Cleanup Goal Determination	2-25
11	2-3 Main Post Surface Water Cleanup Goal Determination	2-29
12	2-4 Location-Specific Applicable or Relevant and Appropriate Requirements for RI Sites at Fort Devens	2-31
13	3-1 Summary of Remedial Technologies for Soils	3-21
14	3-2 Summary of Remedial Technologies for Groundwater	3-23
15	4-1 Results of Screening of Alternatives	4-21
16	5-1 Detailed Analysis of Alternatives for DRMO Yard Soils Operable Unit	5-35
17	5-2 DRMO Yard Soils, Alternative A1: No Further Action Costs	5-39
18	5-3 DRMO Yard Soils, Alternative A2: Institutional Actions Costs	5-41
19	5-4 DRMO Yard Soils, Alternative A3: Containment via Capping Costs	5-43
20	5-5 DRMO Yard Soils, Alternative A4: Excavation, Solidification, and On-Site Disposal	5-45
21	5-6 DRMO Yard Soils, Alternative A6: Excavation and Off-Site Disposal	5-47
22	5-7 DRMO Yard Soils, Alternative Cost Summary	5-49
23	5-8 UST-13 Groundwater Cost Summary, Alternative B1: No Further Action	5-51
24	5-9 UST-13 Groundwater Cost Summary, Alternative B2: Institutional Actions	5-53

Feasibility Study: Fort Devens FA II
Section No.: List of Tables
Revision No.: 2
Date: January 1997

List of Tables (Cont.)

	<u>Table</u>	<u>Page</u>
1	5-10 UST-13 Groundwater Cost Summary, Alternative B3: 2 Intrinsic Remediation	5-55
3	5-11 POL Storage Area/DRMO Yard Groundwater Cost Summary, 4 Alternative C1: No Further Action	5-57
5	5-12 POL Storage Area/DRMO Yard Groundwater Cost Summary, 6 Alternative C2: Institutional Controls	5-59
7	5-13 POL Storage Area/DRMO Yard Groundwater Cost Summary, 8 Alternative C3: Intrinsic Remediation	5-61
9	5-14 ARARs and TBCs for Soils Remedial Alternatives (DRMO Yard)	5-63
10	5-15 Federal and State ARARs for AOCs 32 and 43A, POL Storage Area/ 11 DRMO Yard Groundwater	5-65
12		
13		
14		
15		
16		
17		

1
2
3
4
5
6
7
Feasibility Study: Fort Devens FA II
Section No.: List of Illustrations
Revision No.: 2
Date: January 1997

8
9
10
11
12
13
14
15
16
17
18
19
20
21
22
23
24
25
26
27
28
LIST OF ILLUSTRATIONS

<u>Figure</u>		<u>Page</u>
1-1	Location of Fort Devens in Massachusetts	1-27
1-2	Location of Functional Area II Sites	1-29
1-3	Site Map of AOC 32 (DRMO Yard)	1-31
1-4	Site Map of AOC 43A (POL Storage Area)	1-33
2-1	Generalized Approach to Selecting Cleanup Goals	2-17
2-2	Detections Above Cleanup Goals at DRMO Yard	2-19
2-3	Proposed Surface Soil Remediation Areas at DRMO Yard	2-21
5-1	Alternative A3: Areas of Excavation and Cap	5-31
5-2	Alternatives A4 and A6: Areas of Excavation	5-33

1
2
3 **LIST OF ACRONYMS AND ABBREVIATIONS**
4
5
6

7	AOC	Area of Contamination
8	APEG	A combination of alkaline earth metal hydroxides and polyethylene glycol
9	ARAR	Applicable or Relevant and Appropriate Requirement
10	AST	Above Ground Storage Tank
11	BCD	Base-Catalyzed Dechlorination
12	BGS	Below Ground Surface
13	BNA	base/neutral and acid extractable organic compounds
14	BTEX	Benzene, Toluene, Ethylbenzene, and Xylene
15	CERCLA	Comprehensive Environmental Response, Compensation, and Liability Act
16	CMR	Code of Massachusetts Regulations
17	COPC	Contaminant of Potential Concern
18	CWA	Clean Water Act
19	DDD	dichlorodiphenyldichloroethane
20	DDE	dichlorodiphenyldichloroethylene
21	DDT	dichlorodiphenyltrichloroethane
22	DNB	Dinitrobenzene
23	DNT	Dinitrotoluene
24	DOI	United States Department of the Interior
25	DRMO	Defense Reutilization and Marketing Office
26	E & E	Ecology and Environment, Inc.
27	EF	Exposure Frequency
28	EMO	Environmental Management Office
29	EPA	United States Environmental Protection Agency
30	FS	Feasibility Study
31	HA	Health Advisory
32	HDPE	High Density Polyethylene
33	HEAST	Health Effects Assessment Summary Tables
34	HI	Hazard Index
35	HMX	cyclotetramethylene tetranitramine
36	IEUBK	integrated exposure uptake biokinetic model
37	LDR	Land Disposal Restriction
38	MA SMCLs	Massachusetts Secondary Maximum Contaminant Levels
39	MCL	Maximum Contaminant Level
40	MCLG	Maximum Contaminant Level Goal
41	MCP	Massachusetts Contingency Plan
42	MDEP	Massachusetts Department of Environmental Protection
43	MGL	Massachusetts General Law
44	MMCL	Massachusetts Maximum Contaminant Level
45	MNHESP	Massachusetts Natural Heritage and Endangered Species Program
46	NCP	National Oil and Hazardous Substances Pollution Contingency Plan

1	NPDES	National Pollutant Discharge Elimination System
2	O&M	Operation and Maintenance
3	ORSG	Office of Research and Standards Guidelines
4	OSHA	Occupational Safety and Health Administration
5	OSWER	Office of Solid Waste and Emergency Response
6	PAH	Polynuclear Aromatic Hydrocarbon
7	PCB	Polychlorinated Biphenyl
8	PETN	Pentaerythritol Tetranitrate
9	POL	Petroleum, Oil, and Lubricant
10	POTW	Publicly-Owned Treatment Works
11	PPE	Personal Protection Equipment
12	QA/QC	Quality Assurance/Quality Control
13	RAO	Remedial Action Objectives
14	RBC	Risk-based Concentrations
15	RCRA	Resource Conservation and Recovery Act
16	RF	Radio Frequency
17	RfD	Reference dose
18	RI	Remedial Investigation
19	RI/FS	Remedial Investigation/Feasibility Study
20	RME	Reasonable Maximum Exposure
21	ROD	Record of Decision
22	SARA	Superfund Amendments and Reauthorization Act of 1986
23	SDWA	Safe Drinking Water Act
24	SI	Site Investigation
25	SMCLs	Secondary Maximum Contaminant Levels
26	TAL	Target Analyte List
27	TBC	To Be Considered
28	TCE	trichloroethene
29	TCL	Target Compound List
30	TCLP	Toxicity Characteristic Leaching Procedure
31	TMV	Toxicity, Mobility, or Volume
32	TNB	Trinitrobenzene
33	TOC	Total Organic Carbon
34	TPHC	Total Petroleum Hydrocarbons
35	TSCA	Toxic Substances Control Act
36	TSS	Total Suspended Solids
37	UCL	Upper Control Limit
38	USAEC	United States Army Environmental Center (formerly USATHAMA)
39	USDOD	United States Department of Defense
40	UST	Underground Storage Tank
41	UV	Ultraviolet
42	VOC	Volatile Organic Compound
43	WQC	Water Quality Control
44		

1

2

3

UNITS OF MEASURE

4

5

6	°C	degree(s) Celsius
7	cfs	cubic feet per second
8	cm	centimeter(s)
9	cm/sec	centimeters per second
10	°F	degree(s) Fahrenheit
11	ft	foot (feet)
12	ft ²	square foot (feet)
13	ft ³	cubic foot (feet)
14	g	gram(s)
15	gal	gallon(s)
16	gpm	gallons per minute
17	kg	kilogram
18	L	liter(s)
19	m	meter(s)
20	mg	milligram(s)
21	mi	mile(s)
22	µg	microgram(s)
23	µm	micrometer
24	ppb	part(s) per billion
25	ppm	part(s) per million
26	ton	short ton(s) (i.e., 2,000 pounds)
27	yd ³	cubic yard(s)

28

EXECUTIVE SUMMARY

Under contract with the United States Army Environmental Center (USAEC), Ecology and Environment, Inc. (E & E) conducted this Feasibility Study (FS) for two Areas of Contamination (AOCs) at Fort Devens, Massachusetts: AOC 32 and AOC 43A. These AOCs are in Functional Area II, the Main Post. This FS is intended to identify and establish cleanup objectives for contaminated media, to evaluate and refine a list of alternative technologies that are being considered to remediate the contaminated sites, and to analyze in detail a short list of feasible alternatives.

E & E conducted a Remedial Investigation (RI) of AOCs 32 and 43A and collected samples of environmental media to characterize the sites and to support ecological and human health risk assessments. Future use of the AOCs in Functional Area II (the Main Post) is expected to be of an industrial nature, similar to the current use of the sites. These expected uses were considered when the risk assessments for Functional Area II were developed.

As part of this FS, remedial action objectives were formulated for the contaminated soils and groundwater in Functional Area II. Cleanup goals were developed based on an evaluation of applicable or relevant and appropriate requirements (ARARs), other criteria and guidelines to be considered (TBCs), findings of the site-specific baseline risk assessment and ecological assessment, and background data compiled from Fort Devens. Several distinct areas within the AOCs, were identified that exceeded cleanup goals.

At the Defense Reutilization and Marketing Office (DRMO) underground storage tank (UST) area, the groundwater was found to be contaminated with petroleum hydrocarbons, chlorobenzenes, chlorinated ethylenes, and several other organics. The soil near the UST contained one sample of elevated lead and one of elevated arsenic. However, soils have since been removed. In the soil surrounding the DRMO Yard, the following contaminants were detected at levels above their cleanup goals: arsenic, cadmium, lead, pesticides, polychlorinated biphenyls (PCBs), and total petroleum hydrocarbons (TPHC). Groundwater at the DRMO Yard exceeded cleanup goals for manganese and TCE. However, manganese, which was highest in an upgradient well, is clearly natural, and TCE, which was not found in wells immediately downgradient of DRMO, is clearly of very limited extent. TCE levels in the groundwater are close to drinking water standards but groundwater is proposed as an operable unit.

In the groundwater and saturated soil of the Petroleum, Oil, and Lubricant (POL) Storage Area, RI screening data suggested the presence of three distinct hydrocarbon plumes in subsurface soils (below 16 feet from ground surface). Although screening samples analyzed for benzene, toluene, ethylbenzene, and xylene (BTEX) compounds showed concentrations of all four aromatics above cleanup goals, confirmation sampling of soils and groundwater did not confirm any exceedances of cleanup goals for these compounds. TPHC and 2-methylnaphthalene levels exceeded regulatory levels in both the soil and groundwater.

1 These exceedances were sporadic and isolated and because of their location they represent no
2 threat to human health or the environment at present. This was confirmed by contaminant
3 transport modeling for the zone of capture of the McPherson well. Except for one isolated
4 occurrence of arsenic in surface soil, attributed to natural variation, no soil sample exceeded
5 screening values where exposures to any population can occur. Remediation is proposed for
6 the POL site groundwater because of exceedances of ARARs and the need to confirm that
7 intrinsic remediation will result in reductions of human health risks to acceptable levels.

8 General response actions were developed for soil (at the DRMO Yard) and
9 groundwater (at both the POL and the DRMO Yard). For soil the general response actions
10 are: no further action, institutional action, containment, excavation, ex situ treatment, in situ
11 treatment, and disposal. For groundwater the general response actions are: no further action,
12 institutional action, intrinsic remediation (with long-term monitoring), containment, extraction,
13 ex situ treatment, in situ treatment, and disposal.

14 Within each general response action, there are several technologies that address the
15 remedial action objectives. The technologies are screened based on applicability to the wastes
16 present in a given medium, effectiveness, and implementability. Technologies that passed this
17 screening were then assembled into complete remedial alternatives. These complete alterna-
18 tives are then screened again based on effectiveness and implementability. The alternatives
19 that passed this screening are developed and analyzed further in the detailed analysis section.

20 Remedial alternatives were developed for each of three operable units: the DRMO
21 Yard soils, the DRMO UST 13 groundwater, and the POL Storage Area/DRMO Yard
22 groundwater. Five alternatives are analyzed in detail for DRMO Yard soils:

23

- 24 • No Further Action;
- 25 • Institutional Actions;
- 26 • Containment with Capping;
- 27 • Excavation, Solidification, and On-Site Disposal; and
- 28 • Excavation and Off-Site Disposal.

29 Three alternatives are analyzed in detail for DRMO UST 13 groundwater and the POL
30 Storage Area/DRMO Yard groundwater:

31

- 32 • No Further Action;
- 33 • Institutional Actions; and
- 34 • Intrinsic Remediation (with long-term monitoring).

1 Feasibility Study: Fort Devens FA II
2 Section No.: 1
3 Revision No.: 2
4 Date: January 1997

1
2
3 **1. INTRODUCTION**
4
5

6 **1.1 PURPOSE AND ORGANIZATION OF REPORT**
7

8 The United States Army Environmental Center (USAEC) tasked Ecology and
9 Environment, Inc. (E & E) to conduct a Remedial Investigation/Feasibility Study (RI/FS) at
10 two areas of contamination (AOCs) at Fort Devens, Massachusetts (Figure 1-1), under
11 Contract No. DAAA15-90-D-0012, Delivery Order No. 0003. The two sites are located
12 within Functional Area II (the Main Post), which includes AOC 32, the Defense Reutilization
13 and Marketing Office (DRMO) Yard; and AOC 43A, the Petroleum, Oil, and Lubricant
14 (POL) Storage Area (Figure 1-2). This work was performed in accordance with the Federal
15 Facility Agreement (Inter-Agency Agreement) between the United States Army and the United
16 States Environmental Protection Agency (EPA) under Section 120 of the Comprehensive
17 Environmental Response, Compensation, and Liability Act (CERCLA) as amended by the
18 Superfund Amendments and Reauthorization Act (SARA).
19

20 The detailed results of the RI conducted at these sites are documented in the Remedial
21 Investigation Report for Functional Area II (E & E 1994). The RI results, including human
22 health and ecological risk assessment, were used in preparing this FS. The FS is conducted
23 in accordance with the EPA's *Guidance for Conducting Remedial Investigations and*
24 *Feasibility Studies under CERCLA* (EPA 1988b). In accordance with the Federal Facility
25 Agreement for Fort Devens, the FS report has been prepared in three stages. The first stage
26 was the Draft Initial Screening of Alternatives, and included the development and screening of
27 remedial alternatives. The second submittal was the Detailed Analysis of Alternatives report.
28 The third stage is this FS report, which incorporates the final versions of the Initial Screening
29 of Alternatives and the Detailed Analyses of Alternatives documents.
30

31 This FS report includes six sections and three Appendices. Section 1 provides a brief
32 site description and history, a summary of the nature and extent of contamination, and
33 summaries of the human health and ecological risk assessments from the RI report. Section 2
34 defines the remedial action objectives for each of the sites, and develops clean-up goals for
35 each site included in the FS process. The identification and screening of technologies are
36 presented in Section 3 and alternatives to remediate each site are developed in Section 4.
37 Section 5 presents a more detailed analysis of the alternatives that are retained in Section 4.
38 References cited or consulted are provided in Section 6. A particle tracking analysis for the
39 groundwater flow system of the POL Storage Area is provided in Appendix A. Appendices B
40 and C contain the back-up cost calculations used for the detailed analysis of alternatives and
41 responses to comments on the draft FS, respectively.
42

43 **1.2 SITE DESCRIPTIONS**
44

45 This section presents brief discussions of site descriptions including site geology and
46 the nature and extent of contamination found, as well as summaries of the human health and

Feasibility Study: Fort Devens FA II
Section No.: 1
Revision No.: 2
Date: January 1997

1 ecological risk assessments for the two sites on the Main Post identified for inclusion in the
2 FS process.

3
4 **1.2.1 Defense Reutilization and Marketing Office (DRMO) Yard - (AOC 32)**

5 **1.2.1.1 Site Description**

6
7 AOC 32, the DRMO Yard, is located in the northeast corner of the Main Post at Fort
8 Devens, just to the south of Shepley's Hill Landfill. AOC 43A, the POL Storage Area, is
9 just to the south of the DRMO Yard site, across Market Street (see Figure 1-2). The DRMO
10 Yard consists of two fenced enclosures on either side of Cook Street, which serves as the
11 access road to the Shepley's Hill Landfill. The two enclosed areas are paved with asphalt.
12 Together the paved surface totals approximately 250,000 square feet (see Figure 1-3). Also
13 associated with AOC 32 is a 30,000 square foot fenced area used to store and recycle used
14 tires. This unpaved yard is located immediately north of the eastern DRMO Yard.
15

16
17 The DRMO Yard is an active materials storage facility, and has been operational in
18 its current location for several decades. The yard on the west side of Cook Street contained
19 various types of used equipment. The northwest corner of the yard was dedicated to used
20 lead-acid battery storage. All battery acid was drained from the batteries by the generator
21 prior to arrival. Batteries were stacked on pallets, with the top of the battery turned sideways
22 to avoid any accumulation of precipitation. About 40,000 pounds of batteries passed through
23 the DRMO per month. The nature of the material that is processed in this yard varies
24 considerably. As Fort Devens continues to move toward closure and elements of the tenant
25 commands are either deactivated or transferred to new installations, the DRMO Yard will
26 receive more office and administrative equipment.
27

28
29 In the yard on the east side of Cook Street, vehicles were cut-up and disassembled to
30 recover usable parts. This yard formerly contained scrap metal, tires, stored items that are
31 ready for sale, and was the accumulation point for used photographic solution. The recovery
32 of scrap precious metals (silver and platinum) from the solution was performed by a
33 subcontractor off site (Berry 1988). Because of the history of vehicle scrap, a radiation
34 survey was performed by ABB Environmental Services, Inc. (ABB), primarily to find radium
35 dials. The Army identified three "affected" areas: the tire recycling yard, the north portion
36 of the east yard, and the combined area of a 12 meter by 31 meter concrete pad east of
Building T204, with a 10 meter wide perimeter around the pad.
37

38
39 One hundred percent of the "affected" areas was scanned using a sodium iodide
40 detector, and 10 percent of the remainder of the DRMO Yard was scanned as well.
41 Measurements of total alpha and total beta/gamma surface activity were made at all locations
42 showing elevated count rates (hot spots), and soil samples were collected and analyzed to
43 determine Radium-226 levels in both background soils and unpaved areas of the yards.
44 Twelve hot spots were found; all were in the north end of the east yard and all were
45 remediated by the removal of radium contaminated soil or radium dials (ABB 1996). Just
46 north of the east yard is a fenced area that is used to hold used tires. Tires are accumulated
over a period of time and then when the quantity is sufficient, the DRMO shreds them and

Feasibility Study: Fort Devens FA II
Section No.: 1
Revision No.: 2
Date: January 1997

ships out the shredded material. In the east yard, there is an excavation trench which was reported to be part of the remediation of a polychlorinated biphenyl (PCB) contaminated rectifier oil spill that was reported to the Environmental Management Office (EMO) by DRMO personnel on 5 April 1990. In 1992, an underground storage tank (UST) used for the storage of waste oil was removed from a location just to the east of the DRMO Yard.

The enclosure for the two sections of the DRMO Yard and the tire storage area consists of a 6-foot tall chain-link fence, surmounted with barbed wire. The paved asphalt surfaces of the two main yards drain to the north into a 36-inch storm drain, with a catch basin just to the north of the eastern yard and two catch basins located in the separately fenced tire recycling area. The storm drain extends southeast along the edge of Shepley's Hill Landfill, and discharges via a 48-inch pipe to a man-made drainage ditch. The drainage ditch carries storm runoff north towards Plow Shop Pond.

Overall, this site does not support an abundance or diversity of wildlife species. However, a few species-of-concern, including the grasshopper sparrow, upland sandpiper, Cooper's hawk, and bald eagle, have been known to occur on the grassland habitat adjacent to the study area (i.e., on Shepley's Hill Landfill). An additional 12 state- and federally-listed species of concern are known to occur within 1.5 miles of the site, but none were observed during the field survey. One area located within 1.5 miles of the site is identified as an estimated habitat of state-listed rare wetlands wildlife by the Massachusetts Natural Heritage and Endangered Species Program (MNHESP 1993); it is located approximately 3,000 feet north of the site, adjacent to Nonacoicus Brook.

1.2.1.2 Geology and Hydrology

The DRMO Yard area is fairly level. The soil layer in the area is thin, and the soils are sandy and well drained. Bedrock beneath the site is Ayer's granite (granodiorite). The site lies within a north-northeast trending terrace fragment that connects the entrance to Shepley's Hill Landfill with the POL Storage Area, and lies between Shepley's Hill to the west and other bedrock outcrops to the east and southeast. Borings at the DRMO Yard show bedrock becoming shallower to the north and east. Under the DRMO Yard, bedrock ranges from 10 to 30 feet below ground surface (BGS).

Groundwater was encountered from 12.7 to 28 feet BGS at the DRMO Yard as measured in November 1993. It is probable that there is no permanent aquifer in some of the unconsolidated deposits above bedrock at the DRMO Yard, both because the soil is thin and well drained and because it is near a watershed divide between the Willow Creek drainage to the west and Plow Shop Pond to the east. Bedrock topography is the major influence on groundwater hydrology. An east-west groundwater divide is present at the north end of the DRMO Yard. North of the divide, flow is to the northeast towards Shepley's Hill Landfill; south of the divide, flow is to the south and west, through the POL Storage Area. The hydraulic gradient is also directly related to bedrock topography. Another groundwater divide runs under Building T204, running north-south. The UST area, which is east of Building T204, is in a separate groundwater regime from the DRMO Yard itself. The water table is in the bedrock under the former UST, and the hydraulic conductivity is low. Flow appears to

1 be both easterly and southerly around a small knob of bedrock just east of the UST site (near
2 location of well 32M-92-05X).

3 **1.2.1.3 Nature and Extent of Contamination**

4 During the RI, screening values were compiled by E & E for each analyte for
5 comparison against sampling results. Most screening values were based on chemical-specific
6 applicable or relevant and appropriate requirements (ARARs) identified for this project by
7 Oak Ridge National Laboratories, although where no ARARs existed, other levels to be
8 considered (TBCs) were used. E & E developed a set of numerical criteria, entered the
9 values into the Site Master Database, and ran a comparison of analytical results for each
10 medium against the screening values. Screening values are not intended to be cleanup goals,
11 i.e. goals used to identify areas requiring remediation. These are developed in Section 2 of
12 the FS. Screening values are merely used to identify areas where contamination may exceed
13 regulatory levels and to assist in the nature and extent of contamination discussions.

14 A detailed discussion of the ARAR selection process and the development of
15 screening values can be found in Section 7 of Volumes II and III of the Functional Area II RI
16 report (E & E 1994). A summary of ARARs by medium is provided here:

- 17 • Soils: Massachusetts Contingency Plan (MCP) Method I was identi-
18 fied by Oak Ridge National Laboratories as an ARAR, and was used
19 for the screening values of contaminants in soil. Where no values
20 existed, the EPA Region III risk-based concentrations (RBCs) for
21 commercial/industrial soils were used as screening values. For lead,
22 the EPA Interim Guidance on Soil Lead Cleanup levels at Superfund
23 sites was used.
- 24 • Sediment: There are no promulgated maximum allowable concentra-
25 tions for chemicals in sediments under Massachusetts or Federal
26 Law. Therefore, results were compared to screening values devel-
27 oped for soils.
- 28 • Surface Water: From surface water, the lowest of two levels identi-
29 fied in the Clean Water Act (CWA) Ambient Water Quality Criteria
30 (AWQC) was chosen: one for the protection of human health from
31 risks due to water and fish consumption, and a second for the protec-
32 tion of aquatic organisms in freshwater due to chronic effects. The
33 AWQC criteria were identified as ARARs by Oak Ridge National
34 Laboratory.
- 35 • Groundwater: Screening values in groundwater were based on the
36 lowest of the following criteria: Safe Drinking Water Act (SDWA)
37 Maximum Contaminant Levels (MCLs), the Massachusetts MCL
38 (MMCL), MCP GW-1 water standards, the SDWA MCL Goal
39 (MCLG) and Massachusetts Secondary MCL (SMCL). All were

Feasibility Study: Fort Devens FA II
Section No.: 1
Revision No.: 2
Date: January 1997

1 identified as chemical specific ARARs by Oak Ridge. Where no
2 ARAR existed, SDWA SMCLs, EPA Office of Water Lifetime
3 Health Advisories (HA), and Massachusetts Office of Research and
4 Standards Guidelines (ORSG) were reviewed. Although these
5 standards are only TBC guidance, the lowest value was selected.
6

7 Surface Soils

8

9 A total of 20 surface soil samples were collected in the AOC 32 area. Samples were
10 analyzed for target analyte list (TAL) metals, target compound list (TCL) pesticides/PCBs,
11 and total petroleum hydrocarbons (TPHC). A large number of inorganics were detected at
12 levels above background in the soils, including the following metals of significance:
13 antimony, arsenic, barium, beryllium, cadmium, chromium, cobalt, copper, iron, lead,
14 mercury, nickel, silver, vanadium, and zinc. The RI report identifies cadmium, lead, and
15 beryllium as exceeding various standards. Although cadmium does not exceed the screening
16 value used in the RI report, it is quite elevated in two samples. Lead exceeds the screening
17 value in seven samples. Beryllium does not exceed the screening value used in the RI report.
18 Arsenic exceeded its screening value in two samples, mercury exceeded its screening value
19 once, and nickel also exceeded its screening value in one sample.
20

21 The pesticide dichlorodiphenyltrichloroethane (DDT), and its derivatives
22 dichlorodiphenyldichloroethylene (DDE) and dichlorodiphenyldichloroethane (DDD), were
23 detected in AOC 32 soils, particularly around the perimeter of the east yard. DDD and DDE
24 were detected in approximately half of the samples, but all below screening values. Gamma-
25 Chlordane was also detected below its screening value. Three PCBs (PCB-1016, PCB-1254,
26 and PCB-1260) were detected, sometimes exceeding screening values. PCB-1016 was
27 detected in five of the samples, PCB-1254 in seven samples, and PCB-1260 in 10 samples.
28 TPHCs were detected in all but two of the soil samples. Six of the samples exceeded the
29 screening value. These samples are all from around the perimeter of the east DRMO Yard
30 and in the tire recycling area.
31

32 To summarize, the soils surrounding AOC 32 show some contamination with
33 petroleum hydrocarbons, heavy metals, PCBs, and pesticides. The pesticide levels are very
34 low, except for two DDT hits. All are below screening values. DDT is detected throughout
35 the site, particularly in areas near roads and buildings. Therefore, the DDT contamination at
36 AOC 32 may or may not be site-related. The hits of TPHC, metals, and PCBs are very
37 likely related both to each other, and to site-usage. The higher detections of these compounds
38 are found in the same five samples, all around the east DRMO Yard and tire recycling area.
39 These locations are all possible drainage points for the asphalt-covered east yard. It appears
40 likely that the contaminated soil is due to site drainage, perhaps from oil laden with heavy
41 metals and PCBs. This northeast portion of the east yard is also the area where PCB oils
42 were spilled from stored rectifiers.
43

Feasibility Study: Fort Devens FA II
Section No.: 1
Revision No.: 2
Date: January 1997

1 **Subsurface Soils**
2

3 Boreholes were advanced at 15 locations during the RI. Samples were taken at 1
4 foot, 5 feet, and 10 feet, except for one borehole, which was sampled at the surface instead of
5 the 1 foot depth because that location is unpaved. Borehole samples were analyzed for TAL
6 metals, TCL pesticides/PCBs, and TPHC. Three test pits were excavated in the removed
7 UST area east of AOC 32 and were sampled at approximately 6 feet. Subsurface samples
8 from the test pits were analyzed for TAL metals, TCL pesticides/PCBs, TCL volatile organic
9 compounds (VOCs), and TPHC. A large number of metals were detected in the 1-foot,
10 5-foot, and even 10-foot samples, although with decreasing frequency at greater depths,
11 including: antimony, arsenic, barium, beryllium, cadmium, chromium, cobalt, copper, lead,
12 mercury, nickel, silver, and zinc. Lead exceeded the screening value level for subsurface soil
13 at the 1-foot depth in two boreholes. The arsenic screening value level was exceeded at the 5-
14 foot depth in one borehole, and at the 10-foot depth in a second borehole. Two of the test
15 pits showed elevated metals. Arsenic exceeded a screening value in one sample. Lead
16 exceeded a screening value in one test pit. The high lead level in this sample corresponded to
17 a high level of TPHC.

18 No organics at any depth exceeded screening value levels for subsurface soil.
19 However, at one borehole, elevated levels of DDD, DDE, and DDT were detected at 1 foot.
20 TPHC was elevated in five boreholes. In general, there does not appear to be significant
21 contamination in the subsurface soils at AOC 32, with one exception. One borehole showed
22 elevated levels of almost every metal, as well as elevated pesticide and TPHC hits at 1 foot.
23 This may be due to the boring's location, adjacent to the area where PCB-laden oil was
24 spilled into the soil, and then later excavated (E & E 1992). This is particularly likely,
25 because the 1-foot samples in this borehole and a nearby borehole showed PCBs. The other
26 sporadic elevated levels of TPHC and metals are probably the cumulative result of very
27 localized incidents at the DRMO Yard. In the test pits near the UST, the high lead level
28 could be related to the elevated TPHC.
29

30 **Asphalt Samples**
31

32 A total of 15 asphalt samples were taken at AOC 32. These samples were analyzed
33 for pesticides and PCBs and compared to soil screening values. Low levels of p,p-DDE and
34 p,p-DDT were found in 8 of the 15 samples. The higher levels of pesticides were found in
35 the center of the DRMO Yard, and roughly correlated to higher levels of PCBs detected. No
36 pesticides were detected above screening values. PCBs were found in the 12 asphalt samples
37 taken in the east DRMO Yard. PCB-1254 was the most prevalent, detected in 9 of the 12
38 samples, and exceeding its screening value in 4 samples. PCB-1248 was detected in three
39 samples. PCB-1260 was detected in two samples. Based on the PCB hits, the soil
40 contamination at the DRMO Yard, and the history of site usage, it appears that there may be
41 some site-related PCB contamination in the asphalt, particularly because some of the PCB hits
42 are found in the area of the known rectifier oil spill.
43

1 **Groundwater**
2

3 Groundwater samples were collected in three rounds in November 1992, March 1993,
4 and June 1993. The samples from the first two rounds were analyzed for TCL organics, TAL
5 metals, TPHC, and hardness, with several samples also analyzed for dissolved TAL metals.
6 Samples from the third round were analyzed for both total and dissolved (i.e., filtered) TAL
7 metals, explosives, and hardness. Because of the content of silt and clay in the water from all
8 of the DRMO Yard wells, which are only bailed and sampled at long intervals (three months
9 or more), the metals levels in unfiltered samples frequently exceed screening values. To
10 distinguish those metals levels from the levels of metals dissolved in groundwater or on
11 colloidal particles, additional samples were taken in the June 1993 round, and filtered through
12 0.45 micron glass filters. In all cases, the non-soluble metals such as aluminum and iron are
13 dramatically reduced, while soluble metals such as sodium are little affected. Toxic heavy
14 metals such as arsenic, cadmium, chromium, and copper, often correlate with levels of
15 aluminum and iron, suggesting that the heavy metals may be present in suspended sediment or
16 may be sorbed onto aluminum or iron oxides.

17
18 All the wells in the DRMO Yard tend to show aluminum, iron, and manganese in
19 unfiltered samples. Where there are high levels of iron and aluminum, there are also likely to
20 be high levels of other metals associated with particulates in the groundwater. Metals whose
21 maximum levels exceed MCLs are: arsenic, beryllium, chromium, lead, sodium, and nickel.
22 Sodium is obviously high in one monitoring well because of its proximity to sources of runoff
23 carrying road salt. The fact that all the other metals are highest in the two wells showing
24 highest aluminum and iron is indicative of the role that particulates play in affecting
25 groundwater quality data with respect to many metals. When the filtered samples from the
26 same wells are reviewed, sodium is still high in the one monitoring well because it is highly
27 soluble as sodium chloride. In addition, the following exceedances of MCLs for other
28 dissolved metals were noted in several wells: manganese, aluminum, and iron. Manganese is
29 as high or higher in a filtered sample from the upgradient well as it is in unfiltered samples
30 from the same well, or in unfiltered samples from downgradient wells. It appears that there
31 are high levels of soluble manganese naturally occurring in the groundwater at this site. The
32 maximum level of iron in filtered samples is less than one percent of the average level in
33 three unfiltered samples from the same well. Another filtered sample taken 3 months later
34 shows non-detect for iron. The highest level of aluminum in filtered samples is 392
35 micrograms per liter ($\mu\text{g/L}$). Again, a filtered sample taken three months later shows non-
36 detect for aluminum. Apart from the elevated dissolved manganese which appears to be
37 background, there is no convincing evidence that AOC 32 has any levels of dissolved metals
38 above screening values. Overall, it appears that groundwater quality downgradient of the
39 DRMO Yard has not been impacted by the activities of the DRMO Yard with respect to
40 metals, considering the data from the filtered samples.

41
42 The upgradient well contains several organics, including *bis*(2-ethylhexyl)phthalate, a
43 common contaminant from sample-handling. The same organics do not appear in the wells
44 most directly downgradient of this well, and appear to be local contaminants. The other wells
45 downgradient of AOC 32 show scattered hits from eight organics. These are 6-
46 aminohexanoic acid lactam, dodecanoic acid, di-n-butylphthalate, 1,2-dichloroethane, acetone

Feasibility Study: Fort Devens FA II
Section No.: 1
Revision No.: 2
Date: January 1997

1 and toluene, chloroform, and trichloroethene (TCE). TCE is the only chemical exceeding its
2 screening value, which it does by over 300 percent in one well (POL-3) located immediately
3 downgradient of the DRMO Yard.

4 The three wells placed immediately adjacent to the UST Area excavation site, from
5 which the UST was removed, an additional well placed south of the tank excavation and south
6 of Market Street to monitor potential flow in that direction, and an existing Shepley's Hill
7 Landfill well used to monitor downgradient flow to the east, are considered as one group,
8 separate from the other DRMO Yard wells. They are in a separate groundwater flow system,
9 east of a groundwater divide running north-south under the DRMO office at Building T-204.
10 Inorganics in these wells show the same characteristics as the other wells. Unfiltered samples
11 are typically high in aluminum, iron, and manganese, and show exceedances of MCLs for
12 lead and arsenic. Filtered samples show no exceedances for aluminum, but one well shows
13 exceedances for arsenic and manganese. It appears that the manganese could possibly be
14 natural, given the levels noted in other DRMO wells, but it does not appear in filtered
15 samples from either downgradient well. It appears that both arsenic and manganese could
16 reflect impacts from the former UST; however, these impacts do not appear to extend off site.
17

18 The two wells immediately adjacent to the UST excavation (32M-92-04X and 32M-
19 92-06X) showed high levels of petroleum hydrocarbons greatly exceeding screening values,
20 by nearly 1,000 times, in one case. They also showed a wide range of organics, dominated
21 by dichlorobenzenes, which exceeded screening values. Both showed a variety of other
22 compounds: 13 other organics were found in one well, and 10 other organics were found in
23 the second well. The most marked differences between the two wells were the presence of
24 PCB-1260 and 1,1,1-trichloroethane in 32M-92-04X, and the presence of 1,2-dichloroethene
25 and of TCE (in excess of screening values) in 32M-92-06X. Both wells showed sharp
26 declines in levels of organics between November 1992 and March 1993. However, an
27 additional sampling event conducted in July 1995 showed TPHC concentrations similar to the
28 November 1992 rounds.
29

30 The monitoring well in what appears to be the downgradient direction (32M-92-05X)
31 shows non-detect for both total hydrocarbons and chlorinated benzenes in the first sample
32 round, and only a small hit of total hydrocarbons in the second sample round. Organics
33 detected in the second round include 1,1,1-TCA and 1,2-dichloroethane. The monitoring well
34 south of Market Street showed non-detect for total petroleum hydrocarbons, but a slight trace
35 of 1,1,1-TCA suggesting a connection between this well and the monitoring well to the north.
36 As the data currently exist, only the two wells closest to the tank excavation exceed MCLs,
37 but they both have multiple exceedances which imply the requirement to assess remedial
38 alternatives. The groundwater regime in this area is complex, so the ultimate transport of the
39 organics is difficult to predict. However, it appears that groundwater from west of the UST
40 area flows both to the east and south around a small knob of low conductivity bedrock into
41 which 32M-92-05X was placed. Flow then continues to the east and northeast, toward
42 Shepley's Hill Landfill. This would explain the lack of organics detection in 32M-92-05X.
43 However, the organics also were not detected in SHL-25, which is further east. The waste
44 material spilled at this site was oil containing a number of other contaminants, primarily
45 chlorinated aromatics. These have a much higher solubility in the oil than in water and
46

partition very unequally between the oil and water. Because the oil was apparently spilled at the surface (the oil tank was excavated intact), it had to migrate through the unsaturated sands of the glacial outwash overburden to reach the bedrock. Since the bedrock matrix is essentially impermeable it must have migrated into the fractures in the bedrock in order to reach the water table in the bedrock and to be found in the monitoring wells. The fracture porosity of largely unweathered granodioritic gneiss is of the order of one to five percent, and only the two wells closest (within 20 feet) of the tank excavation showed high levels of TPHC and chlorinated aromatics; it appears clear that only a small area of bedrock was invaded by the waste oil. Because the oil-soaked overburden was excavated and removed at the time of the tank removal, there is now no longer any mass of additional waste oil to move into and replenish the oil in the bedrock. This means that the remaining oily phase in the bedrock must consist of a small volume of material that is not being increased by further movement from the overburden, and is not moving, since it is in residual saturation. Furthermore, the area of contamination is located at a groundwater divide, with little or no natural groundwater flow gradients. This information strongly implies that groundwater contamination is not migrating from the location of the spill.

Surface Water

Because there is no naturally occurring surface water at the DRMO Yard, the only surface water sample taken was from a storm drain catchment basin, north of the east yard. The storm drain discharges to the surface at the drainage ditch and the water seldom, if ever, reaches the end of the ditch leading to Plow Shop Pond. It is likely that all the discharge from the DRMO Yard drain sinks into the very sandy soil and becomes part of the groundwater, except during very exceptional storms, or during snow melt over frozen ground. The surface water sample was analyzed for TAL metals, TCL pesticides/PCBs, and water quality parameters. The one sample collected from the storm drain catch basin showed elevated antimony, cadmium, copper, lead, and zinc, when compared to background surface waters for Fort Devens. Cadmium was detected at 16.2 $\mu\text{g}/\text{L}$, approximately four times the limit of detection (which ranged from 4 to 6 $\mu\text{g}/\text{L}$). The detection limit was assumed to be the upper limit of the background concentration, since cadmium was not detected in background samples. Zinc was detected at eight times the maximum background level.

Sediments

Four sediment samples were collected at AOC 32, two from the storm drain system, and two from the drainage ditch south of Shepley's Hill Landfill, into which the storm drain discharges. The two storm drain sediment samples were from two locations: one from the catchment basin north of the east yard on the east side of Cook Road, and the second from the outlet of the drain where it discharges into the drainage ditch. The catch basin sample was collected in duplicate, and showed numerous exceedances of background levels for metals as well as TPHC and total organic carbon. Metals of particular concern were cadmium and lead. Barium, iron, nickel, and zinc also exceeded background levels on average, as did calcium and potassium, although they are not of concern for human health or the environment. The second sample from the storm drain discharge showed even higher levels of most metals, as well as greatly increased total organic carbon, but identical TPHC. Metals

1 elevated above background included: antimony, barium, cadmium, calcium, chromium,
2 copper, iron, lead, mercury, nickel, potassium, silver, vanadium, and zinc. The levels were
3 higher at the discharge than in the catch basin, apparently as a result of the greatly increased
4 organic carbon of the sediment, onto which the metals are likely to sorb.

5 In the sediment samples taken from the drainage ditch, the following metals are
6 elevated above background: aluminum, antimony, barium, cadmium, calcium, chromium,
7 cobalt, copper, iron, lead, magnesium, nickel, potassium, vanadium, and zinc. The levels are
8 in the same range or higher than those in the storm drain, which probably reflects the high
9 cation exchange capacity of clay in the sediment, which has apparently sorbed metals from the
10 storm drain discharge. It appears that discharge of runoff from the DRMO storm drain has
11 contributed metals to the sediment along the drainage ditch and also metals to the groundwater
12 recharge in this area, since much of the discharge sinks into the ground and recharges
13 groundwater. This, in turn, discharges to Plow Shop Pond. The pesticide/PCB results show
14 hits of DDD, DDT, and PCB-1254 in the storm drain sediments. The ditch sediments
15 showed lindane and DDD. The PCB evidently migrated from the DRMO Yard after a spill of
16 PCB transformer oil, but the low level pesticide hits may reflect general pest control activities
17 around the base in the past.

19 20 21 1.2.1.4 Human Health Risk Assessment Summary

22 The main yards of the DRMO (east and west yards) have been used for storage of
23 used equipment, vehicles, automotive batteries, and containerized hazardous waste, and for
24 the processing and sorting of used parts and scrap metal. Spills from storage yard operations
25 have contaminated the asphalt pavement in the yards and the surrounding surface soils with
26 PCBs and metals, some of which have infiltrated to groundwater. Additionally, subsurface
27 soils and groundwater to the east of the DRMO are contaminated with metals and petroleum
28 constituents, probably by spills around the waste oil underground storage tank that once was
29 located there.

30 31 There are two main exposure pathways under current site conditions.

32 33 34 35 36 37 38 39 40 41 42 43 44 45

- Direct Contact (dermal contact and incidental ingestion) with contaminated asphalt, surface soils, and sediment; and
- Inhalation of vapors released to ambient air at the soil surface.

Potential receptors include DRMO workers and site visitors, both authorized (customers) and unauthorized (trespassers). Normally, inhalation of contaminated dust is not regarded as a major exposure pathway because wind erosion of surface soil at this AOC is limited by pavement and vegetative cover. However, if the cover were removed and soils were excavated (i.e., maintenance of utility lines that run under the site), workers could potentially inhale airborne dust from surface and subsurface soils, and come into direct contact with subsurface contaminants for a short period, probably several days.

1 Under current EPA Superfund Policy (USEPA 1992), acceptable exposure levels for
2 carcinogens are those that represent an excess upper bound lifetime cancer risk of between
3 10^{-4} and 10^{-6} . For noncarcinogens, acceptable exposures are those with a hazard index (HI)
4 of 1.0 or less.

5 The estimated cancer risk to current site workers from exposure to contamination in
6 the asphalt paving and surface soil at AOC 32 is 9.2×10^{-5} for the reasonable maximum
7 exposure (RME) case and 1.8×10^{-5} for the average exposure case, within the EPA range of
8 10^{-4} to 10^{-6} . Estimated cancer risks for site trespassers are approximately an order of
9 magnitude lower, because of their lower exposure frequency (EF). Most of the estimated
10 cancer risk (over 90 percent) is due to dermal absorption and ingestion of PCBs and arsenic in
11 soil. The only HI exceeding 1.0 under current site conditions is associated with the RME
12 case of worker soil exposure; the HI for dermal absorption and ingestion of PCBs is 4.4,
13 while the HI for exposure to lead by these routes is 0.9. Lead and PCBs cause different types
14 of adverse health effects. Therefore, the HIs for exposure to these two chemicals should not
15 be summed. It should be noted that these chemicals do not have EPA-approved reference
16 doses (RfDs), and that these HIs are based on RfDs recommended by the Massachusetts
17 Department of Environmental Protection (MDEP) in its Risk Assessment shortform (MDEP
18 1992).

20 Several alternative exposure scenarios that could occur under possible future site
21 conditions were evaluated. Two scenarios (Scenario 3 — Future Construction Workers and
22 Scenario 4 — Future Site Workers Outdoors) address potential exposure to contaminants in
23 soils by direct contact and by inhalation of ambient air; one scenario (Scenario 5 — Future
24 Site Workers Indoors) addresses potential exposure to volatile groundwater contaminants that
25 could infiltrate to indoor air; and the last scenario (Scenario 6 — Groundwater Usage)
26 addresses potential ingestion of contaminants in groundwater.

27 Future permanent site workers could be exposed to contaminants in both the soil and
28 the groundwater; therefore, the estimated soil and groundwater risks should be summed for
29 this group of potential receptors. However, only one of the two soil exposure scenarios
30 (indoors or outdoors), and one of the five sets of groundwater risk estimates can apply to
31 these receptors at a time. The highest estimated soil risks are for a future outdoor worker,
32 and the highest estimated groundwater risks are for unfiltered groundwater from the DRMO
33 Yard. Combining these risk estimates gives a maximum estimated RME cancer risk of $6 \times$
34 10^{-3} , due almost entirely to the groundwater. When metals data from filtered groundwater
35 samples are used to remove the effects of suspended sediments, estimated cancer risks
36 dropped two orders of magnitude. The highest plausible combined soil and groundwater
37 RME risks for future workers are for outdoor workers using filtered groundwater from the
38 UST area. Any future use of area groundwater as drinking water is unlikely because of the
39 existing public water supply system and the very low yield of wells at the DRMO Yard;
40 therefore, the highest realistic future worker risks are those for outdoor workers from
41 potential exposure to soil contaminants alone.

42 The site contaminants estimated to pose potential excess lifetime cancer risks greater
43 than 10^{-6} include arsenic, beryllium, 1,4-dichlorobenzene, PCBs, and TCE. Arsenic is

1 classified as a Group A, human carcinogen. Beryllium, PCBs, and TCE are classified as
2 Group B2, probable human carcinogens, and 1,4-dichlorobenzene is classified as a Group C,
3 possible human carcinogen, based on carcinogenicity in animals. Site contaminants that pose
4 potentially significant noncarcinogenic adverse health effects via ingestion or dermal routes
5 include arsenic, lead, manganese, and PCBs. Inhalation of chromium (VI) potentially present
6 in airborne soil particles could potentially pose adverse health effects during
7 excavation/construction activities. Chromium (VI) is an irritant which can cause damage to
8 the nasal mucosa if inhaled in sufficient amounts.

9
10 The major factors driving estimated site risks are:

11

- 12 • The presence of PCBs, arsenic, and lead in site soils and potential
13 exposures by site workers and visitors; and
- 14 • The presence of elevated concentrations of metals (primarily arsenic),
15 PCB, and 1,4-dichlorobenzene in the groundwater coupled with the
16 possible future use of groundwater as a drinking water source.

17
18 Exposures to soil contaminants are either currently occurring or could reasonably be
19 expected under current land use conditions; however, the conservative (health protective)
20 exposure assumptions used may overestimate actual exposures. Because Fort Devens is
21 scheduled to close in the near future, the exposure duration of current site workers could be
22 less than the default value of 25 years that was used to estimate risks under current site
23 conditions. The Massachusetts Government Land Bank (Devens Reuse Plan, November 1996)
24 has proposed the area for rail, industrial, and trade-related uses. Groundwater in the vicinity
25 of the site is not a current, future water supply source because there is an existing public
26 water supply system, and the aquifers are thin and not productive. Therefore, the probability
27 of exposure to site contaminants in groundwater is extremely small. There is a drinking water
28 well, the McPherson well, approximately 4,000 feet hydraulically downgradient from the
29 DRMO Yard. However, as discussed in the RI Functional Area II Report, Volume III,
30 Section 6 (E & E 1994a), it would take hundreds of years for benzene, toluene, ethylbenzene,
31 and xylene (BTEX) contaminated groundwater to reach this well. Given the volatility and
32 biodegradation rates of BTEX, it will not persist long enough to do so. This is confirmed by
33 a contaminant transport model conducted after completion of the RI, which showed xylene
34 degrading completely before leaving the POL Storage Area just downgradient of the DRMO
35 Yard (see Appendix A). It would take approximately 10 times longer for TCE to reach this
36 well, based on its retardation factor. TCE has already declined to below detection limits even
37 in AOC 43A wells less than 500 feet downgradient of the DRMO Yard.

38
39
40 **1.2.1.5 Ecological Risk Assessment Summary**

41
42 Field studies were conducted and the ecology of AOC 32 and surrounding areas was
43 characterized. This characterization involved the identification of plant and animal
44 communities, as well as observations of any actual or potential effects of chemical and/or
45 physical stress on these biological resources. In general, four different plant community types
46 were identified; three upland communities and one wetland area.

1 Based on the field surveys and data collected during the RI sampling effort, other
2 than the human disturbance/development in the area, there appear to be only chemical
3 stressors present at AOC 32. Since the human activities (i.e., roads, buildings, mowing, etc.)
4 have been present for a number of years, the vegetation and wildlife have adapted to these
5 changes. Therefore, the presence of human activity in the area is not considered a physical
6 stressor to the ecological community, but rather a defining character of the existing
7 community. No species of concern were identified on site during the field surveys, and none
8 of these species were considered likely to be significantly exposed to site contaminants.
9 Therefore, risks to federal- or state-listed species were not quantitatively evaluated.
10

11 AOC 32 is a potential source of environmental contamination in drainage ditch
12 sediment. The drainage ditch is a narrow, linear area surrounded by areas of human activity.
13 Therefore, the site will support only a few individuals that are tolerant of human activity, and
14 the potential impacts to plant or animal populations as a whole are minimal. Furthermore,
15 wildlife are not likely to be adversely affected due to the comparatively limited extent of the
16 contamination. Contamination of the drainage ditch does not appear to be extensive. The
17 maximum concentrations of contaminants of potential concern (COPCs) were found within 60
18 yards of the culvert, and the sample taken furthest downgradient showed significantly lower
19 concentrations of COPCs. Therefore, the ecological significance of this contamination is
20 considered to be minimal.

21 Metals and organic chemicals in drainage ditch sediments at the DRMO Yard are not
22 considered to pose significant risks to ecological receptors. Levels of cadmium and nickel
23 exceed reference values for invertebrates, but these exceedances are not likely to be ecolog-
24 ically significant, due to the limited extent of contamination. Potential risks of contaminants to
25 wildlife species such as small mammals and carnivores are minimal. Therefore, no further
26 action is considered necessary at the DRMO Yard to further investigate or to mitigate
27 ecological risks of sediment contamination at the site.
28

30 1.2.2 Petroleum, Oil, and Lubricant (POL) Storage Area - (AOC 43A)

32 1.2.2.1 Site Description

34 The POL Storage Area is in the northeast portion of the Main Post adjacent to
35 Shepley's Hill Landfill. It is located across Market Street from the DRMO Yard and is
36 bounded on the south, west, and north by Antietam Street, Cook Street, and Market Street
37 (Figure 1-4). The POL Storage Area served as the central distribution point for all gasoline
38 stations at Fort Devens during the 1940s to 1950s. It was subsequently used to store fuels for
39 various purposes and is currently used to store fuel for military vehicles. The distribution
40 facility formerly consisted of a main gasoline station building (T-401), a pump house, three
41 12,000 gallon USTs, two 12,000-gallon above ground storage tanks (ASTs), and two 8,000-
42 gallon ASTs. Gasoline was delivered to the facility by rail cars where it was transferred to
43 the tanks. Tanker trucks delivered the gasoline to the other stations on base.
44

45 Four ASTs originally located in a pit behind T-401 were removed between 1965 and
46 1972. The three USTs located beneath the pump house were excavated from the site in 1989

1 and 1990 (*Fort Devens Tank Replacement Project Final Report*, Environmental Applications,
2 Inc. [EA 1990]). After removal of the USTs and 800 cubic yards of contaminated soil,
3 confirmatory soil samples were collected from the excavation and analyzed for TPHC. The
4 highest TPHC concentration was 237 milligrams per kilogram (mg/kg) (EA 1990). The
5 excavations were backfilled and no further soil removal has occurred at this area. Five new
6 USTs were installed in the POL Storage Area in 1991. These USTs are used to store fuel for
7 military vehicles.

8 The POL Storage Area consists of a fenced lot located within a developed industrial
9 area of buildings, roads, and grass lots with the exception of the east side of the site, which is
10 bounded by a wooded area on a rock outcrop. With the exception of the wooded area, the
11 ground is flat, with only two or three feet of relief throughout. A set of railroad tracks,
12 formerly used to transport gasoline to the site, is on the north side of the site. The UST area
13 is fenced and an asphalt driveway leads from Antietam Street through a gate. The driveway
14 is bermed to contain any spills. A pump station is located in the center of the fenced area and
15 the new USTs, with associated filling points, are located on the eastern side.

16 The majority of the POL Storage Area site is developed and/or maintained and
17 provides minimal habitat for wildlife. The centrally located portion of the AOC is paved, and
18 it is surrounded by a grass area that is regularly mowed. Located to the east of this grass
19 area is a small wooded lot that consists of mature oak trees. The remaining area includes
20 buildings, roads, and parking lots. The paved area and buildings are fenced. Surface
21 drainage is internal, as the POL Storage Area is in a shallow closed depression. Overall, this
22 site does not support a variety of wildlife species due to the limited habitat types and the
23 constant human activities. Approximately 14 species of concern are known to occur within
24 1.5 miles of the POL Storage Area site, but none were observed during the field survey. One
25 area located approximately 0.5 mile north of the site is identified as an estimated habitat of
26 state-listed rare wetlands wildlife (MNHESP 1993).

27 1.2.2.2 Geology and Hydrology

28 Bedrock beneath the site is Ayer's Granite (granodiorite or granodioritic gneiss). The
29 site lies within a north-northeast trending glacial lake terrace fragment that connects the
30 entrance to Shepley's Hill Landfill with the POL Storage Area. Shepley's Hill is located to
31 the northwest and other bedrock outcrops are located to the east and northeast. Soils are all
32 sandy or gravelly, but probably no natural soils occur undisturbed in this area because of
33 construction activities.

34 Groundwater at the POL Storage Area is encountered at depths ranging from 17.4
35 feet BGS to 27.9 feet BGS as measured in March 1993. Groundwater at the site is found
36 within the unconsolidated overburden with local flow directions probably influenced by
37 bedrock surface configuration. The direction of groundwater flow is initially to the southwest
38 toward Willow Brook and then turns north, around Shepley's Hill, to the Nashua River. A
39 watershed divide is located north of the site, separating water draining to the west towards
40 Willow Brook from water draining to the east towards Plow Shop Pond. The POL Storage
41 Area is bounded on three sides by asphalt roads and on the east side by a wooded rock

1 outcrop. The ground within these roads is a shallow depression which would have to flood in
2 order to overflow into the storm drain catch basins located in the southwest corner of the
3 area. Surface drainage off the site could occur only if the ground is frozen, or during very
4 exceptional storm events.

5

6 1.2.2.3 Nature and Extent of Contamination

7

8 A discussion of screening values, which were used in the RI to evaluate the analytical
9 data, appears at the beginning of Section 1.2.1.3.

10

11 Surface Soils

12

13 Ten surface soil samples were collected from the POL Storage Area. The samples
14 were analyzed for TAL metals, TCL polynuclear aromatic hydrocarbons (PAHs), TCL
15 pesticides/PCBs, and TPHC. Seven metals in surface soils exceed background: arsenic,
16 calcium, cobalt, copper, lead, nickel, sodium, and zinc. Arsenic exceeded screening levels in
17 one sample.

18 Organics in surface soils included DDT, DDE, DDD, alpha-BHC, nine PAHs, and
19 heptadecane. Five PAHs exceeded screening values in one sample. The levels of TPHC are
20 very low (less than 20 $\mu\text{g/g}$ to 102 $\mu\text{g/g}$) considering their location within a POL area.

21

22 Subsurface Soils

23

24 One hundred eighty-three subsurface soil samples were collected from boreholes
25 during field activities at the POL Storage Area. The samples were collected at intervals
26 approximately 5 feet above the water table, at the water table, and 5 feet below the water
27 table. Most of the samples underwent field screening analyses for BTEX and TPHC. Fifteen
28 of the subsurface samples were collected in July 1993 and laboratory analyzed for TCL
29 VOCs, TCL PAH, TCL pesticide/PCBs, TAL metals, and TPHC. Metals analyses were
30 performed on all soil samples collected from confirmation (i.e., laboratory analyzed) borings
31 to determine if they are also contaminants of concern at AOC 43A. Eighteen samples were
32 collected from six confirmation boreholes, and metals were not elevated above screening
33 values. No lead levels above background were noted, for example. Three of 18 soils showed
34 arsenic slightly above background. Calcium and sodium exceeded background in six and one
35 sample(s), respectively, but this is probably due to natural variations. The same can be said
36 of cobalt (two above background), and nickel and zinc (one above background each). There
37 is no evidence of site related contamination.

38

39 Subsurface soils from the confirmation boreholes showed relatively high TPHC in
40 two boreholes. One of these samples (21,000 $\mu\text{g/g}$) exceeded the screening value of 5,000
41 $\mu\text{g/g}$. All other samples ranged from non-detect to 152 $\mu\text{g/g}$, with an average positively
42 identified level of only 31 $\mu\text{g/g}$. Other organics noted include 2-methylnaphthalene and
43 several other base/neutral and acid extractable organic compounds (BNAs) related to fuels,
44 such as pentadecane, hexadecane, and phenanthrene at lower levels. Only one pesticide,
45 DDT, was noted at trace levels in two samples.

1 Two large hydrocarbon plumes and one small one were detected in field screening
2 data. The easternmost plume originates at the site of the removed USTs, inside the fenced
3 area. A second plume originates on the western side of the POL Storage Area at the site of
4 the former ASTs. The third plume apparently originates from the building across Antietam
5 Street from the POL Storage Area. Isolated detections were made at other points in the
6 vicinity; however, they appear to be unrelated to the three plumes.

7 The easternmost plume is approximately 120 feet long by 100 feet wide. This plume
8 has the highest concentrations of TPHC at the POL Storage Area (30,000 mg/kg at 25 to 27
9 feet BGS). The water table is within this depth range in the area. No BTEX compounds in
10 soil were detected within the boundaries of the easternmost plume. Two confirmation
11 boreholes were drilled in this area. The data for TPHC correlated well between the field
12 screened samples and those sent to the laboratory for analyses. A cross-section of the
13 easternmost plume depicts a classic UST release. From about 10 feet to 20 feet, the plume is
14 approximately 30 feet wide. It then flows southeast down the slope of the top of bedrock or
15 of the less permeable sediments on top of the bedrock and appears to spread out on top of the
16 water table, to both northeast and southwest. Because the hydraulic gradient slopes to the
17 southwest the plume is deeper in this direction, but it appears not to have extended for more
18 than seventy or eighty feet in that direction from where it encountered the water table (at
19 B-21S).

20
21 The westernmost soil plume at the POL Storage Area is approximately 120 feet long
22 by 90 feet wide. Concentrations of TPHC in screening samples from this plume are much
23 lower than in the easternmost plume - the highest TPHC concentration was 520 mg/kg.
24 BTEX compounds were detected in screening samples from three boreholes at the POL
25 Storage Area and all of them were within this plume. BTEX levels were 100,000 mg/kg at
26 one soil boring. No BTEX compounds were detected in the soil samples collected from the
27 confirmation borehole or from the monitoring well, making the BTEX screening results
28 questionable. The main difference between the origin of the two plumes is that the
29 westernmost plume release occurred essentially at the surface whereas the easternmost release
30 occurred below surface. From about 23 feet BGS (where the first sample was collected) to
31 the top of the water table, the western plume is only 30 feet wide. As seen in the other
32 plume on site, the product migrated vertically through the vadose zone before reaching
33 groundwater. It is likely that the hydraulic gradient in the area of the release limited any
34 movement to the northeast. The plume is migrating in a southwestern direction from the
35 source area with the direction of groundwater flow.

36
37 A third plume also appears to exist at the site with its origin near the lawn machine
38 maintenance building across Antietam Street from the POL Storage Area. During the
39 screening sample program, BTEX compounds were detected at a high of 4,700 mg/kg.
40 However, confirmation boreholes for these two borings did not confirm these results.
41 Confirmation boreholes had TPHC detections of 23.7 mg/kg and <20 mg/kg, respectively,
42 and no BTEX. The results suggest a high background was present during the screening
43 analysis and that TPHC may not be a problem in this area.

1 Several boreholes, apparently unrelated to the identified plumes, showed TPHC. An
2 isolated hit was detected in front of Building 213. Three soil borings in the parking lot across
3 Antietam Street from the POL Storage Area had TPHC levels ranging from a high of 180
4 mg/kg to 56 mg/kg. However, two boreholes drilled between these borings did not have any
5 measurable TPHC levels and the results suggest variability in the screening analysis and in the
6 distribution of TPHC in soils.

7

8 Groundwater

9

10 Groundwater samples were collected from wells during five separate sampling
11 rounds. Samples were analyzed for both total and dissolved TAL metals, TCL VOCs,
12 pesticides/PCBs, and PAH, explosives, and TPHC. No BTEX levels exceed screening values
13 and screening values for TPHC are exceeded in the eastern plume only, at 43MA-93-04X.

14 Filtered and unfiltered metals analyses were conducted on all water samples collected
15 from the newly installed monitoring wells. Filtered metals were collected from all previously
16 installed wells during the third round of sampling and only from selected wells during earlier
17 rounds of sampling. Silt and clay particles in the water often result in metals levels in
18 unfiltered samples that exceed MCLs. To determine the level of soluble constituents, the
19 samples were filtered through a 0.45 micrometer (μm) barrel filter. Low solubility metals
20 such as aluminum and iron were greatly reduced, while soluble metals such as sodium and
21 calcium were much less affected.

22 All of the wells exceed screening values for aluminum, iron, manganese, and sodium
23 in unfiltered samples. Except for one monitoring well, screening values for manganese are
24 exceeded in all unfiltered samples. Other metals were detected at levels exceeding
25 background or screening values. The wells with the highest aluminum and iron level also had
26 the highest levels of other metals, which implies a relationship between the presence of
27 particulates and the content of metals in groundwater.

28 Filtered samples from these wells have markedly lower levels of inorganics indicating
29 that the majority of the metals are in the suspended solids. Levels of calcium, sodium,
30 potassium, and magnesium show little change because their compounds are more soluble than
31 those of iron and aluminum. The maximum level of iron in filtered samples was 1,560 $\mu\text{g/L}$
32 (in 43MA-93-10X). This level is essentially the same as in the unfiltered sample. All other
33 levels of iron in filtered samples decreased to less than 1 percent of the unfiltered levels.
34 Aluminum levels exceeded background in four wells. Weathering of aluminosilicate bedrock
35 may account for the levels of aluminum detected at AOC 43A. This is increased by low pH
36 in poorly buffered soils such as those that occur at Fort Devens. Manganese levels are above
37 background in all wells except two. Manganese was above background in one well, which
38 although hydraulically upgradient to the POL Storage Area is downgradient of DRMO where
39 it was concluded that elevated levels of naturally occurring manganese exist. With the
40 exception of manganese, which apparently occurs naturally at the site, the data collected do
41 not indicate the presence of dissolved metals resulting from site activities. The background
42 level of dissolved iron is exceeded in one monitoring well, but this appears to be localized as
43 samples from two nearby downgradient wells do not yield levels above background.

Feasibility Study: Fort Devens FA II
Section No.: 1
Revision No.: 2
Date: January 1997

1 Groundwater samples, collected from the boreholes after soil samples were collected,
2 were screened in the field for the presence of BTEX and TPHC. The screening samples
3 suggest that BTEX and TPHC contaminated groundwater occurs as two plumes at AOC 43A.
4 The contamination is apparently a result of the release of petroleum products from ASTs,
5 USTs, and associated piping. The levels of contaminants in groundwater are distributed in
6 the same general pattern as soil contamination. The groundwater plumes are longer and
7 narrower due to the greater mobility of the contaminants in groundwater.

8 The eastern plume measures approximately 140 feet long by 80 feet wide. TPHC
9 concentrations in groundwater range from 17,000 $\mu\text{g}/\text{L}$ to 53 $\mu\text{g}/\text{L}$ at the downgradient edge
10 of the plume. Total BTEX concentrations range from a high of 3,550 $\mu\text{g}/\text{L}$ to 85 $\mu\text{g}/\text{L}$. The
11 western groundwater plume measures approximately 150 feet by 60 feet. TPHC
12 concentrations range from 4,100 $\mu\text{g}/\text{L}$ to 43 $\mu\text{g}/\text{L}$ at the downgradient edge of the plume.
13 BTEX concentrations are the highest contaminant concentrations on site ranging from 29,990
14 $\mu\text{g}/\text{L}$ to 74 $\mu\text{g}/\text{L}$.

15 Isolated detections of TPHC and BTEX compounds were encountered in other
16 boreholes during the screening program. The source of the TPHC material is unknown.
17 These boreholes were located in the fork of the railroad tracks. Gasoline shipments were
18 offloaded from rail cars to the various tanks at this point and it is likely that these detections
19 are the result of spills. It is likely that BTEX and TPHC detected in screening samples were
20 sorbed on particles in the inevitably turbid samples at the bottom of the boreholes. BTEX and
21 TPHC may therefore exist at much lower levels as dissolved components of groundwater.

22 Samples collected from monitoring wells using USAEC procedures underwent
23 analyses for TAL metals, VOCs, PAHs, explosives, and TPHC utilizing full laboratory
24 methods. Generally, results for BTEX and TPHC were significantly lower than the screening
25 results, indicating a poor correlation for the screening results. Only a few VOCs were
26 detected in groundwater. Trichloroethene was detected in three wells, and exceeded its
27 screening value in one but was not found in any wells downgradient of AOC 43A and is
28 clearly coming from the DRMO Yard area. Acetone was detected at 23.0 $\mu\text{g}/\text{L}$, but this
29 detection did not exceed any screening values. This compound was detected in one well only.
30 The sample collected three months later was non-detect for acetone, which is a common
31 laboratory contaminant. Xylene was detected at levels of 22 $\mu\text{g}/\text{L}$ and 13 $\mu\text{g}/\text{L}$, respectively.
32 The locations of the wells place them inside of the eastern BTEX plume. These levels are
33 below the screening value for xylene. No BTEX compounds were found in any other wells.

34 2-Methylnaphthalene was detected in two monitoring wells at levels exceeding
35 screening values. 2-Methylnaphthalene is a semivolatile component of gasoline and fuel oil.
36 In the first well, the detection was in March 1993; a sample collected three months later was
37 a non-detect. The detection in the second monitoring well took place in November 1993, the
38 only round this well was sampled. TPHC was detected in all wells at the POL Storage Area
39 either in or downgradient of the source areas. The maximum level of TPHC was 7,820 $\mu\text{g}/\text{L}$
40 in a monitoring well which is in the eastern plume at the approximate point of the UST
41 release. A monitoring well approximately 80 feet southeast had a TPHC level of 1,250 $\mu\text{g}/\text{L}$.
42 Both of these levels exceed screening values. A monitoring well located approximately 1,000
43

1 feet west of the POL Storage Area had a TPHC concentration of 742 $\mu\text{g}/\text{L}$. The
2 contamination detected does not appear to be related to activities at the POL Storage Area. A
3 gravel-covered storage yard and an unpaved road are near this well and probably are the
4 sources of this contamination.

5 Essentially, the BTEX and TPHC detections in screening samples were not confirmed
6 in groundwater samples taken from completed monitoring wells (except for one TPHC hit of
7 7,820 $\mu\text{g}/\text{L}$). Wells were completed in the "hot spots" as revealed by the field screening, but
8 the well samples showed only sporadic hits at concentrations much lower (by orders of
9 magnitude) than field screening detections. In fact, the groundwater screening samples were
10 determined to not be representative of the groundwater conditions, based on sampling
11 methodology. Borings were advanced with an auger bit until the water table was reached.
12 Groundwater filled the hole, and this water was sampled. Any contamination which may have
13 been present in the soils would be free to fall down into the water in the bottom of the
14 borehole. Therefore, it is not possible to differentiate between contamination in the
15 groundwater and contamination in the soils (BTEX was also not confirmed in soil samples)
16 from field screening samples. Furthermore, it was not possible to purge the water samples
17 obtained from field screening methodology, as is normal protocol for well sampling. These
18 are the reasons confirmatory sampling was planned. The fact that well samples did not
19 confirm screening samples makes the screening sample results highly questionable as
20 representative of groundwater quality.

21
22 Explosive compounds were detected in three wells at or near the POL Storage Area.
23 Two of the wells are located at the site, while the third well is located approximately 950 feet
24 west of these two wells. Nitroaromatics detected at the two site wells include: 1,3,5-
25 trinitrobenzene (1,3,5-TNB), 2,6-dinitrotoluene, 2-amino-4,6-dinitrotoluene, 4-amino-2,6-
26 dinitrotoluene, and 3- and 4-nitrotoluene. According to available information, the POL
27 Storage Area has never treated, stored, or disposed of explosive compounds, and therefore the
28 origin of these compounds is unknown. Levels detected at the third well were 1,3-
29 dinitrobenzene (1,3-DNB), 2,6-dinitrotoluene, 2-amino-4,6-dinitrotoluene, 2-nitrotoluene, 3-
30 nitrotoluene, and Cyclonite, at levels below any screening values. The origin of these
31 detections are unknown. The detection of explosives in the groundwater correlates directly
32 with high levels of TPHC and may not be related to explosive contamination. PAHs were
33 detected in two wells. They are often found as a result of incomplete fossil fuel combustion.
34 2-Methylnaphthalene exceeded its screening value in two samples.

35
36
37 **Surface Water and Sediment Samples**

38
39 There are several storm drain catch basins at the junction of Cook Street and
40 Antietam Street, with one on the southwest corner of the POL Storage Area. These inlets,
41 and several others along Antietam Street convey storm water to Willow Brook adjacent to the
42 primary school west of AOC 43A. Another storm drain, now only a surface ditch, began
43 within the Coal Pile area across Cook Street (west) from the POL Storage Area. This passes
44 north of the primary school and this drainage also discharges to Willow Brook. Arthur D.
45 Little, Inc. sampled at the head and at the discharge points of these drains. Other samples

1 were taken at various points in Willow Brook including from the outlet of Robbins Pond,
2 below the pond, and opposite the base chapel.

3 All these sediments contain moderately high levels of organic carbon and TPHC
4 above background. Of the locations that could be affected by AOC 43A or the DRMO Yard,
5 the Coal Yard catch basin sample has the highest total organic carbon (TOC), and the sample
6 at the junction of Cook and Antietam Streets has the highest TPHC. This is also the only
7 sample in this sample set of a catch basin at a heavily travelled intersection, but it has a much
8 lower TPHC than other catch basins further south down Cook Street that could not be affected
9 by the AOCs. There are three groups of organics found, PAHs, pesticides, and phthalates,
10 and a few hits of individual compounds such as toluene and dibenzofuran. No pattern of
11 contamination attributable to a single source is observable, nor are there correlations between
12 levels of contaminants within a sample. TOC does not correlate with TPHC or high levels of
13 organic compounds nor do PAHs correlate with TPHC levels. There is no evidence of any
14 specific impact from the DRMO Yard or the POL Storage Area on Willow Brook either via
15 storm drain or groundwater discharge. In the brook, levels of PAHs, TPHC, total organics,
16 and pesticides all rise from a lower level at Robbins Pond to a higher level at some
17 intermediate point and then decline at the downgradient (north) end of the brook. TOC varies
18 both up and down along the brook but the highest value is found at the downgradient end of
19 the brook.

21 None of the levels of metals in these sediments is above background or seems to
22 indicate contamination.

25 1.2.2.4 Human Health Risk Assessment Summary

27 The main exposure pathway under current site conditions is direct contact (dermal
28 contact and incidental ingestion) with contaminated surface soils and sediment. Potential
29 receptors include POL Storage Area workers and site visitors, which include trespassers.
30 Because volatile and semivolatile compounds were detected infrequently and at low
31 concentrations, vapor inhalation is not considered to be a significant exposure pathway at the
32 site. Inhalation of contaminated dust is not regarded as a major exposure pathway under
33 existing conditions because wind erosion of surface soil is limited by pavement and vegetative
34 cover. However, if the cover was removed and soils were excavated for some reason, such
35 as maintenance of utility lines that run under the site, workers could potentially inhale
36 airborne dust from soils and come into direct contact with subsurface contaminants for a short
37 period, probably several days. The area where the POL Storage Area is located will be
38 released for redevelopment following installation closure, and the area is intended to be zoned
39 for industrial/commercial use. If the site is redeveloped for commercial use, construction
40 workers potentially could be exposed to surface and subsurface contamination by all of the
41 pathways described above over a period of several months during excavation and
42 construction. After redevelopment, future workers may be exposed by the same pathways as
43 current workers, assuming similar soil coverage with pavement or vegetation.

44 Groundwater in the vicinity of the site currently is not used for water supply
45 purposes, so direct contact with groundwater contamination is not possible under current

Feasibility Study: Fort Devens FA II
Section No.: 1
Revision No.: 2
Date: January 1997

1 conditions. However, future businesses could conceivably install private wells in the area,
2 and future workers potentially could be directly exposed to groundwater contamination
3 through ingestion of drinking water. The McPherson Well, a public supply well, is nearly
4 4,000 feet hydraulically downgradient from the POL Storage Area. As discussed in the RI
5 Functional Area II Report, Volume III, Section 6, contaminated groundwater is not expected
6 to reach this well (E & E 1994a) from either the DRMO Yard or the POL Storage Area.
7 (The recently completed groundwater model, presented as Appendix A, confirms this
8 expectation.)
9

10 Under current EPA Superfund Policy (USEPA 1992c), acceptable exposure levels for
11 carcinogens are generally those that represent an excess upper bound lifetime cancer risk of
12 between 10^{-4} and 10^{-6} . For noncarcinogens, acceptable exposures are those with a HI of 1 or
13 less. The estimated cancer risk to current site workers from exposure to contamination in the
14 surface soil at AOC 43A is 2.1×10^{-5} for the RME case, and 2.8×10^{-6} for the average
15 exposure case, within the acceptable range of 10^{-4} to 10^{-6} . Estimated cancer risks for adult
16 site trespassers were approximately half as great. Nearly all the estimated cancer risk is due
17 to ingestion and dermal absorption of arsenic (85 percent) and ingestion of carcinogenic PAHs
18 (15 percent). The noncarcinogenic HIs are less than 1 for the exposure scenarios under
19 current site conditions.
20

21 Several alternative exposure scenarios that could occur under possible future site
22 conditions were evaluated. Two scenarios (Scenario 3 - Future Construction Workers and
23 Scenario 4 - Future Site Workers) address potential exposure to contaminants in soils by
24 ingestion, dermal contact, and inhalation of ambient air (construction workers only). The last
25 scenario (Scenario 5 - Groundwater Usage) addresses potential ingestion of contaminants in
26 groundwater. Scenarios 3 and 4 were structured and evaluated as mutually exclusive
27 alternatives. The site worker exposure scenarios assume permanent full-time employment.
28 The construction workers are assumed to be a separate group of workers who move elsewhere
29 to other construction projects once construction on the site is completed. While some
30 construction workers conceivably could take permanent jobs at the site after construction work
31 is completed, this is considered unlikely. Therefore, construction worker risks are not
32 summed with the permanent worker risk estimates.
33

34 For future construction workers exposed to surface soil contaminants, estimated
35 cancer risks are 2.2×10^{-5} for RME cases and 3.0×10^{-6} for the average case, which fall
36 within the 10^{-4} to 10^{-6} range deemed acceptable by the EPA. The majority of this risk (83
37 percent) is due to arsenic; carcinogenic PAHs account for approximately 17 percent of the
38 total cancer risk for the future construction worker scenario. PAHs were considered in risk
39 calculation for the ingestion and inhalation pathways only as there is no approved slope factor
40 for evaluating the dermal contact route. Noncancer HIs total 4.7 for the RME case and 0.75
41 for the average exposure case. Most of the RME total is due to ingestion and dermal
42 absorption of arsenic, with a total HI of 4.1. Arsenic was the only COPC with an HI greater
43 than 1.0. It should be noted that PAH and elevated arsenic detections were highly sporadic
44 (one of each), and it appears that they represent ambient conditions and not site-related
45 contamination.
46

Feasibility Study: Fort Devens FA II
Section No.: 1
Revision No.: 2
Date: January 1997

1 Under potential future site conditions, the estimated potential cancer risk to future site
2 workers from exposures to soil is 1.0×10^{-4} for the RME case and 1.4×10^{-5} for the average
3 case. The future RME risk is higher than the current RME risk because the risk calculation
4 assumes that the future workers will spend their entire work day at the site, whereas the
5 current site worker is only at the POL Storage Area for approximately one hour per day.
6 Under future conditions, the worker HIs were greater than the current exposure HIs, but were
7 still less than 1.

8 The potential risks associated with the possible use of site groundwater as a potable
9 water source by a business occupying the site in the future, a highly unlikely possibility due
10 to the existence of a public water supply system in the area and the low yield of the local
11 aquifer, was evaluated at AOC 43A. A large portion of the estimated groundwater risks were
12 due to metals, and a large portion of many of the metal concentrations found in the unfiltered
13 groundwater samples appear to be associated with suspended sediment (soil minerals) which
14 would not be present in groundwater used as drinking water. Therefore, for the POL Storage
15 Area, potential risks were estimated two ways:

16

- 17 • Using concentrations of COPCs detected in unfiltered groundwater;
18 and
- 19 • Using metals data from filtered groundwater to exclude the effects of
20 suspended sediment.

21 At the POL Storage Area, estimated potential cancer risks from consumption of
22 groundwater based on data from unfiltered groundwater samples are 1.9×10^{-4} for the RME
23 case, exceeding EPA's acceptable range, and 4.1×10^{-5} for the average exposure case.
24 Almost all of the potential risk is due to ingestion of beryllium (> 99 percent). However, the
25 highest concentrations of beryllium detected in unfiltered groundwater are associated with high
26 levels of suspended sediments, levels that would not be present in groundwater actually used
27 as drinking water. When metals data from filtered groundwater samples are used to remove
28 the effects of suspended sediment, estimated cancer risks drop more than an order of
29 magnitude to 3.3×10^{-6} and 2.4×10^{-6} for the RME and average exposure cases, respectively.
30 It should also be noted that the risk factors for beryllium are derived from laboratory
31 experiments using soluble salts such as beryllium sulfate, while the beryllium at the POL
32 Storage Area is almost certainly in the form of beryl (beryllium aluminum silicate) or
33 beryllium oxide, which are very insoluble and therefore biologically inactive. So these risks
34 are extremely unrealistic.

35 Total HIs for noncarcinogenic effects from consumption of groundwater at the POL
36 Storage Area, based on data from unfiltered groundwater samples, are 21 for the RME case
37 and 3.9 for the average exposure case, both above the acceptable HI of 1; the HI for the
38 RME case is mostly due to manganese (HI = 16) and lead (HI = 3). However, the elevated
39 concentrations of many metals in the groundwater are associated with high levels of suspended
40 sediments. When the HIs are recalculated using metals data from filtered groundwater
41 samples, the total HIs drop to 2.7 and 0.8 for the RME and average exposure cases.
42 Manganese was the only COPC in filtered groundwater with a HI greater than 1.

1 Future permanent site workers could be exposed to contaminants in both the soil and
2 the groundwater; therefore, the estimated soil and groundwater risks should be summed for
3 this group of potential receptors. The highest estimated soil risks are for a future worker and
4 the highest estimated groundwater risks are for unfiltered groundwater. Combining these risk
5 estimates gives a maximum estimated RME risk of 2.9×10^{-4} due mostly to the ingestion of
6 groundwater. The highest plausible future worker risk is the sum of risks from soil exposure
7 and usage of filtered groundwater. Any future use of area groundwater as drinking water is
8 unlikely because of the existing public water supply system and the low yield of the local
9 aquifer; therefore, the most realistic future worker risks are those for the future site worker
10 from potential exposure to soil contaminants alone.

11 The site contaminants estimated to pose potential excess lifetime cancer risks greater
12 than 10^{-6} include arsenic, beryllium, and PAHs. Site contaminants that pose potentially
13 significant noncarcinogenic adverse health effects via ingestion or dermal routes include
14 arsenic, lead, and manganese.

17 The major factors driving estimated site risks are:

18

- 19 • The presence of arsenic in site soils and potential exposure to it by
20 site workers and visitors; and
- 21
- 22 • The presence of elevated concentrations of metals (beryllium, lead,
23 and manganese) in the groundwater coupled with the possible future
24 use of groundwater as a drinking water source.
- 25

26 Exposures to soil contaminants are either currently occurring or could reasonably be
27 expected under current land use conditions, however, the conservative (health protective)
28 exposure assumptions used may overestimate actual exposures. For example, because Fort
29 Devens is slated to close in the near future, the exposure duration of current site workers
30 could be considerably less than the default value of 25 years that was used to estimate worker
31 risks near current site conditions. Furthermore, the identified risks are due to arsenic and
32 PAHs, which were detected very sporadically. Groundwater in the vicinity of the site is not a
33 current or likely future water supply source because there is an existing public water supply
34 system and the local aquifer is of low yield. Therefore, the probability of exposure to site
35 contaminants in groundwater is extremely small.

37 1.2.2.5 Ecological Risk Assessment Summary

39 Field studies were conducted and the ecology of the POL Storage Area and
40 surrounding areas was characterized. This characterization involved the identification of plant
41 and animal communities as well as observations of any actual or potential effects of chemical
42 and/or physical stress on these biological resources. Only two plant community types were
43 identified, and both were upland communities.

45 Based on the field surveys and data collected during the RI sampling effort, other
46 than the human disturbance/development, there appear to be only chemical stressors present at

1 the POL Storage Area. Since the human activities have been present for a number of years,
2 the vegetation and wildlife have adapted to these changes. Therefore, the presence of human
3 activity in the area is not considered a physical stressor to the ecological community, but
4 rather a defining character of the existing community.

5 The chemical stressors present within the POL Storage Area include metals and
6 organic chemicals that were detected in soils and groundwater at levels exceeding background
7 and ecological criteria. None of these contaminants are considered COPCs for ecological
8 receptors due to the minimal likelihood of exposure. Based on the disturbed/developed nature
9 of the site and the limited abundance and diversity of flora and fauna, there are very few
10 ecologically sensitive receptors or pathways present at the site. The site consists of paved
11 areas, roads, grass, an upland woodlot, and areas of dirt and/or gravel. The areas of dirt are
12 not vegetated and are adjacent to the roads where vehicles park or drive. Some small
13 mammals and songbirds may occasionally visit the grass area to feed, but their frequency of
14 usage is minimal since there are numerous other suitable foraging areas in the general
15 vicinity. Also, their exposure to contaminants while on site is considered to be minimal due
16 to the limited areal extent of contamination. In addition, the vegetation observed in the POL
17 Storage Area during the field survey did not exhibit any signs of stress. In addition, no state-
18 or federally-listed plant or animal species are expected to occur at the site. There are no
19 permanent surface water resources located on the site, and stormwater runoff is piped to
20 Willow Brook. However, the POL Storage Area does not appear to impact Willow Brook.
21 Similarly, the potential ecological risks of groundwater discharge are not evaluated due to the
22 distance of the site from the potential groundwater discharge points.

23 Since there are no ecologically sensitive receptors exposed to contaminants at the
24 POL Storage Area, no further evaluation of these contaminants is included in the risk
25 assessment. No ecologically significant receptors or pathways are present at the POL Storage
26 Area and, therefore, no risks from site contamination were identified for this site.

27 1.3 RECOMMENDATIONS FROM THE REMEDIAL INVESTIGATION

28 The RI report (E & E 1994a) presented recommendations for further action in Section
29 10 of Volumes II and III from Functional Area II. This Feasibility Study has been developed
30 based on these RI recommendations and subsequent discussion with regulatory agencies.


31 At AOC 32 on the Main Post (Functional Area II), it was determined that contami-
32 nants in the soils of the DRMO Yard pose a potential risk of unacceptable exposure to site
33 workers. This contamination appears to be related to the historical activities at the DRMO
34 Yard and may have impacted the drainage pathways leading from the yard. Therefore, it was
35 recommended that this FS consider remedial action for these soils.

36 It was determined that there could be a potential risk resulting from the future use of
37 groundwater in this area. However, the risk assessment concluded that the use of
38 groundwater is highly unlikely. Therefore, no remedial action was recommended despite
39 exceedances of screening values at UST 13 and isolated low level exceedances at the DRMO
40 Yard. As a result of discussions with the regulatory agencies, the FS will develop alternatives

Feasibility Study: Fort Devens FA II
Section No.: 1
Revision No.: 2
Date: January 1997

1 for UST 13 groundwater and POL Storage Area/DRMO Yard groundwater separately.
2 Organic contaminants in DRMO groundwater have not apparently migrated downgradient into
3 the POL Storage Area, and a recently completed model indicates that further migration of
4 organics contamination will be at very low concentrations. Remedial alternatives will be
5 developed for the POL Storage Area/DRMO Yard groundwater regime, with the continued
6 monitoring of wells downgradient of the POL Storage Area/DRMO Yard.
7

8 At AOC 43A, a potential risk was identified under the highly unrealistic scenario of
9 consumption of unfiltered groundwater. The risk is due to beryllium, which is most likely to
10 exist in its insoluble form, and therefore be unavailable for biouptake. Potential risks were
11 also identified in surficial soils, but these risks were due to arsenic and PAHs, which were
12 detected very sporadically, and represent ambient conditions rather than site-related
13 contamination. Field screening samples indicated plumes of BTEX and TPHC in subsurface
14 soils and groundwater. BTEX detections were not confirmed in laboratory confirmation, and
15 the screening data were therefore not considered usable in the risk assessment. Regardless,
16 the existence of BTEX or TPHC in the subsurface (mostly 25 feet BGS) would not pose a risk
17 to human health. Furthermore, it was demonstrated in the recently completed groundwater
18 model that groundwater contaminants would not impact McPherson well. (The modeling was
19 performed using xylene as the contaminant of concern, but would hold for all BTEX
20 compounds, and even more so for TPHC, which is also biodegradable and characterized by
21 more highly sorbing longer-chain hydrocarbons than xylene). The arsenic which was detected
22 in groundwater is most likely to be naturally occurring, and in any case is not mobile enough
23 to impact McPherson well. The POL Storage Area/DRMO Yard groundwater does not pose
24 any realistic risks to human health or the environment and there will be no impact on the
25 McPherson well, under present site conditions. The possibility of remedial action was
26 assessed for AOC 43A/AOC 32, with continued long-term monitoring, because of future
27 potential consumption of groundwater.






Figure 1-2 LOCATION OF FUNCTIONAL AREA II SITES




Figure 1-3 SITE MAP OF AOC 32 (DRMO YARD)




Figure 1-4 SITE MAP OF AOC 43A (POL STORAGE AREA)

1

2

3

2. REMEDIAL ACTION OBJECTIVES AND CLEANUP GOALS

4

5

6

2.1 INTRODUCTION

7

In this section, remedial action objectives are established for all media (soil, sediment, groundwater, and surface water) at the Fort Devens AOCs. Remedial action objectives exist for the protection of human health and the environment and are developed based on an evaluation of ARARs, TBCs, and findings of the site-specific baseline risk assessment and ecological risk assessment. This evaluation determines the numerical levels which each contaminant must not exceed. Each of these categories is discussed briefly below.

8

2.1.1 Applicable or Relevant and Appropriate Requirements (ARARs)

9

Compliance with ARARs is one of the CERCLA criteria to be evaluated for each of the alternatives screened for detailed analysis in Section 5. A remedial alternative must meet this criterion to be eligible for selection as a remedy. CERCLA was passed by Congress and signed into law on December 11, 1980 (Public Law 96-510). This act was intended to provide for "liability, compensation, cleanup, and emergency response for hazardous substances released into the environment and cleanup of inactive waste disposal sites." The Superfund Amendments and Reauthorization Act, adopted on October 17, 1986 (Public Law 99-499), did not substantially alter the original structure of CERCLA, but provided extensive amendments to it.

10

In particular, Section 121 of CERCLA specifies that remedial actions for cleanup of hazardous substances must comply with requirements or standards under federal or more stringent state environmental laws that are applicable or relevant and appropriate to the hazardous substances or circumstances at a site. Inherent in the interpretation of ARARs is the assumption that protection of human health and the environment is ensured.

11

Terms and Definitions

12

The following is an explanation of the terms used throughout this ARARs discussion:

13

Applicable requirements are "those cleanup standards, standards of control, and other substantive (non-administrative) environmental protection requirements, criteria, or limitations promulgated under federal or state law that specifically address a hazardous substance, pollutant, contaminant, remedial action, location, or other circumstances at a CERCLA site" (52 FR 32496, August 27, 1987).

14

Relevant and appropriate requirements are "those cleanup standards, standards of control, and other substantive (non-administrative) environmental protection requirements, criteria, or limitations promulgated under federal or state law that, while not applicable to a

1 hazardous substance, pollutant, contaminant, remedial action, location, or other circumstances
2 at a CERCLA site, address problems or situations sufficiently similar to those encountered at
3 the CERCLA site that their use is well suited to the particular site" (52 FR 32496).

4 Requirements under federal or state law may be either applicable or relevant and
5 appropriate to CERCLA cleanup actions, but not both. However, requirements must be both
6 relevant and appropriate for compliance to be necessary. In the case where both a federal and
7 a state ARAR are available, or where two potential ARARs address the same issue, the more
8 stringent regulation must be selected. However, CERCLA Section 121(d)(4) provides several
9 ARAR waiver options that may be invoked, providing that the basic premise of protection of
10 human health and the environment is not ignored. A waiver is available for state standards
11 that have not been uniformly applied in similar circumstances across the state. In addition,
12 CERCLA Section (d)(2)(C) forbids state standards that effectively prohibit land disposal of
13 hazardous substances.

14
15 CERCLA on-site remedial response actions must only comply with the substantive
16 requirements of a regulation and not the administrative requirements such as obtaining permits
17 and agency approvals, recordkeeping, reporting, and off-site activities such as waste disposal
18 (CERCLA Section 121(e)). As noted in the ARARs guidance (USEPA 1988a):

19
20 The CERCLA program has its own set of administrative procedures which
21 assure proper implementation of CERCLA. The application of additional or
22 conflicting administrative requirements could result in delay or confusion.

23
24 **Substantive requirements** pertain directly to the actions or conditions at a site, while
25 **administrative requirements** facilitate their implementation. In order to ensure that
26 CERCLA response actions proceed as rapidly as possible, the EPA has reaffirmed this
27 position in the final National Oil and Hazardous Substances Pollution Contingency Plan
28 (NCP) (55 FR 8756, March 8, 1990). The NCP defines on site as "the areal extent of
29 contamination and all areas in very close proximity to the contamination necessary for
30 implementation of the response action." The interagency agreement (IAG) provides additional
31 guidance on the applicability of permitting requirements to response actions at Fort Devens
32 (USEPA 1991c). The EPA recognizes that certain of the administrative requirements, such as
33 consultation with state agencies and reporting, are accomplished through the state involvement
34 and public participation requirements of the NCP.

35
36 The Army's interpretation of the applicability of the Massachusetts Contingency Plan
37 (MCP) to AOCs 32 and 43A of Fort Devens parallels guidance provided by EPA in
38 comments dated February 28, 1994 on the Draft Proposed Plan and Final Feasibility Study
39 for AOCs 44 and 52 at Fort Devens (USEPA 1994). In its comments, EPA references the
40 following sentences from the *CERCLA Compliance with Other Laws Manual* 310 CMR
41 40.0111(1)(a):

42
43 The CERCLA program has its own set of administrative procedures which
44 assure proper implementation of CERCLA. The application of additional or
45 conflicting administrative requirements could result in delay or confusion.

1 Further reference is made to the MCP at 310 CMR 40.0111 which contains a specific
2 provision for deferring application of the MCP at CERCLA sites. 310 CMR 40.0111(1)(a)
3 provides that response actions at CERCLA sites shall be deemed adequately regulated for
4 purposes of compliance with the MCP, provided the MDEP concurs in the CERCLA record
5 of decision. Thus, it is the Army's interpretation in following EPA guidance that the MCP
6 shall not be considered an ARAR.

7
8 ARARs are divided into the three categories listed below:
9

10 • **Location-specific ARARs** "set restrictions upon the concentration of
11 hazardous substances or the conduct of activities solely because they
12 are in special locations" (53 FR 51394). In determining the use of
13 location-specific ARARs for selected remedial actions at CERCLA
14 sites, one must investigate the jurisdictional prerequisites of each of
15 the regulations. Basic definitions and exemptions, must be analyzed
16 on a site-specific basis to confirm the correct application of the
17 requirements.

18 • **Chemical-specific ARARs** are usually health- or risk-based
19 numerical standards or methodologies that limit the concentration of
20 a chemical found in or discharged to the ambient environment. They
21 govern the extent of site remediation by providing either actual
22 cleanup levels, or the basis for calculating such levels. For example,
23 groundwater MCLs may provide the necessary cleanup goals for sites
24 with contaminated groundwater. There are no direct chemical-
25 specific ARARs for soils. Chemical-specific ARARs for the site may
26 also be used to indicate acceptable levels of discharge in determining
27 treatment and disposal requirements, and to assess the effectiveness
28 of future remedial alternatives.

29 • **Action-specific ARARs** set controls or restrictions on particular
30 kinds of technologies or activities related to the management of
31 hazardous waste (53 FR 51437). Selection of a particular remedial
32 action at a site will invoke the appropriate action-specific ARARs
33 that may specify particular performance standards or technologies, as
34 well as specific environmental levels for discharged or residual
35 chemicals. Action-specific ARARs are established under the
36 Resource Conservation and Recovery Act (RCRA), the Clean Air
37 Act, the Clean Water Act, the Safe Drinking Water Act, the Toxic
38 Substances Control Act, and other laws.

41 Many regulations can fall into more than one category. For example, many location-
42 specific ARARs are also action-specific because they are triggered if remedial activities affect
43 site features. Likewise, many chemical-specific ARARs are also location specific. However,
44 only chemical-specific ARARs are candidates for site cleanup goals. Action- and location-
45 specific ARARs apply to the execution of remedial actions.

1 The Occupational Safety and Health Administration (OSHA) has promulgated
2 standards for protection of workers at hazardous waste operations at RCRA or CERCLA sites
3 (29 CFR Part 1910). These regulations are designed to protect workers who would be
4 exposed to hazardous waste. Federal construction activities involving no potential for
5 hazardous substance exposure are covered by the OSHA standards found at 29 CFR Part
6 1926. EPA, in the NCP (40 CFR 300.150), requires compliance with the OSHA standards.
7 OSHA standards are not discussed in the FS, but typically would be addressed in the remedial
8 action site-specific Health and Safety Plan.

9 The determinations of ARARs in this report have been made in accordance with
10 Section 121(d)(2) of CERCLA. They are also consistent with EPA guidance set forth in the
11 CERCLA NCP (40 CFR 300) (USEPA 1992b); the two-part guidance document entitled
12 *CERCLA Compliance With Other Laws Manual*, Office of Solid Waste and Emergency
13 Response (OSWER) Directives 9234.1-01 and 9234.1-02 (USEPA 1988a); and the document
14 entitled *Guidance for Conducting Remedial Investigations and Feasibility Studies under*
15 *CERCLA* (EPA-540/G-89/004) (USEPA 1988b).

16 2.1.2 "To Be Considered" (TBC) Guidance

17 TBCs are non-promulgated or nonapplicable Federal or State standards or guidance
18 documents that are to be used on an "as appropriate" basis in developing cleanup standards in
19 the absence of federal- or state-promulgated regulations. Because they are not promulgated or
20 enforceable they do not have the same status as ARARs and are not considered required
21 cleanup standards. TBCs include proposed standards, guidance values, criteria, and
22 advisories that are not legally binding, but may serve as useful guidance for remedial actions.
23 These are not ARARs but are "to be considered" guidance. These guidelines may be
24 addressed as deemed appropriate.

25 2.1.3 Site-Specific Risk Assessments

26 CERCLA requires that remedial actions meet ARARs and be protective of human
27 health and the environment. The results of the human health risk assessment conducted
28 during the RI were used to calculate contaminant concentrations corresponding to an
29 acceptable risk level. For noncarcinogens, concentrations corresponding to a hazard index of
30 1 were calculated. For carcinogens, the EPA specifies an "acceptable range" of 10^{-4} to 10^{-6}
31 excess cancer risk to determine site-specific risk-based concentrations. Increasingly, EPA has
32 recommended that a 10^{-4} excess cancer risk be used for risk-based cleanup goals. The MCP
33 suggests that a 10^{-5} excess cancer risk be used for risk-based concentrations, but the MCP is
34 a TBC rather than an ARAR.

35 Site-specific ecological risks were also evaluated as part of the RI. For the most part,
36 no quantitative risks were identified for any of the Fort Devens sites, although some minimal
37 quantitative risks were calculated for sediments along the storm drainage at AOC 32,
38 discussed in Section 1.2.1. Therefore, for purposes of this FS, no cleanup goals have been
39 established for the sediments.

1 2.2 DEVELOPMENT OF REMEDIAL ACTION OBJECTIVES 2

3 Remedial action objectives (RAOs) are intended to serve as qualitative guidelines for
4 remediation. State and Federal laws, regulations, and guidance documents are reviewed to
5 identify any ARARs or TBCs. Then, the risk assessments are consulted to identify complete
6 exposure pathways. The RAOs are developed for specific media, but not for specific
7 operable units.

8 The following are RAOs for site-related surface and subsurface soils:
9

- 10 • Prevent direct and indirect contact, ingestion, and inhalation of the
11 soil contaminated with COPCs by human and ecological receptors at
12 levels that could pose risks;
- 13 • Prevent erosion and migration of soil contaminated with COPCs to
14 storm sewers and surface water bodies; and
- 15 • Prevent COPC migration to groundwater at levels that could
16 adversely affect human health and the environment.

17 RAOs for site-related groundwater include:
18

- 19 • Prevent off-site migration of COPCs at levels that could adversely
20 affect flora and fauna;
- 21 • Prevent lateral and vertical migration of COPCs at levels that could
22 adversely affect potential and existing drinking water supply aquifers;
23 and
- 24 • Prevent seepage of groundwater from the site that would result in
25 surface water concentrations in excess of ambient water quality
26 standards.

27 No RAOs are developed for surface water because it is impractical to remediate this
28 medium directly. Rather, surface water contamination is addressed by proactive RAOs in
29 other media (see soils and groundwater RAOs). RAOs are not developed for sediments
30 because of minimal site impacts.

31 2.3 APPROACH TO CLEANUP GOAL DETERMINATION 32

33 To determine cleanup goals, tables of candidate cleanup criteria are developed and
34 evaluated. A table is developed for each contaminated medium, where ARARs, TBCs, and
35 site-specific risk values are presented for every contaminant found at the Fort Devens
36 Functional Area II sites. These values are then compared, and the appropriate value selected
37 as candidate cleanup goals, according to logic documented for each table. Figure 2-1 shows a
38 generalized approach to selecting cleanup goals. Background values are considered during
39

1 this process (generally, cleanup goals are not set to levels below background). These
2 candidate goals are then compared to the highest values obtained at the sites for each
3 contaminant. For those contaminants whose maximum concentration is above the candidate
4 goals, the candidate goal is retained as the cleanup goal. For those compounds which are
5 found exclusively below the candidate goal, no further action is warranted, and no cleanup
6 goal is set. Once the cleanup goals are set, the analytical data and the fate and transport
7 conclusions from the RI are reviewed to define the extent of contaminated media that requires
8 remediation.

9

10 2.4 SOILS

11

12 2.4.1 ARARs

13

14 The only ARAR identified for soils is the Toxic Substance Control Act (TSCA)
15 requirement for the remediation of soils contaminated with PCBs. Under 40 CFR
16 761.125(c)(4), soil contaminated with PCBs in unrestricted access areas are required to be
17 treated or removed such that the PCB concentration in the upper 10 inches of soil is less than
18 1 mg/kg, and the concentration below this depth is less than 10 mg/kg. These requirements
19 are considered relevant and appropriate for surface and subsurface soil, respectively.

20

21 2.4.2 TBCs

22

23 Four categories of TBCs have been identified for the Group 1B sites. These are the
24 EPA Region III RBC values, Resource Conservation and Recovery Act (RCRA) corrective
25 action levels, the interim EPA guidance on Soil Lead Concentrations, and background
26 concentrations. Each of these is discussed below.

27

28 2.4.2.1 RBCs

29

30 The RBCs are listed in the "Risk-Based Concentration Table, January-June 1995"
31 published by the EPA Region III. Although this site is in Region I, these values may be
32 considered as candidates for establishing cleanup goals. These risk based concentrations have
33 been calculated by Region III for nearly 600 chemicals. Toxicity constants from the EPA's
34 Health Effects Assessment Summary Table (HEAST) are combined with standard (i.e., not
35 site-specific) exposure scenarios to calculate chemical concentrations corresponding to a
36 lifetime cancer risk of 10^{-6} or an HI of 1, which ever occurs at a lower concentration. As
37 these represent generic exposure scenarios, they are not intended to be used directly as
38 cleanup goals. However, in the absence of other criteria, they may be considered as
39 candidates for cleanup criteria.

40

41 2.4.2.2 RCRA Corrective Action Levels

42

43 The proposed RCRA corrective-action regulations were published in 55 Federal
44 Register (FR) 30798, 27 July 1990 (USEPA 1990) as the table "Examples of Concentrations
45 Meeting Criteria for Action Levels" in Appendix A of the FR citation. In this Appendix, a
46 number of "action levels" for contaminants in soils, including contaminants found at Fort

1 Devens Functional Area II sites, are identified. For purposes of this remediation goals
2 evaluation, these action levels have been identified as TBCs for soils. Although these
3 regulations by definition are intended to establish the need for a RCRA corrective measures
4 study (rather than final cleanup goals), they are the most comprehensive listing of risk-based
5 values for soils available, and thus are regarded as TBCs.

6

7 2.4.2.3 EPA Guidance on Soil Lead Concentrations

8

9 EPA has also published *Revised Interim Soil Lead Guidance for CERCLA Sites and*
10 *RCRA Corrective Action Facilities*, EPA OSWER Directive No. 9355.4-12, July 1994. This
11 guidance established a health-based lead soil screening value of 400 mg/kg in a residential
12 area with children. This guidance was developed using the integrated exposure uptake
13 biokinetic (IEUBK) model for exposure of children to lead and is likely to be more
14 conservative than necessary at sites not frequented by children. This guidance contains no
15 values for strictly adult-exposure scenarios.

16

17 2.4.2.4 Background Concentration

18

19 Also included in the TBC category are background concentrations. These are
20 concentrations of chemicals found in areas known not to be contaminated by site activities. In
21 general (though not exclusively), background concentrations are applicable only to metals.
22 Background concentrations have been calculated for Fort Devens soil from 33 samples:
23 Soil-1 through Soil-20 (August 1991), BKS-21 through BKS-30 (June 1993) and 25S-92-10,
24 25S-92-12, and 25S-92-13 (October 1992) (E & E 1994). Background concentrations were
25 not considered with other TBCs in the selection of cleanup goals. Rather, the candidate
26 cleanup goal was never set below background (see Section 2.4.4).

27

28 2.4.3 Site-Specific Human Health Risks

29

30 A site-specific human health risk assessment was conducted as part of the RI. From
31 this assessment, concentrations can be calculated that correspond to carcinogenic health risks
32 in the range of 10^{-4} to 10^{-6} and/or HIs of 1. The risk assessment examined all chemicals (for
33 which slope factors and/or reference doses exist) detected at the Group 1B Functional Area II
34 sites, and calculated carcinogenic and systemic risks for each. Risks above the threshold
35 values were found. Quantitative values were calculated for risks corresponding to a 10^{-5}
36 cancer risk and an HI of 1 for Main Post soils.

37 Risk-based cleanup levels were calculated by solving for the concentration that
38 corresponds to a 10^{-4} to 10^{-6} estimated excess cancer risks or a hazard quotient equal to 1.0
39 using site-specific risk estimates and exposure point concentrations developed in the human
40 health risk assessment:

$$RBCL = (\text{Target Risk}) \frac{EPC_{site}}{R_{site}}$$

Feasibility Study: Fort Devens FA II
Section No.: 2
Revision No.: 2
Date: January 1997

1 Target Risk = 10^{-4} to 10^{-6} for carcinogens, 1 for systemic toxicants (unitless).
2 EPC_{site} = exposure point concentration derived from site data ($\mu\text{g/g}$).
3 R_{site} = medium-specific risk value for the EPC_{site}, exposure routes for each
4 medium are summed. For example, risks associated with dermal contact
5 are summed with risks associated with soil ingestion to obtain a total risk
6 value for soil (unitless).
7 RBCL = risk-based cleanup level ($\mu\text{g/g}$).
8

9 2.4.4 Selection of Cleanup Goals 10

11 Table 2-1 presents the criteria discussed above for the Main Post. The following
12 procedure was used to select the appropriate values. For all contaminants except PCBs, the
13 values calculated from the risk assessment were used as candidate cleanup goals. For PCBs,
14 an ARAR existed from TSCA and was selected as the cleanup goal. For any compounds that
15 were not addressed by either of these sources, the lower value of the EPA Region III RBCs or
16 the RCRA corrective action levels was selected as the candidate cleanup goal. If the possible
17 candidate cleanup goal selected by the above procedure was below the background
18 concentration, then the background concentration was selected as the candidate cleanup goal.
19

20 Once these candidate cleanup goals were identified, they were compared to the
21 maximum value for each contaminant identified at the Main Post area. If the maximum value
22 observed was less than the candidate cleanup goal, then no areas require remediation, and no
23 cleanup goal needs to be set for that contaminant. If the maximum concentration detected was
24 above the candidate cleanup goal, then the candidate cleanup goal became the cleanup goal.
25

26 2.5 GROUNDWATER REMEDIAL ACTION OBJECTIVES 27

28 There are several ARARs and TBCs that apply to groundwater at the Fort Devens
29 sites. EPA has defined, as guidance, three levels of groundwater. Classes I and II represent
30 current or potential drinking water sources. Class III represents groundwater that is
31 unsuitable for human consumption (e.g., is very saline) and does not have the potential to
32 affect drinkable water (*EPA Guideline for Groundwater Classification* final draft, December
33 1986, referenced in 55 FR 8732). The Main Post groundwater, which potentially is within
34 the zone of influence of groundwater extraction wells, would be classified as Class I or II.
35 For these types of groundwaters, several Federal ARARs would apply.
36

37 2.5.1 Main Post Groundwater Cleanup Goals 38

39 2.5.1.1 ARARs 40

41 Main Post groundwater ARARs include MCLs and MCLGs set by the Safe Drinking
42 Water Act, and Massachusetts MCLs (MMCLs) and secondary MCLs (MA SMCLs). The
43 Federal ARARs were originally intended to apply to water within drinking water distribution
44 systems. However, the NCP sets MCLs and non-zero MCLGs as ARARs for potential or
45 actual drinking water sources (40 CFR 300.430(e)(2)(i)(B)). The MMCLs and MA SMCLs

1 are essentially identical to the Safe Drinking Water Act (SDWA) MCLs with a few
2 exceptions.

3
4 **2.5.1.2 TBCs**

5 Several TBCs have also been identified as candidate cleanup goals for the Main Post
6 sites. These include SDWA secondary MCLs (SMCLs), EPA Office of Drinking Water
7 Health Advisories (HAs), EPA Region III tap water criteria, MDEP Office of Research and
8 Standards Guidance (ORSG) for chemicals for which MMCLs have not been promulgated,
9 and background values. SMCLs are not legally enforceable and address mainly non-health-
10 related issues such as odor or taste. The HAs and Region III criteria are developed using a
11 risk approach, with generic exposure scenarios. Background values are also included as
12 TBCs. In general, it is not necessary to remediate groundwater to below background levels.

13
14
15 **2.5.1.3 Site-specific Human Health Risks**

16 Using site-specific exposure scenarios, a risk assessment was performed for the Main
17 Post groundwater. From the results of this assessment, contaminant concentrations corre-
18 sponding to a carcinogenic risk of 10^{-5} and/or an HI of 1 (which ever is lower) have been
19 calculated.

20
21
22 **2.5.1.4 Selection of Main Post Cleanup Goals**

23 The ARARs, TBCs, and health risk values discussed above are presented on Table
24 2-2. Where available, the most stringent of the ARARs was picked as a potential candidate
25 cleanup goal. If no ARAR was available, the site-specific risk value was selected as a
26 potential candidate cleanup goal. If neither of these options was available for a given
27 compound, then the most stringent of the HAs, Region III tap water criteria, or the MA
28 ORSGs, was picked as the potential candidate cleanup goal. If any concentration selected by
29 this process was below background concentrations, then the candidate cleanup goal was set at
30 background instead. Finally, the candidate cleanup goals were compared against the
31 maximum observed concentration for each compound. If the concentration was found to be
32 above the candidate cleanup goal, then the candidate cleanup goal became the cleanup goal.
33 If the candidate cleanup goal was above the maximum observed concentration, then no
34 cleanup goal was set for that compound. For inorganic contaminants, data from filtered
35 samples were used in the development of cleanup goals. This was done to distinguish
36 between the naturally-occurring mineral presence of metals and dissolved contamination.

37
38
39 **2.6 SURFACE WATER REMEDIAL ACTION OBJECTIVES**

40 Three ARARs have been identified for surface water at the Group 1B sites. These
41 ARARs are all ambient water quality criteria (WQC) established under the Clean Water Act
42 (CWA). There are four categories of standards set under the CWA. These are for direct
43 ingestion, consumption of aquatic organisms, acute toxicity to aquatic organisms, and chronic
44 toxicity to aquatic organisms. The surface water at the sites is the Nashua River, and feeder
45 streams and ponds such as Willow Brook and Plow Shop Pond. These water bodies are
46

1 classified as Class B water bodies by the Massachusetts water quality regulations (314 CMR
2 4.06). Class B streams are designated as a habitat for fish, other aquatic life, and for primary
3 and secondary recreation. They may also be suitable for use as a source of public water
4 supply, providing appropriate treatment is used. Although some incidental ingestion of water
5 may occur during primary contact recreation, in general, class B waters will not be subject to
6 regular ingestion. Thus, human ingestion WQCs are not considered applicable or relevant
7 and appropriate requirements. The remainder of the WQCs established by the CWA would,
8 however, be appropriate. These ARARs are listed in Table 2-3. The strictest of these
9 ARARs that are not below background concentrations are established as the candidate cleanup
10 goals. The candidate cleanup goals are compared to the maximum observed concentrations;
11 any candidate cleanup goals that are less than the maximum observed concentrations are
12 established as the cleanup goals.

13 2.7 COMPARISON OF DATA TO CLEANUP GOALS

14 2.7.1 Definition of Operable Units

15 Operable units are components of an overall site that can be addressed individually,
16 either as separate areas or as separate media in the same general area. Based on the
17 comparison of the chemical data to the cleanup goals, seven separate operable units in three
18 areas are defined for the Fort Devens sites. The three areas are the DRMO Yard, the UST
19 13 area, and the POL Storage Area. The UST 13 area was considered part of the DRMO
20 Yard during the RI, but because it is hydraulically and physically isolated from the DRMO
21 Yard, it is considered a separate area in the FS. Soil and groundwater operable units are
22 present within each area. The seventh operable unit is DRMO Yard surface water.

23 2.7.2 Areas Exceeding Cleanup Goals

24 The cleanup goals developed have been screened against the contaminant levels found
25 during previous investigations. This comparison provides a description of the areas at the
26 Group 1B sites that require remediation. Samples from both the RI and the site investigation
27 (SI) are included in this evaluation. The inclusion of SI data provide better definition of the
28 extent of contamination at many areas, especially at the DRMO Yard (using the SI surface
29 samples). Areas exceeding cleanup goals, and potentially requiring remediation, are discussed
30 below for each operable unit.

31 2.7.2.1 UST 13 Soils

32 The soil at the UST 13 area showed one sample with lead at over 1,000 mg/kg, and
33 another sample with arsenic at 120 mg/kg, both above cleanup goals. It should be noted that
34 additional soils were excavated from the UST 13 area after these samples were taken. These
35 sporadic detections do not warrant the development of remedial alternatives.

1 **2.7.2.2 UST 13 Groundwater**

2
3 At the DRMO UST area, 1,2-, 1,3-, and 1,4-dichlorobenzene, Aroclor 1260, DDT,
4 1,2-DCE, and TCE have been found to exceed groundwater standards near the location of the
5 former (now removed) waste oil UST 13. These compounds exceeding standards were found
6 in samples from monitoring wells 32M-92-04X and 32M-92-06X. In addition, benzene was
7 detected just below its MCL in 32M-92-06X. This plume has not migrated far, because it is
8 present in a low permeability bedrock aquifer which has a very low hydraulic gradient. The
9 groundwater will be considered for remediation of these contaminants.

10
11 Although bis(2-ethylhexyl)phthalate was detected in one well at approximately seven
12 times the groundwater standard, it is believed that this contamination is due to sample
13 handling.

14
15 Metals, including arsenic and iron, were detected in filtered samples at the UST area
16 above groundwater standards. It appears that arsenic reflects residual impacts from the
17 former UST activities; however, these impacts do not appear to extend off site. Iron
18 exceeded its cleanup goal in filtered samples, but at far lower concentrations than in unfiltered
19 samples. This was the case in general indicating the natural presence of iron. Furthermore,
20 based on the risk assessment, iron does not pose a risk to human health. These metals,
21 therefore, will not be considered for remediation.

22 **2.7.2.3 DRMO Soils**

23
24
25 At the DRMO Yard, there were several miscellaneous exceedances of cleanup goals
26 for a wide variety of chemicals at the northern perimeter, and on the surface of the asphalt
27 yard (Figure 2-2). Lead was the most consistently detected contaminant, at levels up to 2,260
28 mg/kg in SI samples. Cadmium was detected above cleanup goals in three soil samples taken
29 during the SI, to a maximum of 78.0 mg/kg. PCBs were also rather widespread in the SI soil
30 samples, with concentrations of individual congeners of up to 5.22 mg/kg as well as in asphalt
31 samples (up to 9.3 mg/kg). DDT and its degradation products DDD and DDE were detected
32 above cleanup goals in two samples in the northeast corner of the DRMO east yard.

33
34 There are also two detections of arsenic above the cleanup goals. The cleanup goal is
35 set at the human health risk level of 24 mg/kg. Neither of the detections (33 and 37 mg/kg)
36 is much above this value. The consistency of arsenic detections in the 10 to 20 mg/kg range
37 detections, suggests that they represent normal background arsenic levels. Furthermore, these
38 concentrations represent a conservative risk estimate of just above 10^{-5} (which is in the EPA's
39 acceptable risk range of 10^{-4} to 10^{-6}). Thus the areas to be remediated do not need to
40 necessarily include the areas with arsenic detections. However, most areas where arsenic was
41 detected would be addressed because of lead and/or PCB contamination.

42
43 The total estimated volume of contaminated soil requiring remediation at the DRMO
44 Yard was determined, based on the comparison of data to soil cleanup goals and on the extent
45 of contamination presented in the RI, to be approximately 1,300 cubic yards (see Figure 2-3).
46 There are four smaller areas which make up this total contaminant volume. The soils of the

1 southwestern portion of the tire storage area (adjacent to the northern border of the DRMO
2 Yard) accounts for approximately 500 of the 1,300 total cubic yards of contaminated soils.
3 The soils of the center portion of the east DRMO Yard account for approximately 330 cubic
4 yards. The soils of the drainage swales along the western and eastern edges of the DRMO
5 Yard account for approximately 220 and 250 cubic yards, respectively, of the total volume of
6 contaminated soil. The depth of soil contamination in each of these four areas is estimated to
7 be one foot. DRMO soils will be considered for remediation.

8

9 2.7.2.4 DRMO Groundwater

10

11 Two wells located just north of the DRMO Yard were found to contain manganese at
12 7,000 to 7,700 $\mu\text{g/L}$ in filtered samples. However, these are upgradient wells, and thus
13 considered background. Three wells, located between the DRMO yard and the POL area
14 were found to contain low levels of TCE. Only one well, POL-3 exceeded the cleanup goal
15 of 5 $\mu\text{g/L}$ with detections of 15 to 19 $\mu\text{g/L}$. Although it is apparent that these contaminants
16 came from the DRMO Yard, there is no apparent continuing source, nor does TCE appear in
17 downgradient wells. DRMO groundwater will be addressed by the remedial alternatives, and
18 continued monitoring of downgradient wells will be maintained to observe intrinsic natural
19 remediation, and to ensure that cleanup goals will be met in the future.

20

21 2.7.2.5 DRMO Surface Water

22

23 Surface water at the main post was found to exceed cleanup goals for cadmium,
24 copper, lead, and zinc. It is, however, not generally appropriate to remediate surface water.
25 Rather, addressing the source of contamination is more appropriate. This "surface water" is,
26 in fact, not truly surface water, but drainage runoff flow from the DRMO Yard. Addressing
27 contamination at the DRMO Yard soils would improve the quality of the main post "surface
28 water." The surface water will not be considered for remediation.

29

30 2.7.2.6 POL Soils

31

32 Isolated hits of arsenic were detected at several different POL Storage Area soil
33 locations. However, only one greatly exceeded the cleanup goals, and no pattern or source of
34 contamination is apparent. These hits include arsenic at a surface concentration of 210 mg/kg
35 150 feet southeast of the intersection of Cook and Antietam Streets, a low detection of 21 to
36 27 mg/kg just east of the removed USTs, and a very deep (33 feet) detection of arsenic
37 adjacent to Building T-247 of 2 to 4 mg/kg. As these detections were isolated and/or only
38 marginally above cleanup goals, no remedial action program will be developed.

39

40 2.7.2.7 POL Groundwater

41

42 Three wells at the POL Storage Area were found to have concentrations in filtered
43 samples above cleanup goals of several naturally occurring metals, specifically, aluminum,
44 iron, and sodium. The sodium was detected above its cleanup goal in wells near Antietam
45 Street, and is expected to be due to street salting in the winter. This is an ongoing operation
46 not subject to regulation, and thus cleanup would not be directed toward this element. Iron

1 and aluminum are naturally occurring compounds, although they are not always detected
2 above their cleanup goals in other wells on site. Iron is not a hazardous metal, and cleanup
3 levels are set for aesthetic reasons (i.e., taste). As it is not considered to be a site
4 contaminant, its cleanup will not be addressed. Aluminum, another naturally occurring metal,
5 was also detected in one sample above its cleanup goal at the POL Storage Area. Its cleanup
6 level is set at the background concentration of 390 $\mu\text{g}/\text{L}$. The POL Storage Area exceedance
7 of 446 $\mu\text{g}/\text{L}$ is judged to be within the realm of background concentrations. Thallium was
8 detected in one well at 1.0 $\mu\text{g}/\text{L}$, just above the cleanup goal of 0.5 $\mu\text{g}/\text{L}$. However, this
9 cleanup goal is based on an MCL goal (the MCL is 2). Regardless, it is not appropriate to
10 develop remedial alternatives for such an isolated hit.

11 A possible explanation as to why naturally occurring metals were slightly higher at
12 the POL Storage Area is from dissolution due to lower pH. Lower pHs were found in wells
13 43SA93-06X (as low as 4.74), 43SA93-04X (to 5.31), 43SA93-07X (to 5.64), and 43SA93-
14 08X (to 5.16). These wells had the highest dissolved metals concentrations. The low pHs
15 found may be the result of past anaerobic degradation of hydrocarbons released at the POL
16 area prior to UST removal. These compounds degrade to organic acids, which reduce the pH
17 of the groundwater.

18 Two wells in the center of the POL area had 1,3,5-TNB concentrations of 2.18 and
19 3.04 $\mu\text{g}/\text{L}$, slightly above the TBC-based cleanup goal of 1.8 $\mu\text{g}/\text{L}$. One well downgradient
20 of the POL Storage Area had a detection of 1,3-DNB above its cleanup goal (also TBC-based)
21 and extremely elevated chlorides (600 to 800 mg/L). DDT and α -BHC were detected above
22 cleanup goals in the same well. This well, approximately 950 feet downgradient of the POL
23 Storage Area, appears to be in a distinct area of contamination from unknown sources, but
24 certainly unrelated to the POL area. Regardless of the source of contamination, these
25 exceedances are not significant enough to warrant a remedial program for this groundwater.
26 However, the groundwater under the POL/DRMO Yard will be addressed as a separate
27 operable unit, to ensure that intrinsic remediation will be demonstrated and cleanup goals are
28 attained.

31 32 2.8 ACTION-SPECIFIC AND LOCATION-SPECIFIC ARARS

33 Depending on which remedial actions are selected and conducted at the Main Post
34 sites, several action-specific and location-specific ARARs may require consideration. Action-
35 specific ARARs are requirements that may be triggered by certain remedial actions. Potential
36 action-specific ARARs include TSCA regulations regarding handling of PCB-contaminated
37 soil, and the Massachusetts National Pollutant Discharge Elimination System (NPDES)
38 program requirements for discharges of treated water to surface water.

39
40 TSCA (40 CFR 761.60(a)(4)) requires that soil contaminated with PCBs at concentra-
41 tions of 50 mg/kg or greater be disposed of in either a TSCA-permitted landfill, incinerator,
42 or by some alternative method that achieves a level of performance equal to incineration. Soil
43 samples taken during the RI did not reveal any concentrations above this level. However,
44 higher concentrations may conceivably be encountered during a remedial program. If such
45 soils are found and excavated, TSCA disposal/treatment standards would be applicable.

1 The Massachusetts Surface Water Discharge Permit Rules (314 CMR 3), regulate the
2 discharges to State waters, including wetlands. Any alternative that would include extraction,
3 treatment, and discharge of groundwater, or generates an aqueous waste stream of any type
4 that is to be discharged to surface water, must comply with these regulations.

5 Other action-specific ARARs may apply depending on the nature of the remedial
6 approach. For example, technologies that produce an offgas would be required to meet the
7 requirements of the Massachusetts Air Pollution Control Regulations (310 CMR 7) for air
8 pollution sources. These and other action-specific ARARs specific to certain technologies will
9 be discussed in the Detailed Analysis of Alternatives (Section 5).

10 Location-specific ARARs are similar to action-specific ARARs in that they only apply
11 when remedial action is being undertaken. However, these ARARs are invoked by the nature
12 of the location of action, rather than type of action. The principal location-specific ARARs
13 include restrictions on activities in floodplains and wetlands, wildlife protection, endangered
14 species protection, and archaeological and cultural resources protection. These location-
15 specific ARARs are summarized in Table 2-4.

16 2.9 CONCLUSIONS

17 Cleanup objectives have been developed from the ARARs, TBC guidance, and risk
18 assessment results as discussed in the previous sections. The previous sections review all
19 detected analytes which exceed cleanup goals, and discuss the patterns of contamination.
20 Remedial alternatives need to be developed for two of the operable units discussed in Section
21 2.7.2.

22 The first operable unit is soils located in and around the DRMO Yard. The
23 contaminants are diverse in this area, but are located near each other and are apparently from
24 the same source — materials stored in the yard. Specifically, cadmium, lead, PCBs, DDT,
25 DDD, and DDE are present above cleanup goals in the northern half of the east yard and the
26 swales on either side of the east yard (Figure 2-2).

27 The second operable unit is the groundwater in the area of the removed UST 13. The
28 contamination consists of 1,2-, 1,3-, and 1,4-DCB, PCB 1260, DDT, 1,2-DCE, and TCE
29 which leaked from this UST and contaminated groundwater in its vicinity. No contaminated
30 soil remains in this area. This area is apparently hydraulically and physically isolated from
31 the rest of the DRMO Yard, and thus is addressed as a separate operable unit.

32 The third operable unit is the groundwater under and downgradient of the DRMO
33 Yard proper (on either side of Cook Street) and the POL Storage Area. These are contiguous
34 and groundwater originating on the DRMO Yard discharges through the POL Storage Area.

35 Remedial alternatives are developed in Section 4 to address the contamination in these
36 operable units only. In the other operable units, there either are no exceedances of cleanup
37 goals, or the exceedances that exist do not warrant remedial action, as discussed in Section
38 2.7.2. Specifically, in AOC 43A the identified risks in soils are due to arsenic and PAHs and

Feasibility Study: Fort Devens FA II

Section No.: 2

Revision No.: 2

Date: January 1997

1 in groundwater the identified risk is due to beryllium. Based on the highly sporadic nature of
2 these detections, these "contaminants" are clearly associated with ambient conditions and not a
3 contaminant source. The time and expense required to implement a remedial program for a
4 non-existent source is clearly unwarranted, but organic contaminants in groundwater wells in
5 and around the site are clearly related to site activities and will be addressed.





Figure 2-1 GENERALIZED APPROACH TO SELECTING CLEANUP GOALS






Figure 2-3 PROPOSED SURFACE SOIL REMEDIATION AREAS AT DRMO YARD

Table 2-1
MAIN POST SOIL CLEANUP GOAL DETERMINATION

Analytes	ARARs		TBCs			Human Health Risk Assessment Levels Corresponding to 10^{-3} risk or $HI=1$	Candidate Cleanup Goal	Maximum Observed Concentration		Cleanup Goal			
	TSCA		Reg. III RBC Commercial/Industrial Levels	RCRA Action Levels (Residential)	EPA Interim Cleanup Level Superfund Sites			Surface Soil		Subsurface Soil			
	Surface Soil	Subsurface Soil						$\mu\text{g/g}$ (b)	$\mu\text{g/g}$ (c)	$\mu\text{g/g}$ (d)	$\mu\text{g/g}$ (e)		
Inorganics													
Aluminum			1000000			18000		1000000		10000	14000		
Antimony			820	6		0.5		40	3.5	23			
Arsenic			3.3	80		19	24(f)	24	210	37	24		
Barium			140000	800		54		800	98	210			
Beryllium			1.3	0.2		0.81	1000(f)	1000	0.68	1.2			
Cadmium			1000	8		1.3		8	78	6.5	8		
Calcium						810			5200	4100			
Chromium (total)			10000			33		10000	36	54			
Cobalt			120000			4.7		120000	38	7.6			
Iron						18000			24000	3400			
Copper			76000			14		76000	52	380			
Lead						400	48	426(g)	426	2260	980		
Magnesium						5500					426		
Manganese			10000	1600(k)		380		1600	530	450			
Mercury			610	4(inore)		0.11	47(g)	47	0.23	0.34			
Nickel			41000	4000		15		4000	36	58			
Potassium						24000			1700	3300			
Selenium			10000	40-80		1							
Silver			10000	40		0.086		40	5.4	1.7			
Sodium						230			750	372			
Vanadium			14000	1200(l)		32		120	34	32			
Zinc			610000	32000(l)		44		3200	260	980			
Volatile Organics													
Carbon Disulfide			200000					200000		0.13			
Decane										0.71			
2,4-Dimethylpentane										1.5			
2,3,4-Trimethylpentane										3.1			
Total Xylenes			1000000					1000000		0.12			
TPHC													
Total Petroleum Hydrocarbons									27500	21000			
Pesticides/PCBs													
alpha-Benzenethachloride			0.91						0.91	0.011			
alpha-Benzenedithiosulfan			12000						12000	0.006			
Aldrin			0.34						0.34	0.001			
beta-Benzenethachloride			3.2						3.2	0.045			
delta-Benzenethachloride										0.005			
DDD			24	3					3	0.018	3		
DDE			17	2					2	0.4	2		

Table 2-1
MAIN POST SOIL CLEANUP GOAL DETERMINATION (continued)

Analytes	ARARs		TBCs			Human Health Risk Assessment Levels Corresponding to 10^{-5} risk or HI = 1	Fort Devens Background Level (Maximum)	Surface Soil	Subsurface Soil	Soil	Cleanup Goal						
	TSCA		Reg. III RBC Commercial/Industrial Levels	RCRA Action Levels (Residential)	EPA Interim Cleanup Level Superfund Sites												
	Surface Soil	Subsurface Soil															
	$\mu\text{g/g (a)}$	$\mu\text{g/g (a)}$															
DDT			17	2		0.12		2	2.9	5.6	2						
gamma-Chlordane			4.4	0.5				4.4	0.005		2						
gamma-BHC (Lindane)			4.4					0.5	0.003	0.002							
Hepachlor			1.3					1.3		0.01							
Hepachlor epoxide			0.63					2.63		0.006							
PCB1254	1	10	41	0.09		2(f)	1	9.3	0.23	1							
PCB1260	1	10	0.74	0.09		2(f)	1	4.35	0.68	1							
BNAs																	
Benzo[A]anthracene			7.8			7(f)	7	2									
Benzo[A]pyrene			0.78			7(f)	7	2									
Benzo[B]fluoranthene			7.8			7(f)	7	2									
Benzo[G, H, I]perylene								2									
Benzo[K]fluoranthene			78			78		0.14									
Chrysene			780			7(f)	7	3									
Dibenzofuran								4.5									
1,6-Dimethylindan									0.27								
4,6-Dimethylindan									0.21								
Fluoranthene			82000			82000		4									
Fluorene			82000			82000		0.7									
Heptadecane								0.27									
Hexadecane									0.18								
Indeno[1,2,3-C,D]pyrene			7.8			8(f)	8	2									
2-Methylnaphthalene								30	10								
Naphthalene			82000			82000		20		3							
Pentadecane									10	2							
Phenanthrene									61000	3							
Pyrene			61000														

Key:
(a) Toxic Substances Control Act (TSCA) (15 USC 2601) - The surface soil cleanup criterion is 1,000 $\mu\text{g/kg}$ and the subsurface soil cleanup criterion is 10,000 $\mu\text{g/kg}$.
(b) EPA Region III Risk-Based Concentration Table (USEPA 1995 January-June) values for commercial/industrial soil.
(c) Calculated RCRA CMS Action Level as outlined in 55FR30798-27 July 1990, corresponding to a hazard index of 0.2 in compliance with MDEP for residential soil.
(d) EPA Interim Guidance on Soil Lead Cleanup levels at Superfund Sites, EPA 1991, OSWER Directive 9355.4-02a, 29 August 1991.
(e) Background levels for soil derived from data compiled by E & E; (see Appendix K of the RI Report for Functional Area II (E & E 1994a) for background data rationale).
(f) Concentration corresponds to a cancer risk of 10^{-5} .
(g) Concentration corresponds to a hazard index of 1.
(h) Candidate cleanup goal was chosen as follows: Values calculated from the site-specific risk assessment, or ARARs, if available. If neither of these two values were available, the lowest value of the remaining TBCs was selected.
(i) Maximum observed concentration based on RI surface soil data collected from DRMO Yard and POL Storage Area.
(j) Maximum observed concentration based on RI soil borings data collected from DRMO Yard and POL Storage Area.
(k) Proposed standard.

Table 2-2
MAIN POST GROUNDWATER CLEANUP GOAL DETERMINATION

Analytes	ARARs						TBCs						Human Health Risk Assessment Levels Corresponding to 10 ⁻³ risk or HI = 1						Maximum Observed Concentration (µg/L) (m)	Candidate Cleanup Goal (µg/L) (j)	Cleanup Goal (µg/L) (n)
	SDWA MCL (a)	MMCL (b)	SDWA MCLG (c)	MA SMCL (d)	SDWA SMCL (e)	EPA Drinking Water HAs (f)	BPA Reg III Tap Water Risk-Based Concentration (g)	MA ORSG (h)	Fort Devens Background (i)	(µg/L) (j)	(µg/L) (k)	(µg/L) (l)	(µg/L) (m)	(µg/L) (n)	(µg/L) (o)	(µg/L) (p)	(µg/L) (q)				
Inorganics																					
Aluminum	50(2)					50/200	50/200			37000			390		390	446	446	390			
Arsenic	50(3)	50					0.02	0.038			3.4	1.6 (j)	50	56	56	50	50	50			
Barium	2000	2000	2000	4	4(4)		2000	2600			17		2000	2000	2000	64	64				
Beryllium	4						0.0008	0.016		4		0.67 (j)	4	4	0.13						
Calcium										27000											
Chromium (total)	100	100	100			100	180						100	100	100	28	28				
Cobalt										2200			2200	2200	2200	11	11				
Copper	1000(2)	1300(1)	1300	1000	1000		1400						1000	1000	1000	1.7	1.7				
Iron	300(2)			300	300					320			320	320	320	2800	2800	320			
Lead	15	15(1)	0							77(k)			15	15	15	2	2				
Magnesium										2600						3200	3200				
Manganese	50(2)			50	50		100	730	100	180	3500	5000(k)	3500	3500	3500	7700	7700	3500			
Nickel	100	100(4)	100										100	100	100	13	13				
Potassium										4300						29000	29000				
Sodium		28000(4)				20000				28000	10000		28000	28000	28000	420000	420000	28000			
Thallium	2		0.5		0.4	0.4			2				0.5	0.5	0.5	1	1	0.5			
Zinc	5000(2)			5000	5000	2000	2000	11000	11000	30.2		5000	5000	5000	260	260					
Volatile Organics																					
Acetone	3000(4)							3700	3000				3000	3000	3000	52	52				
Benzene	5	5	0				1	0.36					5	5	5	4	4	5			
Chloroform	100(14)	50(4)					6	0.15	5				50	50	50	1.3	1.3				
1,2-Dichloroethane	5	5	0				0.4	0.12					5	5	5	1.8	1.8				
Total 1,2-Dichloroethene									55				55	55	55	60	60	55			
Ethylbenzene	700	700	700	1000	1000					700	1300		700	700	700	4	4				
Toluene	1000	1000	1000	200	200					1000	750		1000	1000	1000	3.6	3.6				
1,1,1-Trichloroethane	200	200	200	200	200					200	1300		200	200	200	60	60				
Trichloroethylene (TCE)	5	5	0						1.6			26(k)	26(k)	26(k)	5	5	5				
Total Xylenes	10000	10000	10000	10000	10000					10000	12000		10000	10000	10000	13	13				
TPHC																					
Total Petroleum Hydrocarbons																960000	960000				

Key at end of table.

Table 2-2 (continued)

MAIN POST GROUNDWATER CLEANUP GOAL DETERMINATION										
Analytes	ARARs			TBCs			Human Health Assessment Levels Corresponding to 10^{-5} risk or $HI = 1$ (g/L) (j,k)	Candidate Cleanup Goal (µg/L) (l)	Maximum Observed Concentration (µg/L) (m)	Cleanup Goal (µg/L) (n)
	SDWA MCL	MMCL	SDWA MCLG	MA SMCL	SDWA SMCL	EPA Drinking Water HAS				
Pesticides/PCBs	(a)	(b)	(c)	(d)	(e)	(f)	(g)	(h)	(i)	(j)
alpha-Benzenehexachloride							0.011		0.011	20
DDD	0.5	0.5					0.28		0.5	0.39
DDT	0.5						0.2		0.5	0.5
delta-Benzenehexachloride										3.3
PCB1260	0.5	0.5	0				0.0087			
Explosives								0.39(j)	0.5	7.6
2-Amino-4,6-dinitrotoluene										1.8
4-Amino-2,6-dinitrotoluene										1.9
Cyclonite (RDX)							2		26(j)	26
1,3-Dinitrobenzene							1	3.7		1
2,6-Dinitrobenzene							40		40	0.77
2-Nitroluene							61		61	3
3-Nitroluene							61		61	5.9
4-Nitroluene							61		61	1.3
1,3,5-Trinitrobenzene							1.8		1.8	3.04
BNAs										1.8
Acenaphthene							2200		2200	2.1
Bis(2-ethylhexyl)phthalate	6	6(4)	0				4.8	6	6	40
4,4'-butyldiethyl(2-(1,1-dimethylethyl)-5-phenol)										24
1,2-Dichlorobenzene	600	600					600	270		600
1,3-Dichlorobenzene							600	540		600
1,4-Dichlorobenzene	75	75					75	0.44		75
Di-N-butyl phthalate							3700		3700	4
2-Methylnaphthalene										40
Naphthalene							20	1500		20
Phenanthrene										20
1,2,4-Trichlorobenzene	70	70					70	190	70	40
Other Organics										100
Caprolactam										20
Lauric acid										20
Tetraosane										8

Key at end of table.

Key:

- (a) EPA Drinking Water Regulations (USEPA 1991c), MCLs, 40 CFR 143.
- (b) Massachusetts Drinking Water Standards and Guidelines (Massachusetts 1992) 310 CMR 22.
- (c) Maximum Contaminant Level Goal. Note: MCLs of zero are not considered ARARs in accordance with the NCP.
- (d) Secondary Maximum Contaminant Goal, Code of Massachusetts Regulations, Title 310 Section 22, Effective 20 November 1992.
- (e) National Secondary Drinking Water Standards designed to protect the aesthetic quality of water (FR 42198, 19 July 1979, 51 FR 11396, 2 April 1986; 56FR 3526, 30 January 1991).
- (f) EPA Office of Water Lifetime Health Advisories (HA), May 1993.
- (g) EPA Region III, Risk-Based Concentration Table (USEPA 1993 Fourth Quarter), values for tap water.
- (h) ORSG: Office of Research and Standard Guideline, Massachusetts Department of Environmental Protection, Spring 1993.
- (i) Background levels based on maximum or average detected in upgradient wells or local background concentration as follows: Arsenic and barium based on DRMO Yard local background. Calcium, Iron, Magnesium, Manganese, Potassium, Sodium, and Zinc based on PQL upgradient well.
- (j) Concentration based on cancer risk of 10^{-5} .
- (k) Concentration based on hazard index of 1.
- (l) Remedial action objective was chosen as follows: lowest of ARARs, if no ARARs, then human health risk assessment value. If risk not calculated, then lowest value of the TBCs. If TBC or ARAR was lower than background level, background was used.
- (m) Maximum observed concentration based on RI and SI groundwater data collected from DRMO and POL. Maximum observed concentration for metals is based on filtered data only.
- (n) Concentration based on hazard index of 1.
- (o) Action level.
- (p) Secondary standard.
- (q) Proposed standard.
- (r) Massachusetts Guidance value.

Table 2-3
MAIN POST SURFACE WATER CLEANUP GOAL DETERMINATION

ANALYTES	MA/CWA WQC Human Health, Consumption of Aquatic Organisms (µg/L) (a,b)	ARARs		Background Levels (µg/L) (b,d)	Candidate Cleanup Goal (ng/L) (e)	Maximum Observed Concentration (µg/L) (h)	Cleanup Goal (µg/L)
		Freshwater Acute MA/CWA WQC for Aquatic Organisms (µg/L) (b,c)	Freshwater Chronic MA/CWA WQC for Aquatic Organisms (µg/L) (b,d)				
Inorganics							
Aluminum		750		87	730	730	530
Antimony	4,300				3	4,300	5.8
Arsenic	0.14	360		190	6.7	6.7	2
Barium					40		20
Cadmium		0.50 (e)	0.27 (e)		4	4	15
Calcium				21,000			5,000
Copper		3.15 (e)	2.47 (e)		8.1	8.1	27
Iron				1,000	1,600	1,600	1,000
Lead		7.92 (e)	0.31 (e)		8.7	8.7	41
Magnesium					3,300		970
Manganese					360		77
Potassium					3,200		2,600
Sodium					36,000		3,000
Zinc		24.8 (e)	22.4 (e)		33	33	260

(a) Concentrations for potential carcinogens correspond to a risk of 10^{-6} .

(b) WQC = Water Quality Criteria from Code of Massachusetts' Regulation, Title 314, Section 4.05(5)(e)/Environmental Protection Agency, 57 FR 60848, 22 December 1992.

(c) One-hour average concentration not to be exceeded more than once every three years.

(d) Four-hour average concentration not to be exceeded more than once every three years.

(e) Water hardness dependent criteria site-specific value of 16 mg/L used.

(f) Background levels for surface water derived from data compiled by E & E.

(g) Remedial action objective chosen as follows: MA/CWA WQC Human Health if available; if not, then aquatic organism criteria were used. If background was higher than lowest ARAR value, background level was used. If background value was lower than ARAR, then ARAR was used.

(h) Maximum observed concentration based on RI surface water data collected from DRMO Yard.

Table 2-4

**LOCATION-SPECIFIC APPLICABLE OR RELEVANT AND APPROPRIATE REQUIREMENTS
FOR RI SITES AT FORT DEVENS**

Location Characteristic(s)	Operating Condition(s)	Requirement(s)	Citation(s)
Floodplains			
<ul style="list-style-type: none"> Within "lowland and relatively flat areas adjoining inland and coastal waters and other flood prone areas such as offshore islands, including at a minimum, that area subject to one percent or greater chance of flooding in any given year." [Executive Order 11988 § 6(c) and 40 C.F.R. § 6, Appendix A, § 4(d) (1992)] 	<ul style="list-style-type: none"> Federal agency action which involves: <ul style="list-style-type: none"> - acquiring, managing, and disposing of lands and facilities - providing federally undertaken, financed, or assisted construction and improvements. - conducting federal activities and programs affecting land use. 	<ul style="list-style-type: none"> Federal agencies shall take action to reduce the risk of flood loss, minimize the impact of floods on human safety, health and welfare, and restore and preserve the natural and beneficial values of floodplains. Federal agencies shall evaluate potential effects of actions in floodplains and ensure consideration of flood hazards and floodplain management. If action is taken in floodplains, federal agencies shall consider alternatives to avoid adverse effects, incompatible development, and minimize potential harm. - Applicable 	<ul style="list-style-type: none"> Executive Order 11988 40 C.F.R. § 6.302(b) (1992) 40 C.F.R. § 6, Appendix Mass. Gen. L. ^bCh. 131, § 40 (1990) Mass. Regs. Code tit. 310, § 10.00-10.60 (1989)
<ul style="list-style-type: none"> Land subject to flooding as defined in Mass. Regs. Code tit. 310, § 10.57(2) (1989) 	<ul style="list-style-type: none"> Activities within the area subject to flooding which involve removal, filling, dredging, or alteration of the area, as defined in Mass. Regs. Code tit. 310, § 10.04 (1989). Activities within 100 feet of land subject to flooding which would alter the area. 	<ul style="list-style-type: none"> Actions in "bordering land subject to flooding" shall provide compensatory storage for flood storage volume lost as a result of the project, shall not restrict flows so as to cause an increase in flood stage or velocity, and shall not impair its capacity to provide important wildlife habitat functions or alter vernal pool habitat. - Applicable Actions in "isolated land subject to flooding" shall not result in flood damage because of lateral displacement of water that would otherwise be confined within the area, adverse effects on water supply or groundwater supply, adverse effects on the capacity of the area to prevent groundwater pollution, or adverse effects on vernal pool habitat. - Applicable 	<ul style="list-style-type: none"> Mass. Regs. Code tit. 310, § 10.00-10.60 (1989)
Wetlands			
<ul style="list-style-type: none"> Presence of wetlands as defined in Executive Order 11990, § 7(c) and 40 C.F.R. § 6, Appendix A, § 4(i) (1992) 	<ul style="list-style-type: none"> Federal agency action which involves: <ul style="list-style-type: none"> - acquiring, managing, and disposing of lands and facilities - providing federally undertaken, financed, or assisted construction and improvements - conducting federal activities and programs affecting land use 	<ul style="list-style-type: none"> Whenever possible, federal agency actions must avoid or minimize adverse impacts on wetlands and act to preserve and enhance their natural and beneficial values. Agencies should particularly avoid new construction in wetlands areas unless there are no practicable alternatives. Federal agencies shall incorporate wetlands protection considerations into planning, regulating, and decision-making processes. - Applicable 	<ul style="list-style-type: none"> Executive Order 11990 40 C.F.R. § 6.302(a) (1992) 40 C.F.R. § 6, Appendix A (1992)

Table 2-4

LOCATION-SPECIFIC APPLICABLE OR RELEVANT AND APPROPRIATE REQUIREMENTS FOR RI SITES AT FORT DEVENS

Location Characteristic(s)	Operating Condition(s)	Requirement(s)	Citation(s)
<ul style="list-style-type: none"> Presence of wetlands as defined in 40 C.F.R. § 230.3(t) (1992) and 33 C.F.R. § 328.3(b)* 	<ul style="list-style-type: none"> Action involving discharge of dredge or fill material into wetlands 	<ul style="list-style-type: none"> Action must be taken to avoid degradation or destruction of wetlands to the extent possible. Discharge for which there are practicable alternatives with less adverse impacts or those which would cause or contribute to significant degradation are prohibited. If adverse impacts are unavoidable, action must be taken to enhance, restore, or create alternative wetlands. - Applicable 	<ul style="list-style-type: none"> Clean Water Act § 404 [33 U.S.C. § 1344 (1991)] <ul style="list-style-type: none"> 40 C.F.R. § 230 (1992) 33 C.F.R. § 320-330*
<ul style="list-style-type: none"> Presence of wetlands as defined in Mass. Gen. L. ch. 130, § 105 (1990) or Mass. Gen. L. ch. 131, § 40 (1990), or regulations pursuant to those statutes 	<ul style="list-style-type: none"> Landfills, land treatment unit, surface impoundment, or waste pile subject to regulation under Mass. Regs. Code tit. 310, § 30.800 (1989) Hazardous waste subject to regulation under Mass. Regs. Code tit. 310, § 30.000 (1989) 	<ul style="list-style-type: none"> Active portions of designated facilities cannot be constructed in, or expanded into, wetlands. - Applicable 	<ul style="list-style-type: none"> Mass. Regs. Code tit. 310, § 30.705(6) (1989)
<ul style="list-style-type: none"> Presence of any bank, freshwater wetland, coastal wetland, beach, dune, flat, marsh, meadow, or swamp bordering on the ocean or on any estuary, creek, river, stream, pond, or lake or any land under these waters or land subject to tidal action, coastal storm flow, or flooding 	<ul style="list-style-type: none"> Activities within a protected area which involve removal, filling, dredging, or alteration of the area Activities within 100 feet of a protected area which would alter the area. 	<ul style="list-style-type: none"> Removal, filling, dredging, or alteration of protected area is prohibited except under the conditions and criteria delineated in Mass. Regs. Code tit. 310, § 8 10.00-10.60(1989). - Applicable 	<ul style="list-style-type: none"> Mass. Gen. L. ch. 131, § 40 (1990) <ul style="list-style-type: none"> Mass. Regs. Code tit. 310, § 10.00-10.60 (1989)
<ul style="list-style-type: none"> Wilderness areas, wildlife resources, wildlife refuges, or scenic rivers 	<ul style="list-style-type: none"> Within wildlife refuge as designated in 16 U.S.C. § 668(dd)* -or- within range in which action could impact such an area 	<ul style="list-style-type: none"> Action which will impact wildlife refuges 	<ul style="list-style-type: none"> A refuge's administering agency and its appropriate regulations must be consulted to determine prohibited activities and possible exemptions <ul style="list-style-type: none"> The effects of actions on the values of the wildlife refuge must be considered. - Applicable
<ul style="list-style-type: none"> Within area affecting stream or river -and- presence of fish or wildlife resources 	<ul style="list-style-type: none"> Action which results in the control or structural modification of a natural stream or body of water 	<ul style="list-style-type: none"> The effects of water-related projects on fish and wildlife resources must be considered. <ul style="list-style-type: none"> Action must be taken to prevent, mitigate, or compensate for project-related damages or losses to fish and wildlife resources. Off-site actions which alter a resource require consultation with the FWS^c, NMFS^d, and/or the appropriate state agency. Consultation with the responsible agency is also strongly recommended for on-site actions. - Applicable 	<ul style="list-style-type: none"> National Wildlife Refuge System Administration Act of 1966 [16 U.S.C. § 668(dd)-668(e)*] Fish and Wildlife Coordination Act (16 U.S.C. § 661*) 40 C.F.R. § 6.302(g) (1992)

Table 2-4

**LOCATION-SPECIFIC APPLICABLE OR RELEVANT AND APPROPRIATE REQUIREMENTS
FOR RI SITES AT FORT DEVENS**

Location Characteristic(s)	Operating Condition(s)	Requirement(s)	Citation(s)
<ul style="list-style-type: none"> • Location encompassing aquatic ecosystem with dependent fish, wildlife, other aquatic life, or habitat 	<ul style="list-style-type: none"> • Action involving the discharge of dredge or fill material into aquatic ecosystem 	<ul style="list-style-type: none"> • Degradation or destruction of aquatic ecosystems must be avoided to the extent possible. Discharges which cause or contribute to significant degradation of the water of such ecosystem are prohibited. - Applicable 	<ul style="list-style-type: none"> • Clean Water Act § 404 [33 U.S.C. § 1344 (1991)] • 40 C.F.R. § 230 (1992) • 33 C.F.R. § 320-330*
<ul style="list-style-type: none"> • Presence of areas such as wetlands, etc., as listed in Mass. Regs. Code tit. 310, § 10.02(1) (1989), which due to their plant community composition and structure, hydraulic regime, or other characteristics, provide important food, shelter, migratory or overwintering areas, or breeding areas for wildlife 	<ul style="list-style-type: none"> • Activities within a protected area which involve removal, filling, dredging, or alteration of the area • Activities within 100 feet of a protected area which would alter the area 	<ul style="list-style-type: none"> • Actions which would have adverse effects on specific habitat characteristics and the important functions they serve are prohibited or regulated if they exceed certain threshold levels delineated in the regulations. - Applicable 	<ul style="list-style-type: none"> • Mass. Gen. L. ch. 131, § 40 (1990) • Mass. Regs. Code tit. 310, § 10.00-10.60 (1989)
Endangered, threatened or rare species		<ul style="list-style-type: none"> • Action involving discharge of dredge or fill material into aquatic ecosystem. 	<ul style="list-style-type: none"> • Dredge or fill material shall not be discharged into an aquatic ecosystem if it would jeopardize such species or would likely result in the destruction or adverse modification of a critical habitat of the species. - Applicable
<ul style="list-style-type: none"> • Presence of endangered or threatened species or critical habitat (see above citation) of same within an aquatic ecosystem as defined in 40 C.F.R. § 230.3(c) (1992) 	<ul style="list-style-type: none"> • Action which is likely to jeopardize species or destroy or adversely modify critical habitat 	<ul style="list-style-type: none"> • Actions which jeopardize species/habitat must be avoided or appropriate mitigation measures taken. • Off-site actions which affect species/habitat require consultation with DOI, FWS, NMFS, and/or state agencies, as appropriate, to ensure that proposed actions do not jeopardize the continued existence of the species or adversely modify or destroy critical habitat. • Consultation with the responsible agency is also strongly recommended for on-site actions. - Applicable 	<ul style="list-style-type: none"> • Endangered Species Act of 1973 (16 U.S.C. § 1531-1-1533*) • 40 C.F.R. § 402 (1989) • 40 C.F.R. § 6.302(h) (1992) • Fish and Wildlife Coordination Act (16 U.S.C. § 661*)
<ul style="list-style-type: none"> • Presence of endangered or threatened species -or critical habitat of such species as designated in 50 C.F.R. § 17 (1989), 50 C.F.R. § 226 (1989), or 50 C.F.R. § 227 (1989) 	<ul style="list-style-type: none"> • Action likely to alter significant habitat 	<ul style="list-style-type: none"> • Actions which alter significant habitat are prohibited if the alteration will likely reduce the viability of significant habitat. - Applicable 	<ul style="list-style-type: none"> • Mass. Gen. L. ch. 131A (1991) • Mass. Regs. Code tit. 321, § 10.00-10.61 (1992)
<ul style="list-style-type: none"> • Presence of endangered, threatened, or rare species or significant habitats of state-listed species as designated pursuant to Mass. Gen. L. ch. 131A (1991) • Presence of a protected resources area, as designated in Mass. Regs. Code tit. 310, § 10.02(1) (1989), which is part of the habitat of a state-listed species 	<ul style="list-style-type: none"> • Activities within a protected area which involve removal, filling, dredging, or alteration of the area • Activities within 100 feet of a protected area which would alter the area 	<ul style="list-style-type: none"> • Short or long term adverse effects on the habitat of the local population of the listed species are prohibited. 	<ul style="list-style-type: none"> • Mass. Gen. L. ch. 131, § 40 (1990) • Mass. Regs. Code tit. 310, 10.00-10.60 (1989)

Table 2-4

LOCATION-SPECIFIC APPLICABLE OR RELEVANT AND APPROPRIATE REQUIREMENTS
FOR RI SITES AT FORT DEVENS

Location Characteristic(s)	Operating Condition(s)	Requirement(s)	Citation(s)
Archaeological and historic resources			
• Presence of archaeological or historic resources	• Action involving dam construction or other alteration of terrain which might cause irreparable loss or destruction of significant scientific, prehistoric, historic, or archaeological data.	<ul style="list-style-type: none"> The Secretary of the Interior must be advised of the presence of such data. A survey must be conducted of affected areas for resources and data. Steps must be taken to recover, protect, and preserve data therefrom or DOI formally requested to do so. 	<ul style="list-style-type: none"> Archaeological and Historic Preservation Act [16 U.S.C. § 469(a)-469(c)*] 40 C.F.R. § 6.301 (1992) 32 C.F.R. § 650.181*
• Presence of federally owned, administered, or controlled prehistoric or historic resources -or- the likelihood of undiscovered resources		<ul style="list-style-type: none"> Cultural resources included on, or eligible for inclusion on, the National Register of Historic Places (36 C.F.R. § 60*) or National Historic Landmark Program (36 C.F.R. § 65*) must be identified. A determination must be made as to whether proposed action(s) will affect such resources and, if so, alternatives to the action(s) must be examined and considered. When alteration or destruction of the resource is unavoidable, steps must be taken to minimize or mitigate the impacts and to preserve records and data of the resource. When all or part of a remedial action is off site, the consultation requirements of 16 U.S.C. § 470(f)* must be completed. Consultation is also strongly recommended for on-site actions. 	<ul style="list-style-type: none"> National Historic Preservation Act [16 U.S.C. § 470(a)-470(w)*] Executive Order 11593 40 C.F.R. § 6.301 (1992) 36 C.F.R. § 800* 32 C.F.R. § 650.181*
• Presence of properties included on the State Register of Historic Places	• Action(s), as listed in 950 CMR 71.05, which impact state listed properties	<ul style="list-style-type: none"> All prudent means to eliminate, minimize, or mitigate adverse effects must be adopted.- Relevant and appropriate 	<ul style="list-style-type: none"> MGL c. 9, ss. 26-27C 950 CMR 71.00 <i>et seq.</i>

* Version of cited law or regulation used in the preparation of this document was that in effect in June, 1993.

^aMass. Regs. Code = Code of Massachusetts Regulations.^bMass. Gen. L. = Massachusetts General Laws.^cFWS = U.S. Fish and Wildlife Service.^dNMFS = National Marine Fisheries Service.^eDOI = Department of the Interior.

Source: Oak Ridge National Laboratory, 1994.

1
2
3 Feasibility Study: Fort Devens FA II
4 Section No.: 3
5 Revision No.: 2
6 Date: January 1997
7

8
9
10 **3. IDENTIFICATION AND SCREENING OF REMEDIAL ACTION TECHNOLOGIES**
11 **AND MONITORING REQUIREMENTS**
12
13
14

15 The purpose of this section is to identify and screen potential remedial action
16 technologies that may be applicable to remediation of soil and groundwater at Fort Devens
17 and to identify monitoring requirements. Each of the technologies identified in this section
18 was evaluated with respect to effectiveness and implementability to determine whether they
19 would be retained for further evaluation. In Section 4, those remedial technologies that are
20 retained are combined to form remedial action alternatives. Tables 3-1 and 3-2 summarize
21 these technologies.
22
23

24 **3.1 GENERAL RESPONSE ACTIONS**
25
26

27 The following general response actions have been identified for soil: no action,
28 institutional action, containment, excavation, ex situ treatment, in situ treatment, and disposal.
29 General response actions identified for groundwater include: no action, institutional action,
30 containment, collection, ex situ treatment, in situ treatment, and disposal. In the following
31 sections, technologies corresponding to each general response action are identified and
32 screened.
33
34

35 The contamination in the soils at the DRMO Yard includes PCBs, DDT, DDD,
36 DDE, lead, and cadmium. Groundwater contamination at UST-13 includes petroleum
37 hydrocarbons, chlorinated benzenes, TCE, 1,2-DCE, DDT, and PCBs. Although
38 groundwater contamination levels exceeding ARARs or TBCs are few and scattered in the
39 POL Storage Area/DRMO Yard, they do occur. POL-3, downgradient of the DRMO Yard,
40 showed low levels of TCE (up to 19 µg/L) and both 43MA93-04X and 43MA93-10X showed
41 elevated TPHC, while 43MA93-10X also showed 2-methylnaphthalene (30 µg/L). For these
42 reasons, the POL Storage Area/DRMO Yard will be considered a separate operable unit for
43 groundwater remediation. Therefore, the remedial action technologies presented in Sections
44 3.2 and 3.3 are screened only in reference to the soil contamination at the DRMO Yard, the
45 groundwater contamination in the UST 13 area, and the groundwater in the POL Storage
Area/DRMO Yard.

46 **3.2 SOILS**
47
48

49 **3.2.1 No Further Action**
50
51

52 The No Further Action alternative does not include any remedial action regarding soil
53 contamination. No Further Action will be retained and developed into a remedial alternative
54 as required by the NCP.
55

1 **3.2.2 Institutional Actions**

2 Institutional actions do not include the use of remedial technologies, but involve
3 actions taken to reduce the potential for exposure to the contaminated soils, such as fencing,
4 zoning, and deed restrictions. Institutional actions will be retained for further evaluation.

5 **3.2.3 Containment**

6 Containment, or capping, involves the placement of an impermeable material over the
7 contaminated area. This process prevents direct exposure to the soil itself, mobilization of
8 soil particles by surface flow, infiltration and subsequent leaching of standing water, and the
9 wind-induced mobilization of soil particles in air. Capping may be preferable when other
10 remedial actions (e.g., excavation, treatment, and disposal) are cost-prohibitive, particularly
11 when quantities are large. However, drawbacks of containment are the finite and uncertain
12 design life and the need for long-term maintenance. Nevertheless, these alternatives may be
13 less costly than excavation and treatment. Standard design practices specify permeabilities of
14 at most 10^{-7} centimeters per second (cm/sec) for the liner. Two types of caps exist, single-
15 and multi-layered. Because of their significant differences, they are discussed separately.

16 **3.2.3.1 Single-Layered Caps**

17 Several different single-layered techniques exist for the containment of contaminated
18 soils. All begin with clearing, grubbing, and grading the site. Then, one of several low-
19 permeable materials is applied. Examples include the spray application of a layer of asphalt;
20 base course and concrete slab; and the placement of a base course and an asphalt pavement.
21 All reduce infiltration and limit air-mobilization of particulates from the soil surface. They
22 require little material handling and a small labor-force, and are easy to implement. However,
23 they are not very reliable. Asphalt is susceptible to cracking from settlement and shrinkage.
24 It is photosensitive and tends to weather rapidly. Concrete is more durable and resistant to
25 chemical and mechanical damage. However, it is susceptible to cracking from settlement,
26 shrinkage, and frost heave. In general, single-layer caps are not reliable enough to be
27 acceptable unless frequent inspection and maintenance is performed. Because of these
28 limitations in effectiveness, they will not be retained for further discussion.

29 **3.2.3.2 Multi-Layered Caps**

30 Multi-layered caps are more common and are required for RCRA land disposal facilities.
31 After clearing, grubbing, and grading, the site is covered with an impermeable layer to
32 minimize infiltration and eliminate particulate emissions from the soil surface. Options
33 include a 24-inch-thick layer of compacted, low-permeability (10^{-7} cm/s) clay; a synthetic,
34 impermeable membrane; or a combination of the two (membrane over clay). If the membrane
35 is used, it must be overlain by a minimum 12-inch-thick layer of permeable sand to facilitate
36 drainage. The final layer is topsoil to control moisture, protect the integrity of the
37 impermeable layer and promote revegetation. These technologies are effective, and will be
38 durable for extended periods assuming proper design, installation, and maintenance. Both
39 clay and synthetic liners are less susceptible to cracking from settlement and frost heave.

1 Clay tends to be self-repairing, although maintenance may be required to prevent growth of
2 deep-rooted trees that could penetrate the seal. Synthetic membranes are less susceptible to
3 this problem, but are not self-repairing. In either method, a layer of gravel may need to be
4 added over the impermeable layer to prevent burrowing animals from compromising the cap.
5 These technologies can be very effective in reducing infiltration of water through
6 contaminated soils. They are also readily implementable. Thus, they will be retained for
7 further consideration.

8

9 3.2.4 Excavation

10

11 Excavation, combined with confirmatory sampling, ensures the permanent removal of
12 contamination from the site. Once excavated, the soil can be treated to remove the
13 contaminants and then backfilled, or can be hauled off site to a facility that will accept the
14 waste (see sections below). In either case, however, the volume of soil, if large, may make
15 this option cost-prohibitive, particularly if the contamination is very deep. Furthermore,
16 excavation of soils increases the risks of exposure through airborne contaminants.
17 Nevertheless, excavation enables a variety of ex situ treatment processes to be used. It is thus
18 effective towards this goal, and is readily implementable. Thus, excavation will be retained
19 for further consideration.

20

21 3.2.5 Ex Situ Treatment

22

23 A variety of treatment processes exist for soil once it has been excavated. A
24 description of some potentially applicable techniques appear below.

25

26 3.2.5.1 Thermal Oxidation/Incineration

27

28 Thermal oxidation or incineration is a method in which the soil is subjected to a high-
29 temperature under controlled conditions to fully oxidize organic contaminants. Products
30 include carbon dioxide, water vapor, sulfur dioxide, nitrogen oxides, and ash. Incineration
31 methods can be used on or off site to destroy organic contaminants in liquid, gaseous, and
32 solid waste streams.

33 Several types of incinerators are technically feasible and have been used to treat
34 hazardous waste. In general, multiple hearth, fluidized bed, infrared heating, and rotary kiln
35 incinerators are most applicable for the incineration of solids. Each of these systems would
36 destroy all organic contaminants present.

37 There are several drawbacks to this technology, however. It is a large unit process
38 that may not be appropriate for small volumes of soil. In addition, there is an increased risk
39 of exposure, not only due to the excavation of soil, but also from the actual incineration,
40 incomplete combustion, process upsets, and additional waste streams from incineration.
41 Furthermore, inorganic contaminants are not destroyed by incineration.

42 There are many vendors for this technology, making it implementable.
43 Implementation would require, however, obtaining necessary permits, including those for air

1 emissions. Also, some public opposition may be expected. However due to its effectiveness
2 in destroying organic contaminants, including PCBs, incineration will be retained as a possible
3 remedial technology appropriate for this site.

4

5 3.2.5.2 Chemical Treatment

6

7 Chemical treatment techniques include those which destroy, degrade, or reduce the
8 toxicity of contaminants. Glycolate dechlorination is a chemical treatment that has potential
9 effectiveness in remediating PCB-contaminated soil. The technology uses chemical reagents
10 to remove chlorine atoms from PCBs, greatly reducing their toxicity. Reagents include
11 APEG, a combination of alkaline (A) earth metal hydroxides and polyethylene glycol (PEG),
12 and a proprietary new reagent developed by the EPA known as Base-Catalyzed Dechlorination
13 (BCD) process. Regardless of the reagent used, this process mixes the reagent with the soil,
14 sometimes with a non-toxic or low-toxicity cosolvent. The soil is batch-treated at high
15 temperatures (150°C to 350°C) for several hours. When treatment is complete, the soil is
16 removed and separated from the reagent/cosolvent liquid, which is recycled.

17

18 The effectiveness of this technology is site-specific, and must be determined through
19 treatability studies. There are several vendors of this technology and no institutional
20 obstacles. It is not effective in treating other organic contaminants or metals present at the
21 site, but it will be retained as a treatment technique for PCBs.

22

23 3.2.5.3 Physical Treatment

24

25 Physical treatments involve physical manipulation of the soil in order to immobilize
26 or remove contaminants. Potentially applicable remedial technologies for contaminated soils
27 include soil washing, solvent extraction, solidification/stabilization, volatilization/thermal
28 desorption, and asphalt batching.

29 Soil washing is a volume reduction technology that segregates the fine solid fractions
30 from the coarser soils through an aqueous washing process and washing water treatment
31 system. This technology is based on the observation that the vast majority of contaminants
32 are found adsorbed to the fine soil particles due to their greater specific surface area. The
33 coarser clean soil particles could be backfilled on site while the fine fraction would require
34 further treatment or disposal. The volume of surficial contaminated soil at the DRMO Yard
35 is not large compared to many sites. Thus, a volume reduction step would not greatly
36 facilitate the remediation. Furthermore, the fine soils must be treated further. Such treatment
37 would be difficult because most technologies other than incineration and solidification work
38 best on coarser soils. Therefore, soil washing will not be retained for further evaluation.

40 Solvent extraction uses a treatment vessel in which soil is homogeneously mixed,
41 flooded with a solvent, and again mixed thoroughly to allow the waste to come in contact with
42 the solution. Liquid or supercritical phase solvents may be used. Once mixing is complete,
43 the solvent is drawn off by gravity, vacuum filtration, or some other dewatering process. The
44 solids are then rinsed with a neutralizing agent (if needed), dried, and placed back on site or
45 otherwise treated/disposed of. Solvents and rinse waters are processed through an on-site
46

1 treatment system and recycled for further use. Supercritical solvents may be recovered by
2 simply reducing the pressure and removing the fluid as a gas. There are not many vendors of
3 this technology. However, it is otherwise implementable. This process has shown potential
4 effectiveness in the removal of metals as well as PCBs. Therefore, it will be retained as a
5 viable technology.

6 Solidification/stabilization treatment systems, sometimes referred to as fixation
7 systems, are meant to improve handling and physical characteristics of the waste, reduce the
8 surface area across which contaminants can migrate, and/or reduce the solubility of hazardous
9 constituents in the waste. Solidification involves techniques that seal the wastes into a
10 relatively impermeable stable block. Stabilization involves techniques that would either
11 neutralize or detoxify the wastes, so that the contaminants are maintained in the least soluble
12 or toxic form.

13 Solidification/stabilization methods for chemical soil consolidation can immobilize
14 contaminants. Most of the techniques involve a thorough mixing of the solidifying agent and
15 the waste. Solidification of wastes produces a monolithic block with high structural integrity.
16 The contaminants do not necessarily interact chemically with the solidification reagents but are
17 mechanically locked within the solidified matrix. Stabilization methods usually involve the
18 addition of materials which limit the solubility or mobility of waste constituents even though
19 the physical handling characteristics of the waste may not be improved. Remedial actions
20 involving combinations of solidification and stabilization techniques are often used and are
21 readily implementable.

22 Solidification processes available as remedial action technologies for contaminated
23 soils include the following:

- 24 • Cement-based processes;
- 25 • Pozzolanic processes;
- 26 • Thermoplastic techniques;
- 27 • Organic polymer techniques;
- 28 • Surface encapsulation techniques;
- 29 • Self-cement techniques; and
- 30 • Vitrification techniques.

31 Solidification is considered by EPA to be appropriate for large volumes of waste
32 material containing toxic heavy metals. Organic contaminants do not bond chemically to the
33 material, but are physically bound in the matrix. Solidification will be retained for further
34 consideration.

35 Volatilization can be accomplished through thermal treatment or mechanical aeration.
36 An example of this physical treatment is thermal desorption. In this process solids with
37 organic contamination are heated, volatilizing water and organic contaminants and producing a
38 dry solid containing trace amounts of the organic residue. An inert carrier gas is used to
39 transport the volatilized water and organics to an off-gas handling system, a three stage
40 cooling and condensing train which may condense organics of low, medium, and high

1 volatility in a step wise fashion. The system is designed to treat organic wastes with boiling
2 points up to 1,000°F, less than 10 percent total organics, and less than 60 percent moisture.
3 This technology is effective for PCBs, is implementable, and is retained for further
4 consideration. It would have to be combined with a metals-treatment technology such as
5 solidification or solvent extraction.

6
7 Asphalt batching, also referred to as hot asphalt incorporation, involves the
8 incorporation of organic-contaminated soils into hot asphalt mixes as a partial substitute for
9 stone aggregate. Soil treatment by this method is achieved by volatilization, thermal
10 destruction, and dilution. In addition, the soil is solidified in the asphalt/aggregate mixture,
11 immobilizing the soil contaminants. The hot mix process involves sorting the soil aggregate,
12 then heating and mixing the soil with liquefied asphalt. As the aggregate is heated,
13 temperatures reach 260°C to 430°C for approximately five minutes. The mixture is stored,
14 transported, and applied while still warm (approximately 150°C).

15
16 The hot mix technique requires the presence of an asphalt plant near the area of
17 contamination. This facility must have appropriate environmental permits, particularly for air
18 emissions. Past experience with asphalt batching have shown that plants may need to be
19 retrofitted to accept the contaminated soils (Czarnecki 1989). Few data are available on
20 removal efficiencies in practice and long-term integrity of the asphalt product. The cost of
21 treating organically contaminated soil by incorporation into hot asphalt is high; therefore, this
22 remedial technology will not be retained for further evaluation.

23
24 **3.2.5.4 Biological Treatment**

25
26 Biological treatment processes use indigenous or selectively cultured microorganisms
27 to degrade organic compounds. Generally aerobic degradation is preferred, with the
28 microorganisms breaking down the contaminants to water, carbon dioxide, and (if chlorinated)
29 hydrogen chloride. Anaerobic processes only partially degrade organic contaminants, ideally
30 resulting in a reduction of toxicity or making the end product more amenable to further
31 treatment (e.g., aerobic treatment). Aromatic molecules such as the BTEX compounds are
32 readily biotransformed. Even some of the chlorinated benzenes may be degraded. However,
33 larger chlorinated molecules, such as PCBs and DDT, are recalcitrant to biological activity.
34 Some progress has been reported in using anaerobic, followed by aerobic biodegradation to
35 transform PCBs. However, biotreatment has not been routinely applied to PCB wastes, and is
36 thus not considered effective. Therefore, biotreatment will not be retained for further
37 consideration.

38
39 **3.2.6 In Situ Treatment**

40
41 Several methods are currently being developed which involve manipulation of the
42 subsurface in order to immobilize, remove, or transform waste constituents. In situ
43 techniques eliminate the need to excavate any soil. This approach can reduce remedial costs,

1 and also eliminate the possibility of additional exposure. Therefore, the following physical
2 treatments are evaluated:

- 3 • Bioventing,
- 4 • Vapor Extraction,
- 5 • Soil Flushing,
- 6 • Vitrification,
- 7 • Steam Stripping,
- 8 • Radio Frequency Heating,
- 9 • Solution Mining, and
- 10 • Stabilization and Solidification.

11

12 3.2.6.1 Bioventing

13 In situ bioventing is applied to contaminated soils in the unsaturated zone. This
14 technology involves optimizing environmental conditions within the contaminated soils to
15 promote the growth of microorganisms. Inorganic nutrients are intermittently delivered to the
16 subsurface as aqueous solution through injection wells or an infiltration system. To increase
17 the population of the degrading bacteria, groundwater from the saturated zone may be
18 removed, treated in an above-ground bioreactor (generating increased numbers of
19 microorganisms) and returned, with the delivered nutrients and oxygen, to the contaminated
20 zone. Between periodic nutrient additions, air is drawn through the contaminated zone with a
21 vapor extraction system. This supplies the necessary oxygen. Because PCBs and DDT are
22 not readily biodegradable, in situ bioventing will not be retained for further evaluation.

23

24 3.2.6.2 Vapor Extraction

25 Vapor extraction is an in situ technique used to remove volatile and semivolatile
26 organics from the vadose zone of soils. The basic components of the system include
27 production wells, monitoring wells, and high-vacuum pumps. The system operates by
28 applying a vacuum through the production wells. The vacuum system includes air flow
29 through the soils, stripping and volatilizing the organics from the soil matrix into the air
30 stream. The contaminated air stream is then typically treated by utilizing an activated carbon
31 bed. However, the soil contaminants present are not volatile. Thus vapor extraction will not
32 be retained for further evaluation.

33

34 3.2.6.3 Soil Flushing

35 Soil flushing is an extraction process in which organic and inorganic contaminants can
36 be washed from contaminated soils. An aqueous solution is injected into the area of
37 contamination, and the contaminant elutriate is pumped to the surface for removal,
38 recirculation, on-site treatment, or reinjection. During elution, sorbed contaminants are
39 mobilized into solution because of solubility, formation of an emulsion, or chemical reaction
40 with the flushing solution. An in situ soil flushing system includes extraction wells installed
41 in the area of contamination, injection wells installed upgradient of the contaminated soils
42 area, and a wastewater treatment system.

1 This technology will not be retained for further evaluation. At the DRMO Yard,
2 PCBs sorb strongly to soil particles and it would be difficult, if not impossible, to make them
3 soluble. Although the metals may be mobilized with this technology, most contamination is at
4 the surface and spread over a wide area. This would make it difficult to apply this
5 technology. In addition, it would also be very difficult to select a flushing solution that would
6 capture all of the different contaminants, due to their different chemistries.

7 **3.2.6.4 Vitrification**

8 In situ vitrification is a technology that was initially developed to stabilize transuranic-
9 contaminated wastes, and it has been found to be applicable to other hazardous waste. The
10 technology is based upon electric meter technology, and the principle of operation is joule
11 heating, which occurs when an electrical current is passed through a molten mass.
12 Contaminated soil is converted into durable glass, and wastes are pyrolyzed or crystallized.

13 In the process, a voltage is applied across electrodes placed in the ground. Under the
14 high voltage, the soil volume between the electrode is heated to temperatures in excess of
15 3,000°F, thereby melting the soils. The molten mass of soil is then cooled to form a glassy,
16 crystalline end product that is extremely stable. It is projected that materials will remain
17 totally isolated for greater than 10,000 years. Although this technology is promising, and
18 would almost certainly be successful in stabilizing the contamination, it is not an appropriate
19 method for the small-scale contamination at the DRMO Yard. It also has not been fully
20 developed, limiting its implementability. Therefore it will not be considered further.

21 **3.2.6.5 Steam Stripping**

22 In situ steam stripping is a technology in which steam is forced into areas of
23 contamination to volatilize the contaminants. There are two types of technology available.
24 Several vendors offer systems that inject steam through wells to deep organic contamination.
25 The vaporized contaminants are then collected in a vapor extraction well. This approach is
26 applicable only for contaminants located deep in the ground, or at sites with a cap.
27 Application to shallow contaminated soil would cause contaminant vapors to be released to the
28 atmosphere. Thus this process would not be applicable to the DRMO soils.

29 The second process uses twin large bore augers to penetrate and mix the soil, while
30 simultaneously injecting steam. To capture the volatilized contaminants, a shroud is placed
31 over the area being treated (approximately 30 square feet are treated at once). The shroud
32 captures contaminants for condensation. Some success has been reported for semivolatile
33 compounds. However, it is unlikely to be at all effective on PCBs or metals present at the
34 DRMO Yard. Therefore, it will not be retained for further discussion.

35 **3.2.6.6 Radio Frequency Heating**

36 Radio frequency (RF) heating has been proposed as a method to remove organic
37 contaminants in the subsurface through vaporization. In situ RF heating is applicable to

1 vadose zone contamination. Vadose zone contamination in the DRMO Yard soils consists
2 primarily of PCBs, DDT, and metals, none of which can be adequately handled by this
3 technology. Therefore, in situ RF heating is not effective and will not be evaluated further.
4

5 3.2.6.7 Solution Mining 6

7 Solution mining is similar in principle to soil flushing. This technology involves
8 flooding contaminated land areas with a solvent and then collecting the elutriate with a series
9 of shallow well points. The process requires that the contaminants be mobilized into the
10 solvent for recovery, either by solution or chemical reaction. Wastewater treatment of the
11 recovered elutriate would be required. Potential problems associated with in situ solution
12 mining include the difficulty of achieving adequate contact time with buried wastes and the
13 increased risk of solvent or elutriate contributing to or spreading contamination. The degree
14 of contact between solvent and contaminants can be difficult to determine. At the DRMO
15 Yard, the contaminants are too diverse to allow this technology to be effective. A solvent
16 capable of recovering the metals, PCBs, and DDT together would be difficult or impossible to
17 develop. Thus this technology would be ineffective and is not retained for further evaluation.
18

19 3.2.6.8 Stabilization and Solidification 20

21 In situ stabilization consists of applying or injecting substances into a contaminated
22 area with chemicals that detoxify pollutants. As with solution mining, a localized increase in
23 hydraulic head due to injection could increase the vertical gradients, particularly near the
24 injection points. In order to ensure complete contact with the subsurface contaminants, either
25 very large quantities of stabilization chemicals would have to be injected, or some provision
26 for controlling groundwater flow by pumping or diversion would be necessary. Variations in
27 soil permeability may prevent complete contact with some of the contaminants. Because some
28 of the contaminants present, such as PCBs and DDT, are not subject to detoxification agents
29 in situ, in situ stabilization will not be retained for further consideration.
30

31 In situ solidification is a process in which the contaminants are immobilized. Several
32 vendors market systems that solidify soils in place. Generally, these systems utilize large
33 bore augers that penetrate and mix the soil. Meanwhile, solidification agents such as portland
34 cement, silicates, or others (sometimes proprietary agents) are introduced through the auger to
35 the soil. This technology can adequately reduce the mobility of contaminants, especially
36 metals, providing sufficient in situ mixing is realized. Metals are best treated by this
37 technology because they actually bond with the solidification agents. Organic contaminants
38 may be less effectively treated by solidification. Unlike metals, they do not react with the
39 added pozzolanic materials to form immobile complexes; they would simply be entrapped in
40 the matrix. The soil contamination at the DRMO is located in both the asphalt pad and in
41 native soils. It would be difficult to adequately mix these media in place with the
42 solidification agents. This would be a significant obstacle for the implementation of this
43 alternative. Thus, in situ solidification is not recommended and will not be evaluated further.
44

1 **3.2.7 Disposal**
2

3 **3.2.7.1 Off-Site Disposal**
4

5 Off-site disposal of contaminated soil/waste involves the hauling of excavated soil/
6 waste to a commercial sanitary or secure landfill for disposal. This technology effectively
7 eliminates contaminant exposure routes. Several factors influence the implementability of off-
8 site disposal in secure or sanitary landfills. The primary factors are whether the excavated
9 soil is classified as hazardous by RCRA or is considered a TSCA-regulated waste. Some of
10 the soils at the DRMO Yard would be regulated under TSCA due to the presence of PCBs.
11 Those soils that are not hazardous or TSCA-regulated can be disposed of in a sanitary landfill.
12 Thus, this technology is both effective and implementable and will be considered further.

13 **3.2.7.2 On-Site Disposal**
14

15 Excavated soil could be disposed of on-site either in a constructed landfill (with or
16 without prior treatment) or directly on the site (after treatment). Untreated soil would have to
17 be disposed of in a landfill constructed in accordance with Massachusetts Landfill regulations.
18 Meeting these regulations would be an obstacle to implementation, but could still be possible.
19 Treated soils may be disposed of directly on site as backfill. A special case would be soils
20 treated by solidification. Although these soils would not be required to be disposed of in a
21 landfill, it may be desired to backfill them in a designated area (because of their monolithic
22 morphology) and under a cap to minimize weathering. On-site disposal will be retained for
23 further evaluation.
24

25 **3.2.8 Summary**
26

27 Table 3-1 summarizes the remedial technologies for soils at the DRMO Yard operable
28 unit that are screened in Section 3.2.
29

30 **3.3 GROUNDWATER REMEDIAL TECHNOLOGIES AND MONITORING**
31 **(AOCs 32 and 43A)**
32

33 **3.3.1 No Further Action**
34

35 No Further Action provides no remedial actions for the present groundwater
36 contamination. This option will be retained. Groundwater monitoring to observe potential
37 change in water quality will also be retained under this option for both operable units.
38

39 **3.3.2 Institutional Actions**
40

41 Institutional controls over the groundwater contamination plumes can include zoning
42 and deed restrictions, and continued monitoring of existing groundwater wells in the vicinity.
43 Industrial and/or commercial zoning would restrict development of the property from
44 residential usage. Deed restrictions would be required to ensure that no drinking water wells
45 are installed which could potentially be impacted by the contaminated groundwater and that no
46

1 construction would ensue which could expose the contamination. This option is effective in
2 controlling the exposure to the contaminants. A waiver from attaining ARARs would be
3 required. Continued maintenance of the use restrictions increase the difficulty of
4 implementation. However, such action will be retained for further evaluation for both
5 operable units.

6

7 3.3.3 Intrinsic Remediation (With Long-Term Monitoring)

8

9 Intrinsic remediation relies on natural attenuation to remediate contaminants in the
10 subsurface. In many cases natural attenuation, by biotransformation, sorption, dispersion,
11 diffusion, and other natural processes can reduce contaminant concentrations to acceptable
12 levels before potential receptors are reached. Where ARARS are exceeded in the
13 groundwater, the intrinsic remediation can only be applied in conjunction with institutional
14 control, since drinking water wells cannot be permitted where ARARs are exceeded.

15 The use of intrinsic remediation requires the acquisition of sufficient data to
16 demonstrate that the mechanisms of intrinsic remediation are reducing or will reduce
17 contaminant concentrations to acceptable levels within the controlled area. It requires the use
18 of groundwater models with conservative input parameters and sufficient sensitivity analyses
19 to satisfy all plausible contaminant migration scenarios. Where possible, both historical
20 monitoring data and modeling should be used to provide projections that collectively and
21 consistently support the conclusion that the dissolved contaminant plume is naturally reduced
22 to acceptable levels within the controlled area.

23

24 Currently, the POL Storage Area shows no downgradient wells exceeding ARARs or
25 TBCs (since 43M93-05X is registering contaminants from elsewhere). Both 43MA93-04X
26 and 43MA93-10X wells lie within the spill area associated with former leaking USTs, and
27 show elevated TPHC. 43MA93-10X also showed elevated 2-methylnaphthalene exceeding
28 ARARs. No downgradient monitoring wells have sampled water quality in the overburden
29 aquifer except at and just below the water table. Additional investigation would be required
30 to establish if intrinsic remediation is effectively working. The persistent low levels of TCE
31 in POL-3 may possibly be indicative of the presence of a TCE dense non-aqueous phase
32 liquid (DNAPL) within the underlying bedrock, although higher concentrations of TCE would
33 be expected if the DNAPL exists in the overburden aquifer. Again, this possibility cannot be
34 explored without additional investigation.

35

36 The presence of TCE in at least one bedrock well around UST 13 (32M-92-06X) at
37 levels well in excess of those found in POL-3 (up to 200 $\mu\text{g}/\text{L}$) raises the possibility that the
38 hydraulic gradients or fractures within the bedrock allow migration from the location of 32M-
39 92-06X to the vicinity of POL-3, although this seems highly unlikely. To evaluate this
40 question and the question of the effectiveness of intrinsic remediation at UST 13, additional
41 investigation would again be required.

42

43 Intrinsic remediation will be retained as an alternative for both groundwater operable
44 units.

45

1 **3.3.4 Containment**
2

3 Containment involves the prevention of contaminant migration by installing
4 impermeable physical barriers or inducing hydraulic barriers by extracting and reinjecting to
5 the contaminated groundwater. There are three process options involved in impermeable
6 barriers; sheet piling, slurry walls, and grout curtains. Metal sheet piles may be inserted
7 vertically into the overburden downgradient of the contamination plume, creating a physical
8 barrier prohibiting migration of the contamination. The slurry wall is constructed by
9 excavating a trench to the depth of bedrock, while simultaneously filling the trench with a
10 bentonite slurry. A grout curtain is formed by drilling boreholes at a predetermined spacing
11 and injecting grout under pressure to form a physical barrier against contaminant migration.
12 Hydraulic containment can be achieved by extracting water in or downgradient of the plume
13 at a rate sufficient just to reverse the flow gradient so that groundwater no longer migrates
14 from the source area.

15
16 The groundwater at the UST 13 site is present in the bedrock. It is not possible to
17 place physical containment barriers in this medium; thus physical barriers are not
18 implementable. It is theoretically possible to implement a hydraulic containment option.
19 However, the aquifer yields little or no water due to its low permeability, suggesting that
20 hydraulic containment would not be implementable. Furthermore, the objective of hydraulic
21 containment is to reverse the pattern of migration. As stated in Section 1.2.1.3, there is no
22 apparent contaminant migration and the contaminant source (in soils) was removed with the
23 tank. Therefore, this alternative would not be any more effective at reducing contaminant
24 migration than the No Further Action alternative; it will not be retained.

25
26 The groundwater at the POL Storage Area/DRMO Yard shows only intermittent and
27 low level contamination at or close to the water table, or where lower permeability till or
28 bedrock are close to the surface. If subsequent investigation shows higher concentrations of
29 contaminants in the bedrock then physical barriers are not likely to implementable. If higher
30 levels of contamination are found in the deeper parts of the overburden aquifer (up to 50 feet
31 below ground surface in boreholes 43BA93-03X, B-04S, B 43BA93-06X, and over 60 feet
32 below surface in B-59S), costs are prohibitive. This is particularly so because to achieve
33 closure, the barrier would have to extend around the site or be tied into lower hydraulic
34 conductivity bedrock outcrops to east and northwest (Shepley's Hill). The installation of a
35 containment barrier or barriers cannot be justified for this site and will not be retained for
36 further evaluation.

37
38 Capping was discussed in Section 3.2.3 as a containment alternative for soils. It can
39 also be used to minimize the production of leachate and the migration of groundwater, by
40 preventing the infiltration of rainwater. It will be retained for further evaluation at UST 13.

41
42 **3.3.5 Collection**
43

44 The general response action of collection is represented by the technologies of
45 groundwater extraction and subsurface collection trenches. Extraction involves the use of
46 recovery wells to pump contaminated groundwater from the subsurface. In cases where

1 adsorbed contaminants partition slowly to the groundwater, a pulsed pumping mode may
2 reduce the volume of groundwater which is needed to flush the contaminated plume.
3 Subsurface collection trenches are constructed by excavating to bedrock downgradient of the
4 contaminated plume and installing a conduit to collect groundwater by gravity flow.
5 Subsurface collection trenches are not implementable at the UST 13 site. As discussed in
6 Section 3.3.3, the groundwater contamination is present in the bedrock. It is not feasible to
7 install trenches in bedrock. It would be very difficult to collect groundwater from the
8 bedrock due to its very low effective porosity so collection trenches will not be retained.
9 Collection wells are also not likely to be effective in recovering a significant volume of
10 contaminated groundwater. However, in the interest of developing remedial alternatives for
11 this operable unit, collection via recovery wells will be retained for this operable unit.

12
13 If groundwater at the POL Storage Area/DRMO Yard requires remediation, then
14 wells in the overburden aquifer are the most feasible method of intercepting and collecting the
15 groundwater. Collection via recovery wells will be retained for this operable unit.

17 3.3.6 Ex Situ Treatment

19 Ex situ treatment involves either biological or physical/chemical technologies applied
20 once the contaminated groundwater has been brought to the surface through collection.

22 3.3.6.1 Physical/Chemical Treatment

24 Many ex situ physical and chemical treatment technologies are utilized to treat
25 inorganic and organic contaminants resistant to biodegradation.

27 Gravity separation is a technology used to treat two-phased aqueous wastes. It may
28 be used to separate free gasoline or fuel oil from a fuel-contaminated aquifer, or to separate
29 PCB oils from contaminated groundwater. The treatment tank must be designed with
30 appropriate residence time to allow complete separation between the oil and water phases.
31 This technology is effective and implementable. Some oil-phase material may remain at the
32 UST 13 site. Thus this technology will be retained at UST 13 operable unit for further
33 consideration as a pre-treatment step. For the POL Storage Area/DRMO Yard where no
34 separate phase has been found or is expected, this technology will not be retained.

36 Flotation is used to remove oils and other suspended substances with densities less
37 than that of water. Dissolved air flotation may also remove substances slightly heavier than
38 water through adsorption to bubbles. Flocculants are frequently employed to enhance the
39 efficiency of flotation units. Skimming is often incorporated into the flotation process. This
40 technology is generally effective and implementable. As some emulsified organics may be
41 present in the UST 13 groundwater, flotation will be retained for further consideration at this
42 operable unit. At the POL Storage Area/DRMO Yard, the technology is not applicable and
43 will not be retained..

45 The technologies of precipitation, coagulation, and flocculation are utilized to remove
46 heavy metals, colloidal solids, and dissolved solids which could not be removed by sedimenta-

1 tion alone (see below). Precipitation is a chemical process where certain anions are added to
2 the contaminated water to bond with soluble metallic ions, converting them to an insoluble
3 form for precipitation out of the solution. Coagulation is a physical/electrochemical process
4 in which suspended colloidal particles are destabilized. These particles generally possess a net
5 negative charge on their surfaces. Coagulants neutralize this charge. Attractive forces
6 between particles then become sufficient to allow for the creation of larger particles.
7 Flocculation usually is done after precipitation or coagulation. The most common technique
8 is orthokinetic flocculation, in which the water is mixed in a vessel to induce velocity gradients
9 between particles of different sizes. These gradients increase the likelihood of collision
10 between particles. Thus, larger particles result, which can be removed more easily by
11 sedimentation or filtration (described below). Flocculation may be enhanced by the addition
12 of organic polymers. The process is dependent upon chemical interactions, temperature, pH,
13 solubility variances, and mixing effects. These technologies are effective and implementable.
14 Although metals in the UST area groundwater operable unit are not being remediated, these
15 technologies, in conjunction with a removal technique, can be successful in removing metals
16 from an aqueous solution, if such removal is required prior to treatment for organics, through
17 air stripping, for example. They will thus be retained for further consideration as a pre-
18 treatment step. For the POL Storage Area/DRMO Yard groundwater operable unit, this
19 technology could only be selected at a design stage after further site characterization identifies
20 the need for remediation. It will not be retained at this stage.

21
22 Sedimentation removes suspended particles from contaminated water by allowing
23 them to physically settle out if their densities are greater than water. Residence time in the
24 sedimentation chamber must be adjusted to achieve maximum settling. The settled solids
25 form a sludge at the bottom of the chamber, which is pumped out when necessary. This
26 technique is effective when combined with coagulation and flocculation, and will be retained
27 for further consideration as a pre-treatment step at the UST 13 operable unit. For the POL
28 Storage Area/DRMO Yard groundwater operable unit, this technology could only be selected
29 at a design stage after further site characterization identifies the need for remediation. It will
30 not be retained at this operable unit at this stage.

31
32 Filtration is an excellent method for supplemental removal of residual suspended
33 solids from contaminated groundwater. When water percolates from the surface into
34 groundwater aquifers, natural filtration occurs and may remove a large portion of the
35 suspended solids. The media and media size used are dependent upon the size of suspended
36 particles remaining in the water to be treated. Silica sand, anthracite coal, and garnet sand
37 are incorporated in uniform or mixed media filter processes. Filtration may be employed
38 prior to other technologies to reduce potential for clogging, or as a polishing unit to remove
39 residual floc from the effluent. This technology is effective in removing suspended materials
40 that may otherwise interfere with other downstream processes. This technology is readily
41 implementable. Thus, filtration will be retained for further consideration as a pre-treatment
42 step for the UST 13 operable unit. For the POL Storage Area/DRMO Yard groundwater
43 operable unit, this technology could only be selected at a design stage after further site
44 characterization identifies the need for remediation. It will not be retained at this operable
45 unit at this stage.

1 Neutralization is a technology implemented to raise or lower the pH of a wastewater
2 stream to neutral levels. Acidic waters may be neutralized with lime, soda ash, caustic soda,
3 or anhydrous ammonia, while alkaline waters may be neutralized with hydrochloric acid,
4 carbon dioxide, sulfur dioxide, and sulfuric acid. The pH of the groundwater at Fort Devens
5 does not warrant neutralization. However, although metals in the UST area groundwater are
6 not being remediated, this technology may be needed as part of an overall treatment train.
7 For instance, pH may need to be adjusted during precipitation to remove metals prior to
8 treatment for organics, through air stripping, for example. Therefore, this treatment method
9 will be retained for future consideration at the UST 13 operable unit. For the POL Storage
10 Area/DRMO Yard groundwater operable unit, this technology could only be selected at a
11 design stage after further site characterization identifies the need for remediation. It will not
12 be retained at this operable unit at this stage.
13

14 Activated carbon adsorption is a technology that removes organics from contaminated
15 water by adsorbing the organic compounds onto the extensive surface area of activated
16 carbon. Activated carbon is utilized by adding powdered carbon directly into contaminated
17 water, or by a more common method of allowing the water to flow through a column of fixed
18 granulated carbon. When the activated carbon has been utilized to its maximum adsorptive
19 capacity it is removed for disposal or regeneration. Activated carbon adsorption is effective
20 on organics exhibiting low solubility and high molecular weight, and is reliable over a broad
21 range of concentrations. The technology can be readily implemented on site and can remove
22 dissolved organics from aqueous wastes to levels below 1 part per billion. Therefore,
23 activated carbon will be retained for further consideration for the UST 13 operable unit. For
24 the POL Storage Area/DRMO Yard groundwater operable unit, this technology could only be
25 selected at a design stage after further site characterization identifies the need for remediation.
26 It will not be retained at this operable unit at this stage.
27

28 Air and steam stripping technologies involve mass transfer processes in which volatile
29 organic contaminants in water are transferred to gas. The contact between contaminated
30 aqueous solutions and air is maximized, thus transferring volatile organics to the air or steam.
31 Air stripping is effective for dilute waste streams containing highly volatile organics, while
32 steam stripping is more effective for more concentrated waste streams containing less volatile
33 organics. In the steam stripping process, steam is introduced into the bottom of a tower, and
34 heats and volatilizes the organics before exiting the top of the tower. In air stripping, air is
35 forced from the bottom to the top. In either case, it is likely that the off-gas stream will need
36 further treatment by some other process. This technology has proven successful for the
37 removal of organics and is therefore retained for further consideration for the UST 13
38 operable unit. For the POL Storage Area/DRMO Yard groundwater operable unit, this
39 technology could only be selected at a design stage after further site characterization identifies
40 the need for remediation. It will not be retained at this operable unit at this stage.
41

42 Ultraviolet (UV) light chemical oxidation technology provides for the destruction of
43 organic contaminants in groundwater by simultaneously applying UV radiation and chemical
44 oxidants. Hydrogen peroxide or ozone is used as a reagent to reduce or destroy the
45 contaminants while the UV light catalyzes the chemical oxidation of the organics. The
46 process entails passing contaminated groundwater through an oxidation chamber with UV

1 lamps. The organic contaminants absorb the UV light, and the energy activates the
2 contaminant to be easily oxidized by the reagent. This technology is not very effective on
3 highly saturated hydrocarbons, as would be found at the UST 13 operable unit. Thus, this
4 technology will not be retained. For the POL Storage Area/DRMO Yard groundwater
5 operable unit, this technology could only be selected at a design stage after further site
6 characterization identifies the need for remediation. It will not be retained at this operable
7 unit at this stage.

8 Ion exchange technology is employed to remove toxic ions such as heavy metals from
9 the waste stream, and replace them with non-toxic ions. The contaminated groundwater is
10 first passed over an appropriate solid resin material with non-toxic ions to exchange. A
11 second aqueous solution is used to remove the toxic ions from the resin. Liquid ion exchange
12 involves the exchange of inorganic ions in contaminated groundwater to an immiscible organic
13 stream containing reagents. No dissolved inorganic contaminants are present in the UST 13
14 groundwater. Thus this technology would be ineffective and is not retained. For the POL
15 Storage Area/DRMO Yard groundwater operable unit, this technology would be inappropriate
16 and will not be retained for further consideration.

17 Chemical oxidation utilizes an oxidizer such as hydrogen peroxide or chlorine to treat
18 dilute contaminated water containing oxidizable organics. This technology has been
19 successful in treating aldehyde, cyanide, mercaptans, phenols, benzidine, unsaturated acids,
20 and pesticides. The contamination present at UST 13 is not treatable by this technology;
21 therefore, it will not be retained for further consideration. For the POL Storage Area/DRMO
22 Yard groundwater operable unit, this technology would be inappropriate and will not be
23 retained for further consideration.

24 Chemical reduction involves the addition of a reducing agent which lowers the
25 oxidation state of a substance to reduce toxicity, solubility, or to transform it into a form
26 which can be easily handled. This technology is primarily applicable to metals, and therefore
27 will not be retained for further consideration at UST 13. For the POL Storage Area/DRMO
28 Yard groundwater operable unit, this technology would be inappropriate and will not be
29 retained for further consideration.

30 Wet-air oxidation is a technology in which elevated temperatures and high pressures
31 are applied to contaminated water to completely oxidize the organic contaminants. A
32 disadvantage is the high strength recycle liquor produced. Wet-air oxidation is primarily
33 applicable on extremely contaminated waters, thus it will not be retained for further
34 consideration at UST 13. For the POL Storage Area/DRMO Yard groundwater operable unit,
35 this technology would be inappropriate and will not be retained for further consideration.

36 Reverse osmosis and ultrafiltration are two technologies using membranes to
37 segregate clean water from a contaminated concentrated aqueous stream. In reverse osmosis,
38 fresh water is forced through a semipermeable membrane in the direction opposite to that
39 occurring in natural osmosis. This technology is implemented after pretreatment to prevent
40 plugging of the membrane. Reverse osmosis is primarily used to remove dissolved salts.
41 Ultrafiltration technology removes suspended solids and dissolved particles from contaminated

1 water on the basis of their molecular size as it passes through semipermeable polymeric
2 membranes. Ultrafiltration may be applied to homogeneous solutions and colloidal
3 suspensions. Both of these technologies generate a clean water stream, and a concentrate
4 stream containing the contaminants. Thus these technologies principally serve to reduce the
5 volume of liquid needing further treatment. At the UST 13 site, however, the volume of
6 water needing treatment is relatively small. It is unlikely that groundwater can be extracted at
7 any appreciable rate. Thus, it would not be appropriate to use a technology that simply
8 reduces the volume of water requiring treatment, and these two technologies will not be
9 retained.

10
11 At the POL Storage Area/DRMO Yard groundwater operable unit, the applicability of
12 reverse osmosis and ultrafiltration can only be determined after further site characterization
13 has identified the need for remediation and the nature of the contaminants. It will not be
14 retained for this operable unit at this stage.

15
16 **3.3.6.2 Biological Treatment**

17
18 Two basic ex situ biological treatment technologies are fixed-film processes and
19 activated sludge processes. These aerobic processes biologically convert contaminants to
20 carbon dioxide and water.

21
22 The technology of fixed film treatment operates by allowing contaminated
23 groundwater to contact a film of microorganisms attached to a solid material surface. One
24 example is a trickling filter, in which water flows via gravity over a bed of rocks to which
25 microorganisms are attached. This is used for drinking water treatment to remove organic
26 compounds. Another technology for the treatment of hazardous organics is the fluidized bed.
27 In the fluidized bed, water flows under pressure through a bed of treatment media at a rate
28 high enough that the media is fluidized. The surface of the media is covered with a film of
29 microorganisms which degrade the organics. Oxygen and nutrients may be pumped in as well
30 to enhance treatment. The fluidized bed provides more complete mixing than the trickling
31 filter, thereby accelerating the degradation process.

32
33 In activated sludge bioreactors, the microbial population are free floating within the
34 reactor. In general, solids are separated out of the effluent, and a portion of the sludge is
35 recycled back into the reactor to maintain the population. Three basic types of activated
36 sludge reactors exist, batch reactors, completely stirred tank reactors, and plug flow reactors.
37 Batch reactors are simple tanks in which wastewater is completely mixed and organics are
38 allowed to biodegrade with no inflow or outflow. Stirred tank reactors are batch reactors
39 with a constant inflow and outflow. Plug flow reactors are not mixed at all; wastewater
40 simply flows in one end and out the other and organics are degraded along the way. The
41 advantage of a plug flow reactor over the stirred reactor is that as the waste flows in, the
42 concentration of contaminants is relatively high, which promotes fast degradation. The
43 concentration decreases along the length, attaining its minimum at the outflow. In the
44 completely stirred reactor, the concentration of contaminants must be maintained at the
45 relatively low, desired outflow concentration. Therefore, degradation is slow and the volume

1 of the reactor must be large. Nevertheless, they are often preferred because they are easier to
2 operate.

3
4 Bioreactors have achieved some success with some of the contaminants of concern,
5 such as petroleum hydrocarbon and chlorinated aliphatics (DDT and PCBs are difficult to
6 degrade). Therefore, bioreactors will be retained for further consideration at the UST 13
7 operable unit.

8
9 At the POL Storage Area/DRMO Yard groundwater operable unit, these technologies
10 could only be selected at a design stage after further site characterization identified the need
11 for remediation. It will not be retained for this operable unit at this stage.

12
13 **3.3.7 In Situ Treatment**

14
15 Biological and physical/chemical in situ treatment technologies provide for the
16 decontamination of groundwater without requiring its extraction and the construction of ex
17 situ treatment units.

18
19 **3.3.7.1 Permeable Treatment Beds**

20
21 Permeable treatment beds are used to provide in situ treatment of the groundwater by
22 constructing a trench to intercept groundwater flow, filling the trench with appropriate
23 treatment materials, and capping the trench. The materials considered to be feasible in
24 permeable beds are limestone, activated carbon, glauconitic greensands, and synthetic ion
25 exchange resins. Although the relative cost of this technology is low to moderate compared
26 with other technologies, permeable treatment beds will not be retained at the UST 13 site
27 because trenching over 10 feet to the groundwater partly through hard igneous bedrock is not
28 feasible.

29
30 Depth to groundwater and to top of bedrock downgradient of the POL Storage
31 Area/DRMO Yard groundwater operable unit make the use of permeable treatment beds
32 infeasible for this area. The use of "barrier and gateway" permeable treatment walls might be
33 appropriate if subsequent investigation shows high levels of chlorinated solvents in the
34 groundwater, but this could only be selected after further site characterization identifies the
35 need for remediation. Permeable treatment beds will not be retained for further consideration
36 at this operable unit at this stage.

37
38 **3.3.7.2 Air Sparging**

39
40 Air sparging is essentially an air stripping process conducted underground that
41 involves the injection of pressurized air below the water table to create a transient air-filled
42 porosity within the soil by displacing water. This process enhances biodegradation by
43 increasing oxygen transfer to the ground water while promoting the physical removal of
44 VOCs by direct volatilization. The technology is applicable to contaminated aquifer solids
45 and vadose zone materials.

1 Certain limitations to the utility and applicability of air sparging exist. One such
2 limitation is that air sparging systems cause water and contaminants to move away from the
3 point of injection which can potentially accelerate and aggravate the spread of contamination.
4 Changes in lithology can affect both the direction and velocity of air flow. This technology
5 also increases the vapor pressure in the vadose zone; therefore, if the system is not designed
6 properly, exhausted vapors could be drawn into receptors such as basements. Air sparging
7 can be best controlled at depths from 4 to 30 feet at a site with relatively homogenous soil. If
8 significant stratification is present, sparged air has the potential to be trapped below an
9 impervious layer and contamination could be spread laterally.
10

11 As a result of these limitations and since the theory behind air sparging has not been
12 developed to the extent that it can predict success or the time required to achieve it,
13 treatability studies are required to assess site conditions, potential problems, obstacles, and
14 actual timeframes. Because treatability studies are required for this technology, costs are
15 moderate to high compared to other treatment options. Therefore, this technology will not be
16 retained for further evaluation for either the UST 13 operable unit or the POL Storage
17 Area/DRMO Yard operable unit.
18

19 3.3.7.3 Biological Treatment 20

21 In situ biological treatment uses biological cultures combined with aeration, additives
22 such as acidic or caustic solutions for the adjustment of pH, and nutrient supplements such as
23 nitrogen and phosphorus for nutrient-deficient environments to facilitate in-place groundwater
24 treatment of organic contaminants. The cost associated with this treatment is moderate
25 relative to other technologies. Although some of the contaminants of concern at the UST 13
26 site (i.e., DDT and PCBs) are not readily degradable and the chlorinated aliphatics may yield
27 toxic degradation by-products (e.g., vinyl chloride), recent advances have been made in the
28 biotreatment of these compounds. Therefore, this treatment option will be retained for further
29 evaluation at this operable unit. In situ biological treatment can only be evaluated for the
30 POL Storage Area/DRMO Yard groundwater operable unit at a design stage after further
31 characterization identifies the need for remediation. It will not be retained for this operable
32 unit at this stage.
33

34 3.3.8 Disposal 35

36 Upon extraction of the contaminated groundwater at either operable unit, or upon
37 completion of a treatment technique discussed above, the water must be disposed of either by
38 discharging into surface water, reinjection into the groundwater, or by transporting it to a
39 wastewater treatment plant.
40

41 3.3.8.1 Off-Site Disposal 42

43 The wastewater treatment plants in the vicinity are the Ayer publicly-owned treatment
44 works (POTW) and the Fort Devens wastewater treatment plant. The Fort Devens
45 wastewater treatment plant is designed for primary treatment only, and its treatment
46 techniques may not be applicable. The Town of Ayer POTW has a capacity of 1.79 million
47

1 gallons per day, utilizes activated sludge technology, and discharges treated wastewater into
2 the Nashua River. Water would have to be transported to the facility via truck or a new
3 dedicated pipeline. This technology will be retained for further screening, given that the
4 water meets pretreatment requirements before it is piped to one of these facilities.

5 **3.3.8.2 On-Site Disposal**

6 Discharge into a surface water body of treated groundwater would require an NPDES
7 permit and would require satisfaction of all Massachusetts discharge limits. The surface water
8 bodies in closest proximity to the remediation would be Plow Shop Pond or Willow Brook.
9 This option is retained for further screening in conjunction with treatment technologies.

10 Reinjection of the treated groundwater back into the aquifer can be used to dispose of
11 the groundwater. Although it is not possible to reinject water into the bedrock aquifer at the
12 UST 13 site, as discussed in Section 3.3.6, treated water could be injected into the vadose
13 zone/overburden above the bedrock. This reinjection, however, may locally increase the
14 downward vertical gradient and subsequently cause downward movement of contamination.
15 In addition, reinjection may clog the well screens with grit and precipitated matter.
16 Furthermore, to reinject, all constituents in the effluent must be at or below background
17 levels. This technology, therefore, will not be retained for further evaluation at this operable
18 unit. Reinjection of treated groundwater at the POL Storage Area/DRMO Yard groundwater
19 operable unit might be technically feasible, but uncertainties about the effect of reinjecting
20 water of different pH, eH, and oxygen content would require pilot studies to ensure that this
21 type of disposal would, in fact, be feasible. It will not be retained for further evaluation at
22 this stage, since active remediation has not yet been shown to be necessary at this operable
23 unit.

24 **3.4 SUMMARY**

25 Table 3-2 summarizes the remedial technologies screened for the groundwater at the
26 UST 13 and POL Storage Area/DRMO Yard operable units and the results of the screening of
27 the response action. All the remedial technologies except No Further Action, Institutional
28 Action, and Intrinsic Remediation are rejected at this time for the POL Storage Area/DRMO
29 Yard groundwater operable unit, because the proposed remedies can only be evaluated at a
30 later stage, if after further characterization, the need for active remediation is identified.

Table 3-1		
SUMMARY OF REMEDIAL TECHNOLOGIES FOR SOILS		
General Response Action	Remedial Technology	Screening Result
No Further Action		Evaluate
Institutional Actions		Evaluate
Containment	Single layer caps - Sprayed asphalt - Concrete slab - Asphalt pavement Multilayer caps - Clay - Synthetic membrane - Combination	Reject Reject Reject Evaluate Evaluate Evaluate
Excavation		Evaluate
Ex Situ Treatment	Thermal Oxidation/ Incineration Chemical Treatment - Glycolate dechlorination Physical Treatment - Soil washing - Solvent extraction - Solidification/Stabilization - Volatilization/Thermal Desorption - Asphalt batching Biological Treatment	Evaluate Reject Reject Evaluate Evaluate Evaluate Reject Reject
In Situ Treatment	Biological Treatment Physical Treatment - Bioventing - Vapor extraction - Soil flushing - Vitrification - Steam stripping - Radio frequency heating - Solution mining - Stabilization	Reject Reject Reject Reject Reject Reject Reject Reject Reject Reject

Table 3-1		
SUMMARY OF REMEDIAL TECHNOLOGIES FOR SOILS		
General Response Action	Remedial Technology	Screening Result
In Situ Treatment (cont.)	Solidification	Reject
Disposal	Off-site Disposal	Evaluate
	On-site Disposal	Evaluate

Table 3-2

**SUMMARY OF REMEDIAL TECHNOLOGIES FOR GROUNDWATER AT UST
13 AND POL STORAGE AREA/DRMO YARD OPERABLE UNITS**

Table 3-2

**SUMMARY OF REMEDIAL TECHNOLOGIES FOR GROUNDWATER AT UST
13 AND POL STORAGE AREA/DRMO YARD OPERABLE UNITS**

General Response Action	Remedial Technology	UST 13 Screening Result	POL/DRMO Screening Result
	- Ultrafiltration	Reject	Reject
In Situ Treatment	- Permeable Treatment Beds	Reject	Reject
	- Air Sparging	Reject	Reject
	- Biological Treatment	Evaluate	Reject
Disposal	Surface Water Discharge	Evaluate	Reject
	Reinjection	Reject	Reject
	POTW	Evaluate	Reject

1
2
**4. DEVELOPMENT AND SCREENING OF REMEDIAL ALTERNATIVES
3 AND MONITORING**
4
5
6
7

8 The remedial technologies that were identified and retained in Section 3 are developed
9 into remedial alternatives in this section. The retained technologies are assembled, as
10 appropriate, into comprehensive alternatives that address the entire operable unit. Although
11 more combinations of technologies exist than those identified as alternatives, only those
12 technologies that are compatible with each other and potentially feasible for the specific
13 operable unit were combined into the alternatives presented below. Also, some of the
14 technologies that were retained in Section 3 were not included in any alternative, because
15 other technologies were considered more appropriate.
16

17 The developed alternatives are then screened to select those that will be examined in
18 detail in Section 5. Screening is performed on the bases of effectiveness, implementability,
19 and relative costs.
20

21 **4.1 DRMO YARD SOILS OPERABLE UNIT**
22

23 Seven alternatives have been developed for the DRMO Yard soils operable unit.
24 These are:

25
26 A1: No Further Action;
27 A2: Institutional Actions;
28 A3: Containment via Capping;
29 A4: Excavation, Solidification, and On-Site Disposal;
30 A5: Excavation, Solvent Extraction, Thermal Desorption, and Backfilling;
31 A6: Excavation and Off-Site Disposal; and
32 A7: Excavation and Off-Site Incineration.
33

34 Each of these alternatives is described and screened below.
35

36 **4.1.1 Alternative A1: No Further Action**
37

38 **4.1.1.1 Description**
39

40 This alternative involves no remedial action; no treatment or containment will be
41 performed, and the contamination will remain in its present state. The selection of this
42 alternative does not satisfy the remedial action objectives for the DRMO Yard operable unit.
43 This alternative would leave contaminated soil in place; it would also take no action in
44 eliminating the exposure pathways of these contaminants. The No Further Action alternative
45 is included as a requirement of the NCP (40 CFR 300) and to provide a basis of comparison
46 for the remaining alternatives.

1 **4.1.1.2 Evaluation**

2 **Effectiveness**

3 The No Further Action alternative is ineffective and does not meet the remedial action
4 objectives for this operable unit. The human health risks would remain as described in the
5 risk assessment. The soil contamination could conceivably impact drinking water sources in
6 the future. The soil would continue to pose a theoretical hazard to construction workers in
7 the future if the site were to be developed.

8 **Implementability**

9 The no-action alternative would be difficult to implement as the current situation
10 exceeds cleanup goals, including PCB ARARs, and a waiver from meeting ARARs would
11 have to be obtained. This waiver would be difficult to obtain.

12 **Relative Cost**

13 As this alternative involves no remedial action, institutional action, containment,
14 disposal, or monitoring, no capital or operation and maintenance (O&M) costs are associated
15 with it. Although not easily quantified, the cost of future liability from contaminants
16 remaining on site may be significant.

17 **4.1.2 Alternative A2: Institutional Actions**

18 **4.1.2.1 Description**

19 Institutional actions are minimal actions taken to reduce exposure to contaminated
20 media. This alternative would involve no actual remediation. Examples of the actions that
21 could be taken include the installation of a fence surrounding the perimeter of the operable
22 unit, and the prohibition of future development of the land, possibly through deed restrictions.
23 This alternative does not remove the source of contamination, and if these institutional
24 controls were violated in some way, the protection of human health would be compromised.

25 **4.1.2.2 Evaluation**

26 **Effectiveness**

27 This alternative would not be effective in reducing the level of contamination at the
28 DRMO Yard operable unit. It would have no more of a remedial effect than Alternative A1,
29 No Further Action. However, it does have the potential, if executed properly, to reduce
30 exposure to the contaminants of concern. The effectiveness of the institutional actions would
31 depend on the type of control implemented. As most of the contamination is surface
32 contamination, access controls would have to be monitored regularly to ensure effectiveness.

1 **Implementability**
2

3 Implementation of this alternative would depend on legal authority and requirements.
4 It may be difficult to implement Alternative A2 as PCB ARARs would still be exceeded, and
5 it may be difficult to obtain a waiver of this requirement.
6

7 **Relative Cost**
8

9 Institutional actions are very inexpensive relative to treatment, containment,
10 excavation, and disposal.
11

12 **4.1.3 Alternative A3: Containment via Capping**
13

14 **4.1.3.1 Description**
15

16 This alternative would reduce the risks of direct exposure to the DRMO Yard
17 contaminants through capping. A multiple layer cap consisting of clay and topsoil would be
18 used.
19

20 The first step of this alternative would be to grade the areas that are to be capped. In
21 some cases, it may be appropriate to excavate certain isolated hotspots that are far from the
22 main areas of contamination and consolidate these with other contaminated wastes. Once
23 graded, a layer of clay (maximum permeability of 10^{-7} cm/sec) approximately two feet thick
24 would be applied to the area and compacted. Loam (topsoil) would be placed over the clay to
25 allow vegetative growth to help maintain the integrity of the cap. (The clay cap could be
26 replaced by a low permeable plastic liner, overlain by a 12-inch high-permeable sand drainage
27 layer. However, for simplicity, only the clay alternative is fully developed.) The site would
28 require long term monitoring of the integrity of the cap, and future use of the site would be
29 precluded. Cap maintenance would be required from time to time to repair areas that may
30 become eroded or otherwise damaged with age.
31

32 **4.1.3.2 Evaluation**
33

34 **Effectiveness**
35

36 A properly installed and maintained multiple-layered cap would effectively prevent
37 exposure to contaminated soil via dermal adsorption, ingestion, or inhalation because the
38 contaminated material would be physically isolated. It would also prevent erosion and the
39 contamination of groundwater and surface water. Contaminants at concentrations above
40 cleanup goals would remain at the site. This alternative would not meet the preference for
41 treatment of contaminants.
42

43 **Implementability**
44

45 The technology needed for capping this operable unit is reliable and well-established
46 and thus is readily implementable. A storm water management and erosion control plan may
47

1 be required to minimize erosion during cap construction. This alternative would require that
2 the site not be used for development in the future.

3
4 **Relative Cost**

5 Capping costs are dependent on the size of the area to be capped as well as the cap
6 design. Although the area to be capped at the DRMO area is relatively small, the proposed
7 design of the cap is multilayer. Therefore, costs are expected to be moderate relative to
8 treatment, disposal, and institutional actions.

9
10 **4.1.4 Alternative A4: Excavation, Solidification, and On-Site Disposal**

11
12 **4.1.4.1 Description**

13 This alternative would require the excavation of those contaminated areas at the
14 DRMO Yard exceeding cleanup goals. The soils to be excavated are primarily surface soils
15 from various parts of the northern section of the yard. The excavated soils would be
16 consolidated and stockpiled. On-site solidification involves mixing the excavated soils with
17 cement, fly ash and lime, or other reagents that will both transform the soil into solid
18 monoliths, reducing potential exposure risks, and reduce the leachability of metals. Organic
19 contaminants, such as PCBs and DDT, would be physically bound up in the solidified
20 material, making them inaccessible to direct contact. Inorganic contaminants react with the
21 solidification reagents and become chemically bound up in the solidified matrix. This
22 significantly reduces their leachability.

23 Solidification may be carried out in a number of similar ways, including mixing in a
24 pug mill followed by curing in forms, or simple bulk mixing with earth moving equipment on
25 a specially constructed mixing pad. The correct mixture of soil, reagents such as cement, and
26 water that would produce the strongest monolith, reduce leachability, and keep volume
27 increase to a minimum, would be determined with a treatability study. Once mixed, the
28 mixture would have to cure for up to a month to achieve full strength.

29 Once the material was fully cured, it would be placed in a disposal cell on site. This
30 cell would require some excavation, primarily for grading reasons, but for the most part could
31 be above ground, especially considering the limited amount of soil requiring solidification.
32 The location of the disposal cell would have to be determined in consultation with installation
33 authorities, but would likely be near the north end of the yard, from where most of the
34 contaminated soil had been removed. The disposed monoliths would be covered with a layer
35 of topsoil and seeded.

36
37 **4.1.4.2 Evaluation**

38
39 **Effectiveness**

40 This alternative would be effective in reducing direct contact exposure routes to the
41 contaminants. The leachability of lead and cadmium would be drastically reduced, thereby

1 preventing exposure to either surface water or groundwater. Organic contaminants would be
2 essentially contained rather than destroyed. However, the organics would also be far less
3 susceptible to erosion (to surface water) or leaching (to groundwater). Solidification is widely
4 used to treat metals contamination. Although it is generally less effective for organics, it is
5 used successfully on larger molecular weight, less mobile organics, such as PCBs and DDT.

6

7 **Implementability**

8

9 The implementability of the alternative depends on the extent that the installation is
10 willing to have solidified material remain at the DRMO Yard site. Leaving the solidified
11 material there would limit the usefulness of that portion of the site. This would preclude
12 some future uses. Potentially, the MDEP could impose ongoing future monitoring
13 requirements at the disposal site. There would be no legal barriers to implementability, as the
14 soil is not a RCRA hazardous waste. As the solidification process is exothermic, the process
15 would have to ensure that no significant fugitive organic emissions are released during the
16 treatment process.

17

18 **Relative Cost**

19

20 The excavation, solidification, and on-site disposal costs associated with this alternative
21 are moderate compared with the costs of institutional controls, containment, and other
22 treatment methods.

23

24 **4.1.5 Alternative A5: Excavation, Solvent Extraction, Thermal Desorption, and** 25 **Backfilling**

26

27

28 **4.1.5.1 Description**

29

30 This alternative would provide a complete on-site treatment of the DRMO Yard soils
31 contaminated above cleanup goals, allowing them to be backfilled on-site. Because the nature
32 of the contaminants varies throughout this operable unit's soils, two treatment technologies
33 would be employed to provide complete treatment. These treatments would be conducted in
34 series, although, if soils can be segregated during excavation into organic-only and inorganic-
35 only contaminated soils, then these soils need only to be treated in the single appropriate
36 treatment step.

37 The first treatment would be solvent extraction to remove metals from the soil.
38 Solvent extraction uses a solvent to leach contaminants from the solid matrix. The solvent
39 would then be treated to transfer the leached metals from solution into a concentrated sludge.
40 The sludge, which would be a much smaller volume than the contaminated soil, would then
41 be disposed of off-site, possibly after first being treated by solidification at the disposal site.
42 The solvent would then be reused. As it would be difficult to select a solvent that could
43 recover both metals and organic contaminants, the process would be directed only at metals
44 removal. Thus a solvent such as an acid or an aqueous chelator solution would be used. To
45 regenerate an aqueous or chelating aqueous solvent, treatment technologies such as

1 precipitation (possibly simply through neutralization), ion exchange, or evaporation may be
2 used. This process would require the mobilization of tanks, clarifiers, and other process units
3 on site. The system would have to be configured from the results of treatability studies that
4 pick the best solvent, solvent regeneration system, and solvent/soil separation systems.

5 The second treatment would be aimed at removing organic contaminants. Thermal
6 desorption removes volatile and semi-volatile contaminants from soil as vapors through
7 heating. The thermal desorption unit would be a mobile unit owned and operated by one of
8 several vendors in this field. Because of the small volume of soil to be treated, the unit could
9 probably be one of the vendors' pilot units. The actual treatment process is straightforward.
10 Contaminated materials are fed into a thermal processor or materials drier, where they are
11 heated to 500°F to 1,000°F while being mixed to allow moisture and volatile contaminants to
12 escape. The soil can be heated either by direct firing with the hot gases from a combustion
13 process, or indirect firing, where the heat is conducted through the walls of a screw or drum.
14 The indirect firing method results in a smaller volume of offgas requiring treatment. The
15 treated soil would be stockpiled, tested for treatment verification, then backfilled on site.
16

17 The offgas from the process would be directed to an offgas treatment system,
18 including a cyclone/baghouse (fabric filter) system, to remove entrained particulate material, a
19 condenser to remove the condensable organic compounds, and then an additional organic
20 vapor treatment unit such as activated carbon or an afterburner. Condensate from the
21 condenser would be composed of water and condensed organics. The two-phase condensate
22 would be separated in an oil/water separator. The separated oil would be stored for future
23 transport and processing off site. The water, with a relatively low concentration of soluble
24 organics, would typically be treated using a carbon adsorption system. The treated water
25 would be sprayed on the treated soil to cool it and suppress gas generation. The spent carbon
26 from the carbon adsorption system would require periodic replacement and/or regeneration.
27 A likely disposal option for the spent carbon would be regeneration in which the organic
28 contaminants are destroyed by incineration.
29

30 4.1.5.2 Evaluation

31 Effectiveness

32 This alternative would use two separate sequential treatment technologies to remove
33 contaminants from the DRMO Yard soils. Successful treatment of the soils would remove all
34 routes of exposure and would meet all RAOs for the operable unit. The effectiveness of
35 solvent extraction is difficult to predict prior to conducting treatability studies. A solvent that
36 could effectively remove metals (lead and cadmium are the principal metal of concern) could
37 probably be selected. However, it can be difficult to select a solvent that is effective in
38 removing the metals, yet can be easily regenerated. Acid solvents require a great deal of
39 neutralization chemicals to precipitate the dissolved metals. This would also remove the
40 acidity from the solvent, such that it cannot be reused. In addition, it is very difficult to
41 remove chelated metals from solution, although once removed, the solvent could be reused.
42

1 The second technology, thermal desorption, is an increasingly commonly used
2 treatment technology that would be effective in removing organic contaminants, including low
3 volatility chemicals such as PCBs and DDT. Although this technology does not itself destroy
4 the contaminants, once separated, the chemicals are destroyed in subsequent steps, such as
5 when the carbon is regenerated, or the condensate is treated off site. (Glycolate
6 dechlorination was retained in Section 3 as a potential treatment for PCBs. However, since it
7 is not effective for DDT, DDD, and DDE, it was dismissed in favor of thermal desorption in
8 the development of alternatives.)

9
10 **Implementability**

11 Residuals from both of these technologies would require off-site treatment and/or
12 disposal. The metals in the sludge generated from the solvent regeneration would likely be
13 hazardous by the toxicity characteristic, and thus would have to be treated prior to disposal.
14 This treatment would be conducted at the disposal facility. Condensed oil from the desorption
15 unit would have to be destroyed, probably by incineration, at an off-site facility. Because this
16 oil would contain PCBs, it would have to be treated in a TSCA-regulated facility. As such
17 facilities are available, this would not be an obstacle to implementation.

18 Even if the solvent extraction treatment step is effective, residual arsenic below the
19 cleanup goal remaining in the soil after treatment could pose a problem during thermal
20 desorption. This metal, and the compounds in which it is frequently found, is fairly volatile,
21 and difficult to remove from an offgas. Meeting off-gas requirements for this metal could be
22 an obstacle to implementation. This alternative would also be required to meet a number of
23 other requirements during operation, including surface water discharge requirements
24 applicable for any spent solvent or recovered water discharges, and possible RCRA and
25 TSCA requirements from handling characteristic-hazardous wastes and PCBs.

26 Though not specific obstacles to implementation, this alternative would require a great
27 deal of treatability testing, on-site mobilization, and regulatory interface. This may not be
28 appropriate for the relatively small amount of contaminants present at this operable unit.

29
30 **Relative Cost**

31 The excavation, solvent extraction, thermal desorption, and backfilling costs
32 associated with this alternative are high compared with the costs of institutional controls,
33 containment, disposal, and other treatment methods.

34
35 **4.1.6 Alternative A6: Excavation and Off-Site Disposal**

36
37 **4.1.6.1 Description**

38 This alternative is very straightforward. Contaminated soils would be excavated as
39 discussed for previous alternatives. The soils would then be disposed of off site in a non-
40 hazardous industrial landfill. Because of the absence of RCRA hazardous wastes (listed or
41 characteristic), and the relatively low concentrations of PCBs (less than 50 mg/kg), the soil

1 does not need to go to a RCRA- or TSCA-regulated landfill. Because the soils are mostly
2 surficial, backfilling may not be required (i.e., regrading may be sufficient to return the site
3 to an acceptable grade). Regrading may be sufficient for handling any of the deeper areas of
4 excavation, and for smoothing out, in general, the excavated area.

5 **4.1.6.2 Evaluation**

6 **Effectiveness**

7 This technology would remove all routes of exposure, and meet RAOs for the
8 operable unit. It would not satisfy the preference for treatment at the site. However, for the
9 relatively small volume of contaminated soil and the variety of contaminants, treatment may
10 not be appropriate.

11 **Implementability**

12 Because of the non-hazardous nature of the soil, there should be no obstacles to
13 implementing this alternative.

14 **Relative Cost**

15 Excavation and off-site disposal costs are expected to be low to moderate relative to
16 treatment, containment, and institutional actions.

17 **4.1.7 Alternative A7: Excavation and Off-Site Incineration**

18 **4.1.7.1 Description**

19 This alternative would be similar to Alternative A6, except that the soils would be
20 sent to an off-site incinerator rather than a landfill. The incinerator would thermally destroy
21 the organic contaminants in the soil, while the metals would remain in the ash. The
22 incineration facility would then dispose of the ash in accordance with applicable regulations.

23 **4.1.7.2 Evaluation**

24 **Effectiveness**

25 This alternative would remove all routes of exposure and meet all RAOs for the
26 operable unit. It would also satisfy the preference for treatment for the organic contaminants.

27 **Implementability**

28 There are no obstacles to implementation expected with this alternative.

1 **Relative Cost**
2

3 Excavation and off-site incineration costs are expected to be very high relative to
4 institutional controls, containment, disposal, and other treatment methods.
5

6 **4.1.8 Selection of DRMO Yard Alternatives for Detailed Analysis**
7

8 The following alternatives are retained for further consideration in the detailed
9 analysis:
10

11 A1: No Further Action;
12 A2: Institutional Actions;
13 A3: Containment with Capping;
14 A4: Excavation, Solidification, and On-Site Disposal; and
15 A6: Excavation and Off-Site Disposal.
16

17 The other two alternatives were eliminated because they were both significantly more complex
18 and thus would be more expensive, without providing additional levels of protection to human
19 health and the environment. Alternative A5 called for two treatments that would require
20 significant development to work well enough to allow the treated soils to be backfilled. The
21 effort involved is not warranted in light of the small volume of soil to be treated. Alternative
22 A7 calls for off-site incineration, which is not warranted for the levels of organic
23 contaminants present in the soils at this operable unit. Table 4-1 provides a summary of this
24 screening. Alternatives A1, A2, A3, A4, and A6 are analyzed in greater detail in Section 5.
25

26 **4.2 UST 13 GROUNDWATER OPERABLE UNIT ALTERNATIVES**
27

28 Six alternatives were developed for the UST 13 groundwater operable unit:
29

30 B1: No Further Action;
31 B2: Institutional Actions;
32 B3: Intrinsic Remediation (with long-term monitoring);
33 B4: Containment via Capping;
34 B5: Groundwater Extraction with On-Site Treatment via Carbon Adsorption; and
35 B6: In Situ Groundwater Bioremediation.
36

37 Each of these alternatives is described and evaluated below.
38

39 **4.2.1 Alternative B1: No Further Action**
40

41 **4.2.1.1 Description**
42

43 This alternative would involve no remedial action; no treatment or containment would
44 be performed, and the contamination would remain in its present state. The selection of this
45 alternative would not satisfy the remedial action objectives for the UST 13 operable unit.
46 This alternative would leave contaminated groundwater in place; it would also take no action

1 in eliminating the exposure pathways of these contaminants. Monitoring of the groundwater
2 would continue annually and the site would be reevaluated after 5 years. This will ensure that
3 changes at the site do not affect the conclusions concerning the risks of the No Further Action
4 alternative.

5 **4.2.1.2 Evaluation**

6 **Effectiveness**

7
8
9 The no-action alternative is ineffective and does not meet the remedial action
10 objectives for this operable unit. The human health risks would remain as described in the
11 risk assessment. However, because the contamination is in a very small area (less than 0.25
12 acres), with very slow groundwater movement (and groundwater from the site ultimately
13 flows under Shepley's Hill Landfill), it is highly unlikely that it could impact human health or
14 the environment. Groundwater would continue to exceed cleanup goals, but will be
15 monitored for deterioration.

16
17 **Implementability**

18
19 The No Further Action alternative would be difficult to implement as the current
20 situation exceeds groundwater ARARs and a waiver from meeting the ARARs would have to
21 be obtained. This waiver may be difficult to obtain.

22
23 **Relative Cost**

24
25 As this alternative involves no remedial action, institutional action, containment,
26 collection, treatment, or disposal costs, only monitoring costs are associated with it.
27 Although not easily quantified, the costs of future liability from contaminants remaining
28 within the bedrock on site are not likely to be significant.

29
30 **4.2.2 Alternative B2: Institutional Actions**

31
32 **4.2.2.1 Description**

33
34 Institutional actions are minimal actions taken to reduce exposure to contaminated
35 media. This alternative would involve no actual remediation. Examples of the actions that
36 could be taken include prohibition of drinking water well installation, the installation of a
37 fence surrounding the perimeter of the operable unit, and the prohibition of future
38 development of the land, possibly through deed restrictions. It would also include continued
39 monitoring of the wells every 5 years for up to 30 years to detect the movement of
40 contaminants, if any. This alternative fails to remove the contamination, and if these
41 institutional controls were violated in some way (e.g., if a drinking water well were installed
42 at the site), the protection of human health would be compromised. However, the aquifer
43 yield at this site is so low that a drinking water well would probably not provide sufficient
44 water even for domestic supply.

1 **4.2.2.2 Evaluation**

2 **Effectiveness**

3 This alternative would not be effective in reducing the level of contamination at the
4 UST 13 operable unit. It would have no more of a remedial effect than Alternative B1, No
5 Further Action. However, it does have the potential, if executed properly, to minimize
6 exposure to the contaminants of concern. The effectiveness of the institutional actions would
7 be directly dependent on the type of control implemented.

8 **Implementability**

9 Implementation of this alternative would depend on legal authority and requirements.
10 It may be difficult to implement Alternative B2 as groundwater ARARs would still be
11 exceeded, and it may be difficult to obtain a waiver of this requirement.

12 **Relative Cost**

13 Institutional actions are inexpensive relative to treatment, containment, collection, and
14 disposal.

15 **4.2.3 Alternative B3: Intrinsic Remediation**

16 **4.2.3.1 Description**

17 Intrinsic remediation is an approach that relies on natural attenuation to remediate
18 contaminants in the subsurface. Because it relies upon slow natural processes, and involves
19 long-term monitoring to observe the gradual natural restoration of the site to pre-contaminant
20 conditions, it necessarily involves institutional action. During the period of restoration, access
21 to the site for some uses, such as water supply, is necessarily restricted, since the
22 groundwater contaminant levels exceed ARARs.

23 What differentiates intrinsic remediation from institutional action is the degree of
24 characterization of the site, the modeling of groundwater flow and contaminant migration, and
25 the long-term monitoring effort to ensure that natural attenuation is working as expected.

26 Because of these needs, the UST 13 area would require the installation of additional
27 wells (three are costed), integration of the field data into a groundwater flow and contaminant
28 transport model, and the performance of long-term monitoring.

29 **4.2.3.2 Evaluation**

30 The detailed characterization of the site, with eight wells within a two-acre area
31 around the former tank (UST 13) location, will be combined with borehole and geophysical
32 (seismic) data to refine the shape of the top of bedrock. The water levels in the wells will
33 define the relationship between the water table and top of bedrock, and hence the relationship

1 between the "overburden" and "bedrock" aquifers with differing hydraulic conductivities and
2 anisotropies.

3
4 A groundwater model will incorporate climatic, geologic, hydrologic and contaminant
5 distribution data, to test various assumptions about groundwater flow, and to explore the
6 sensitivity of the model to changing assumptions. Once the flow model has been calibrated to
7 reproduce the main features of the site and to fit satisfactorily with the field data, transport
8 modeling of contaminants can be performed.

9
10 Continued monitoring of the site on a yearly basis will confirm or disprove the
11 projected rates of contaminant movement. If the monitoring proves that contaminants are not
12 leaving the site at levels above ARARs, then the remedy will be protective of human health
13 and the environment.

14
15 If monitoring demonstrates that the model is underestimating rates and levels of
16 movement of contaminants, then the remedy may have to be reviewed and perhaps amended.

17
18 **Implementability**

19
20 The materials, techniques, and labor necessary to implement this alternative are all
21 readily available, and aspects of the proposed program have already been implemented.
22 Many vendors are available to provide competitive bids on all aspects of the program: well
23 installation, data collection, modeling, and data assessment.

24
25 After well installation, O&M would be minimal, and continuing costs of sampling and
26 analysis relatively predictable. Investigation-derived waste would have to be properly stored
27 and handled, but no hazardous waste generation is expected.

28
29 If successfully implemented, this remedial alternative would be protective of human
30 health and the environment, and would minimally disrupt site activities.

31
32 **Relative Cost**

33
34 The well installation, continued sampling, and monitoring would be more expensive
35 than institutional controls alone. It would have to be implemented with restrictions on
36 specific activities up to the time of its completion.

37
38 **4.2.4 Alternative B4: Containment Via Capping**

39
40 **4.2.4.1 Description**

41
42 This alternative would construct a cap over the area of contaminated groundwater.
43 Soils contaminated by the UST leak have already been removed. Thus the principle objective
44 of the cap would be to reduce infiltration of precipitation into the overburden above the
45 bedrock aquifer, and hence reduce recharge to the aquifer. This would reduce the plume
46 migration rate within the aquifer. The cap would be as described for Alternative A3. Its

1 principal component would be a layer of 10^{-7} cm/sec permeability clay to eliminate water
2 infiltration.

3
4 **4.2.4.2 Evaluation**

5
6 **Effectiveness**

7
8 Although capping would reduce the infiltration of precipitation and snow melt, the
9 proposed cap would sit approximately 12 feet above the water table, allowing the water to
10 seep in from the adjacent uncapped areas and reach the aquifer. Augmenting the cap with
11 vertical barriers would not be effective in stopping the infiltration from these adjacent
12 uncapped areas, since the aquifer exists mainly in bedrock and vertical barriers cannot be
13 installed in bedrock except with great difficulty and expense. Under present conditions, the
14 migration of the plume is being restrained by the low hydraulic conductivity and low gradient
15 of the bedrock aquifer. Furthermore, the area affected is small, less than 0.25 acres, and this
16 aquifer is not used as a potable water supply.

17
18 **Implementability**

19
20 The technology required to cap and grade the UST 13 area is reliable and well
21 established. No specialized techniques, material, or labor would be required. Long-term
22 maintenance and groundwater monitoring would be required to ensure that the integrity of the
23 cap is maintained. In order to minimize erosion, erosion controls may be necessary. Future
24 residential use of the area would likely be precluded and would be reviewed by the
25 appropriate boards or agencies. However, a waiver may be required because groundwater
26 ARARs would still be exceeded, and this waiver may be difficult to obtain.

27
28 **Relative Cost**

29
30 Capping costs are dependent on the size of the area to be capped as well as cap
31 design. Although the size of the UST area is small, the design of the cap is multilayer. In
32 addition, long-term maintenance and groundwater monitoring would increase costs, making
33 expected capping O&M costs moderate relative to institutional action, collection, treatment,
34 and disposal.

35
36 **4.2.5 Alternative B5: Groundwater Extraction with On-Site Treatment via Carbon
37 Adsorption**

38
39 **4.2.5.1 Description**

40
41 Under this alternative, groundwater would be extracted by an extraction system
42 composed of pumping wells. The groundwater would then be passed through a liquid-phase
43 carbon adsorption system in order to remove organic contamination. The treated groundwater
44 would then be transported to the town of Ayer POTW or commercial aqueous waste treatment
45 facility.

1 **4.2.5.2 Evaluation**
2

3 **Effectiveness**
4

5 Any groundwater that could be recovered would be treated effectively by carbon
6 adsorption, a well-demonstrated technology that can remove organics from aqueous wastes to
7 levels below 1 part per billion (ppb). Carbon adsorption, was selected over air stripping
8 (which was also retained in Section 3) because it is more effective on a wider range of
9 organics. Also, air stripping would require treatment of offgas and use of pre-treatment
10 technologies (separation, precipitation, etc.) to remove metals prior to air-stripping.

11 The UST 13 area aquifer exists mostly in the underlying bedrock and the hydraulic
12 conductivity of the bedrock in this area is relatively low (3.5×10^{-4} cm/sec) and the area
13 involved is small. Therefore, it is expected that very little water could be extracted. It is
14 estimated that less than 1 gallon per minute (gpm) would be extracted. The migration of the
15 plume would be halted, but it is currently being restrained by the low hydraulic conductivity
16 and low gradient of the bedrock aquifer. Furthermore, this aquifer is not used as a potable
17 water supply so no exposure currently occurs.

18 **Implementability**
19

20 The techniques, materials, and labor necessary to implement this alternative are
21 readily available. Many vendors are available to provide competitive bids for the construction
22 and operation of a groundwater extraction system. Impacts on surrounding land use from the
23 installation of extraction wells would be minimal. A carbon adsorption system would be
24 relatively simple to construct and operate. The necessary materials and equipment are
25 available from several vendors. O&M requirements would be minimal, involving monitoring
26 of the effluent for breakthrough. The treated water would be transported to the POTW via
27 truck, rather than a new dedicated pipeline, as transporting it is more feasible, based on the
28 low volume expected. (Transport to a POTW was considered easier to implement than
29 discharge to surface water, which would have required a NPDES permit and SPDES permit
30 for all compounds.) Implementation of this alternative would satisfy the statutory preference
31 for using treatment as a principal element in remediation.

32 **Relative Cost**
33

34 The extraction, carbon adsorption, and disposal costs associated with this alternative
35 are expected to be moderate to high compared with the costs of institutional controls,
36 containment, and other treatment and disposal technologies. The spent carbon can be
37 regenerated, but for strongly adsorbed contaminants, the cost of such regeneration can be
38 higher than simple replacement with new carbon.

1 **4.2.6 Alternative B6: In Situ Groundwater Bioremediation**
2

3 **4.2.6.1 Description**
4

5 Under this alternative, remediation of groundwater would be accomplished in situ via
6 bioremediation using injection and extraction wells. In addition to bioremediation units, an
7 in-line mixing tank and groundwater extraction pump would be needed. Nutrients and an
8 oxygen source would be added to the groundwater through the in-line mixing tank. Air
9 would be delivered to contaminated groundwater through injection wells. Treatability studies
10 or field pilot tests would be required.

11 **4.2.6.2 Evaluation**
12

13 **Effectiveness**
14

15 Under suitable conditions with proper design, in situ bioremediation can reduce
16 organics to nondetectable levels, converting contaminants to innocuous compounds.
17 However, at the UST 13 area, the aquifer exists mostly in the underlying bedrock, the
18 hydraulic conductivity of which is relatively low (3.5×10^{-4} cm/sec). Due to this low
19 hydraulic conductivity, injected oxygen and nutrients may not be adequately delivered to the
20 aquifer, making this method of remediation ineffective. (Ex situ bioremediation was
21 dismissed in favor of in situ because there would be even more difficulty extracting the
22 volume of water required for ex situ treatment.) In addition, this low hydraulic conductivity,
23 as well as the low gradient of the bedrock aquifer, is keeping the plume from migrating from
24 the area. Furthermore, metals that exist in the groundwater may inhibit biological activity,
25 and this aquifer is not used as a potable water supply.
26

27 **Implementability**
28

29 The techniques, materials, and labor necessary to implement in situ bioremediation of
30 groundwater are readily available. However, long periods of time may be required to meet
31 cleanup goals. In addition to the potentially long time frame associated with remediation,
32 treatability studies or field pilot testing necessary prior to full-scale remediation may require
33 as long as six months to one year to complete. In situ bioremediation must be properly
34 controlled to ensure that contaminants or injected materials do not migrate from the point of
35 injection, spreading contamination. It is important that the effectiveness of the system is
36 closely monitored after initial full-scale startup. Periodic modifications will likely be
37 necessary in order to adjust injection and/or extraction flow rates, as well as oxygen and
38 nutrient supplies. As an in situ process, bioremediation would cause minimal land
39 disturbance.
40

41 **Relative Cost**
42

43 In situ bioremediation costs are expected to be moderate compared with the costs of
44 institutional controls, containment, collection, disposal, and other treatment technologies.
45

1 **4.2.7 Selection of UST 13 Alternatives for Detailed Analysis**

2
3 The following UST 13 alternatives will be retained for analysis in the detailed
4 analysis of alternatives:

5
6 B1: No Further Action;
7 B2: Institutional Actions; and
8 B3: Intrinsic Remediation (With Long-Term Monitoring).

9
10 The other three alternatives addressed control and/or treatment of the groundwater plume. As
11 previously indicated (see Section 1.2.1.3), this small plume is already controlled to a great
12 extent by the low permeability and low hydraulic gradient of the bedrock aquifer. The low
13 permeability also renders extraction and treatment approaches infeasible.

14
15 It is clear that adopting Alternative B2, Institutional Actions, will be more protective
16 of human health and the environment than Alternative B1. Groundwater ARARs would still
17 be exceeded in the very limited area of actual contamination. However, it is not technically
18 practical to remediate this plume. This would be a basis of an ARAR waiver. The lack of
19 plume migration ensures that no risk will be present in the future outside this site. Alternative
20 B3, Intrinsic Remediation, will provide a similar degree of protection for human health and
21 the environment, but will do so with more certainty and better data. The increased number of
22 monitoring points ensures that it is less likely that any contaminants can leave the site
23 undetected, and the use of a model allows for verifiable predictions and model recalibrations
24 to evaluate continued effectiveness over time. Table 4-1 provides a summary of this
25 screening. Alternatives B1, B2, and B3 are analyzed in greater detail in Section 5.

26
27 **4.3 POL STORAGE AREA/DRMO YARD GROUNDWATER OPERABLE**
28 **UNIT ALTERNATIVES**

29
30 Three alternatives were developed for the POL Storage Area/DRMO Yard
31 groundwater operable unit:

32
33 C1: No Further Action;
34 C2: Institutional Action; and
35 C3: Intrinsic Remediation (With Long-Term Monitoring).

36
37 Each of these alternatives is described and evaluated below.

38
39 **4.3.1 Alternative C1: No Further Action**

40
41 **4.3.1.1 Description**

42
43 This alternative would involve no remedial action; no treatment or containment would
44 be performed, and the contamination would remain in its present state. The selection of this
45 alternative would not satisfy the remedial action objectives for the POL Storage Area/DRMO
46 Yard groundwater operable unit. This alternative would leave contaminated groundwater in

1 place; it would also take no action in eliminating the exposure pathways of these
2 contaminants. Monitoring of the groundwater would continue annually and the site would be
3 reevaluated after 5 years. This will ensure that changes at the site do not affect the
4 conclusions concerning the risks of the No Further Action alternative.

5

6 4.3.1.2 Evaluation

7

8

Effectiveness

9

10 The no-action alternative is ineffective and does not meet the remedial action
11 objectives for this operable unit. The human health risks would remain as described in the
12 risk assessment. However, because the observed contamination is in only three wells in a
13 small area approximately 2 acres, and MCLs are only slightly exceeded, it is highly unlikely
14 that it could impact human health or the environment. Groundwater could continue to exceed
15 cleanup goals, but will be monitored for deterioration.

16

17 Implementability

18

19 The No Further Action alternative would be difficult to implement as the current
20 situation exceeds groundwater ARARs and a waiver from meeting the ARARs would have to
21 be obtained. This waiver may be difficult to obtain.

22

23 Relative Cost

24

25 As this alternative involves no remedial action, institutional action, containment,
26 collection, treatment, or disposal costs, only monitoring costs are associated with it.
27 Although not easily quantified, the costs of future liability from the low level of contaminants
28 remaining in the groundwater on site are not likely to be significant.

29

30 4.3.2 Alternative C2: Institutional Actions

31

32

4.3.2.1 Description

33

34 Institutional actions are minimal actions taken to reduce exposure to contaminated
35 media. This alternative would involve no actual remediation. Examples of the actions that
36 could be taken include prohibition of drinking water well installation, possibly through deed
37 restrictions. It would also include continued monitoring of the wells every 5 years for up to
38 30 years to detect the movement of contaminants, if any. This alternative fails to remove the
39 contamination, and if these institutional controls were violated in some way (e.g., if a
40 drinking water well were installed at the site), the protection of human health would be
41 compromised. However, the aquifer yield at this site is low so a drinking water well would
42 probably not provide sufficient water for industrial supply, and the site will be zoned
43 industrial.

1 **4.3.2.2 Evaluation**

2 **Effectiveness**

3 This alternative would not be effective in reducing the level of contamination at the
4 POL Storage Area/DRMO Yard groundwater operable unit. It would have no more of a
5 remedial effect than Alternative B1, No Further Action. However, it does have the potential,
6 if executed properly, to minimize exposure to the contaminants of concern. The effectiveness
7 of the institutional actions would be directly dependent on the type of control implemented.

8 **Implementability**

9 Implementation of this alternative would depend on legal authority and requirements.
10 It may be difficult to implement Alternative B2 as groundwater ARARs could still be
11 exceeded, and it may be difficult to obtain a waiver of this requirement.

12 **Relative Cost**

13 Institutional actions are inexpensive relative to treatment, containment, collection, and
14 disposal.

15 **4.3.3 Alternative C3: Intrinsic Remediation (With Long-Term Monitoring)**

16 **4.3.3.1 Description**

17 Intrinsic remediation is an approach that relies on natural attenuation to remediate
18 contaminants in the subsurface. Because it relies upon slow natural processes, and involves
19 long-term monitoring to observe the gradual natural restoration of the site to pre-contaminant
20 conditions, it necessarily involves institutional action. During the period of restoration the
21 access to the site for some uses, such as water supply wells, is necessarily restricted, since the
22 groundwater contaminant levels exceed ARARs.

23 What differentiates intrinsic remediation from institutional action alone, is the degree
24 of characterization of the site, the modeling of groundwater flow and contaminant migration,
25 and the long-term monitoring effort to ensure that natural attenuation is working as expected.

26 The concerns expressed by the regulatory agencies about possible Dense Non-
27 Aqueous Phase Liquid (DNAPL) in the form of TCE liquid in the bedrock, and possible
28 migration of benzene, toluene, ethylbenzene, and xylenes (BTEX) in the lower part of the
29 overburden aquifer downgradient of the POL Storage Area, will be addressed by this
30 alternative.

31 To implement intrinsic remediation, additional site characterization will be required
32 and for costing purposes, the Army is proposing five new wells. Four of these wells would
33 be monitoring the overburden aquifer downgradient of "plumes" of hydrocarbon
34 contamination in the soil, identified by field screening techniques, and one will be a bedrock

1 well adjacent to POL-3 which has shown persistent TCE contamination. Data collected from
2 these new wells and the existing wells on and around the site will be integrated into a
3 groundwater flow model. Once this has been established, it will be used as input to a model
4 to simulate contaminant transport. As long as it appears that there is a potential public health
5 threat from the contaminants in the groundwater, institutional restrictions on groundwater use
6 would be maintained, and monitoring would continue.

7

8 4.3.3.2 Evaluation

9

10 The detailed investigation of the site and its setting, by over 20 wells and over 60
11 boreholes will allow for the development of a well defined and characterized groundwater
12 model. These data combined with results of seismic surveys will be used to define the shape
13 of top-of-bedrock in greater detail than at present, and show the relationship of the water table
14 to the top of bedrock. This in turn will show how the different hydraulic conductivities and
15 isotropy/anisotropy affect the flows of water within and between the "overburden" and
16 "bedrock" aquifers. The groundwater flow model will, in turn, be used for a contaminant
17 transport model, which will incorporate contaminant distribution and groundwater flow to
18 predict migration, and to test the sensitivity of the model to variations in different parameters
19 included in the model.

20

21 Continued long-term monitoring of the site, initially on a yearly basis, will confirm or
22 disprove the project rates of contaminant movement and/or decay. If the monitoring proves
23 that the contaminants are not leaving the institutional control area at levels above ARARs,
24 then the remedy will have been shown to be protective of human health and the environment.

25

26 Implementability

27

28 The materials, techniques, and labor necessary to implement this alternative are all
29 readily available, and aspects of this program have already been implemented. Many vendors
30 are available to provide competitive bids on the different components of the program,
31 including well installation, data collection, modeling, and data assessment.

32

33 After new wells are installed, O&M would be minimal and continued costs of
34 sampling and analysis relatively predictable. Investigation-derived waste would have to be
35 properly stored and handled, but no hazardous waste generation is expected.

36

37 If successfully implemented, this remedial alternative would be protective of human
38 health and the environment, and would minimally disrupt site activities.

39

40 Relative Cost

41

42 The well installation, expanded sampling, and modeling would be more expensive
43 than institutional controls alone, and would have to be implemented in conjunction with
44 institutional controls until such time as the long-term monitoring shows that there is no
45 continuing exceedance of risk-based standards.

1 Feasibility Study: Fort Devens FA II
2 Section No.: 4
3 Revision No.: 2
4 Date: January 1997

1 **4.3.4 Selection of POL Storage Area/DRMO Yard Groundwater**

2 **Alternatives for Detailed Analysis**

3 All three alternatives, C1: No Further Action; C2: Institutional Actions, and C3:
4 Intrinsic Remediation, will be retained for detailed analysis of alternatives.
5
6

Table 4-1

RESULTS OF SCREENING OF ALTERNATIVES

DRMO SOILS OPERABLE UNIT

Alternative	Retained	Comment
A1: No Further Action	Yes	
A2: Institutional Actions	Yes	
A3: Containment via Capping	Yes	
A4: Excavation, Solidification, On-site Disposal	Yes	
A5: Excavation, Solvent Extraction, Thermal Desorption, Backfilling	No	Does not provide significantly greater level of treatment than A4, but would be much more complex and expensive.
A6: Excavation and Off-Site Disposal	Yes	
A7: Excavation and Off-Site Incineration	No	Does not provide a significantly greater level of environmental protection than A4 or A6 to justify higher costs.

UST 13 GROUNDWATER OPERABLE UNIT

Alternative	Retained	Comment
B1: No Further Action	Yes	
B2: Institutional Actions	Yes	
B3: Intrinsic Remediation	Yes	Requires further site characterization.
B4: Containment via Capping	No	Would not eliminate infiltration; would only reduce it. Also, plume is currently contained by the low hydraulic conductivity and low gradient of the bedrock.
B5: Groundwater Extraction with On-Site Treatment via Carbon Adsorption	No	Would extract a volume of groundwater too small to be effective due to the low permeability of the bedrock.
B6: In Situ Groundwater Bioremediation	No	Not likely to deliver adequate oxygen and nutrients to groundwater due to the low permeability of the bedrock. Also, metals may hinder remediation.

POL STORAGE AREA/DRMO YARD GROUNDWATER OPERABLE UNIT

Alternative	Retained	Comment
C1: No Further Action	Yes	
C2: Institutional Actions	Yes	
C3: Intrinsic Remediation (with long-term monitoring)	Yes	Requires further site characterization.

1
2 **5. DETAILED ANALYSIS OF REMEDIAL ALTERNATIVES AND MONITORING**
3
4
5
6

7 In this section, the remedial technologies that were identified and retained in Section
8 are presented as detailed remedial alternatives. To gauge the overall feasibility and
9 acceptability, the relevant information for the selection of a remedy is provided in a detailed
10 analysis with respect to the nine EPA criteria encompassing the statutory requirements of
11 CERCLA. The nine criteria by which the alternatives will be assessed include, in three
12 groups:

13

- 14 • Overall protection of human health and the environment;
- 15 • Compliance with applicable or relevant and appropriate requirements;
- 16 • Reduction of toxicity, mobility, or volume through treatment;
- 17 • Long-term effectiveness and permanence;
- 18 • Short-term effectiveness;
- 19 • Implementability;
- 20 • Cost;
- 21 • State acceptance; and
- 22 • Community acceptance.

23 The first two items are considered threshold criteria. An alternative must satisfy both
24 of these in order to be eligible for selection. Overall protection describes how the alternative,
25 as a whole, achieves and maintains protection of human health and the environment. The
26 compliance criterion assesses whether an alternative complies with ARARs, or, if a waiver is
27 required, how it is justified.

28 The next five are known as balancing criteria. They are technical criteria used to
29 evaluate effectiveness and implementability. Performance of specific treatment technologies is
30 evaluated in the reduction of toxicity, mobility, or volume (TMV) criterion. The extent to
31 which TMV issues are met in each alternative is evaluated and predicted. Long-term
32 effectiveness evaluates whether an alternative will preserve human health and the environment
33 after RAOs have been met. The magnitude of residual risk and adequacy of controls are also
34 considered under this criterion. Short-term effectiveness of an alternative considers both the
35 time required until RAOs are met as well as an evaluation of the impacts on human health and
36 the environment during the remediation stage. The implementability criterion is concerned
37 with the technical and administrative feasibility of an alternative. Post remediation monitoring
38 and additional action are also considered under this criterion. Finally, the major cost
39 components of each alternative are estimated and evaluated.

Feasibility Study: Fort Devens FA II
Section No.: 5
Revision No.: 2
Date: January 1997

1 The assessment of state and community acceptance criteria will be addressed in the
2 Record of Decision (ROD) following public comment on the RI/FS report and proposed plan.
3

4 Following the individual analyses of criteria for each alternative, the alternatives are
5 compared and contrasted based on each set of criteria. A summary of the criteria assessment
6 of the DRMO Yard Soils Operable Unit alternatives subjected to the detailed screening in this
7 section is presented in Table 5-1. For ease of referencing, the costs reported in the text and
8 in Table 5-1 for the DRMO Operable Unit have been rounded to three significant digits. A
9 breakdown of the costs associated with the various DRMO Operable Unit alternatives are
10 reported in Tables 5-2 through 5-7. Detailed costs for the UST 13 groundwater Operable
11 Unit alternatives are provided in Tables 5-8 through 5-10.
12

13 Detailed costs of the POL Storage Area/DRMO Yard groundwater operable unit
14 alternatives are provided in Tables 5-11 through 5-13.
15

16 **5.1 DRMO SOILS OPERABLE UNIT (AOC 32)**

17

18 Five alternatives for remediation of DRMO Yard soils were retained from the initial
19 alternative screening (Section 4). These are described in detail in this section and analyzed
20 with respect to the criteria presented by the EPA. The five alternatives discussed below are:
21

- 22 Alternative A1: No Further Action
- 23 Alternative A2: Institutional Actions
- 24 Alternative A3: Containment via Capping
- 25 Alternative A4: Excavation, Solidification, and On-Site Disposal
- 26 Alternative A6: Excavation and Off-Site Disposal

27 Figure 2-2 shows the detections at AOC 32 that exceed cleanup goals. Figure 2-3 shows the
28 DRMO Yard areas requiring remediation based on the detections above cleanup goals.
29

30 **5.1.1 Alternative A1: No Further Action**

31 **5.1.1.1 Detailed Description**

32 The "No Further Action" alternative is developed and evaluated to establish a baseline
33 for comparison with other remedial alternatives. Under this alternative, no remedial action of
34 any type would be undertaken. The soils at the east DRMO Yard would not be removed or
35 treated in any way. It is assumed that the contamination would remain in its present state and
36 pose the same risks as currently exist including the potential for continued contamination of
37 groundwater.
38

39 Groundwater monitoring would be performed annually for 5 years under this
40 alternative. After 5 years the need for continued monitoring will be reviewed.
41

1 **5.1.1.2 Criteria Analysis**

2 **Overall Protection of Human Health and the Environment**

3 The "No Further Action" alternative would neither contain, treat, nor destroy the
4 contaminants in the soils at the DRMO Yard. No measures, either remedial or institutional,
5 would be taken to protect human health or the environment. Monitoring, however, would be
6 performed in order to detect contaminant migration. This would influence a decision to take
7 additional action, if necessary.

8 **Compliance with ARARs**

9 Maximum detections of PCBs currently exceed the cleanup goal based on TSCA,
10 which is considered a chemical-specific ARAR. Therefore, a waiver would have to be
11 granted to pursue this alternative. However, such a waiver would be difficult to obtain
12 because there would be no reduction of human health risk under this alternative. No location-
13 specific ARARs would be triggered (see Table 2-4). No action-specific ARARs would be
14 triggered. Table 5-14 lists all ARARs and TBCs for the DRMO Yard soils remedial
15 alternatives.

16 **Reduction of Toxicity, Mobility, or Volume through Treatment**

17 The "No Further Action" alternative would have no effect on the toxicity, mobility,
18 or volume of contamination. Monitoring, however, would detect any contaminant migration
19 over time.

20 **Long-term Effectiveness and Permanence**

21 Because the "No Further Action" alternative will not meet the RAOs, the residual risk
22 is equivalent to the existing risks. The potential for human or ecological exposure to
23 contaminants in surface soils would endure, as would the potential for the contamination of
24 other media. This alternative does not satisfy the preference for treatment and permanence,
25 but groundwater monitoring will assess long-term contaminant migration and human health
26 risks, allowing appropriate action to be taken if conditions change.

27 **Short-term Effectiveness**

28 The "No Further Action" alternative will have no impact on existing site conditions.
29 Personal protection equipment (PPE) and field instruments will be used to control potential
30 exposures to field personnel during monitoring.

31 **Implementability**

32 The "No Further Action" alternative does not present any technical implementability
33 obstacles. Monitoring and/or future remedial action would be easily applied. However, the
34 failure to comply with ARARs poses a potentially difficult administrative obstacle.

1 Costs
2

3 There are no capital costs associated with this alternative. O&M costs, as presented
4 in Table 5-2, are associated with the groundwater sampling events, to be conducted for 5
5 years. It is assumed that existing wells would be sampled, and there would be no new wells
6 installed. The approximate present worth of the "No Further Action" alternative is \$80,380,
7 assuming no further monitoring is required after 5 years.

8
9 5.1.2 Alternative A2: Institutional Actions
10

11 5.1.2.1 Detailed Description
12

13 No remediation would occur under this alternative; activity would be limited to
14 minimal measures intended to reduce exposure to contaminated media. Deed restrictions
15 would limit land use and development. The land is currently slated for industrial land use by
16 the Massachusetts Land Bank, which will control development after the Army releases the
17 property, thus no further zoning alterations would be required.

18 There is currently a 6 foot high chain-linked fence with a barbed wire top
19 surrounding the east DRMO and tire yards. However, the contamination is found in drainage
20 ditches along the perimeter of the east yard. It would therefore be necessary to move the
21 eastern and western portions of the fence to the outside of the drainage ditches to ensure that
22 the contaminated zone is fully enclosed. The western fence would be moved to the edge of
23 Cook Street, approximately 15 feet to the west. The eastern fence would be moved 15 feet to
24 the east. Personnel constructing the fence will be outfitted in level C PPE to prevent dermal
25 exposure to and ingestion and inhalation of contaminated soil. Level C PPE includes, but is
26 not limited to, a full-face air-purifying respirator with dual cartridges for filtering organic
27 vapors and particulates; chemical resistant clothing; leather safety boots with chemical
28 resistant overboots as necessary; a hard hat; and chemical resistant gloves.

29
30 The new fencing would isolate the contaminated soils and reduce exposure to
31 authorized future site workers. Site workers would be trained in safety precautions to
32 minimize exposure to the surface soils, and work shifts would be organized to minimize
33 frequency and duration of exposure. Level C PPE would be considered when future site
34 activities are conducted within the contaminated area (i.e., inside the fence).

35
36 Groundwater monitoring would also be performed under this alternative. Every 5
37 years for a period of 30 years, the site conditions will be reviewed to determine the extent of
38 contaminant migration. A groundwater sampling event will be performed during each of
39 these reviews. In addition, exposure scenarios will be revisited based on site use at the time
40 of each review. If warranted, additional action will be considered at these times.

1 **5.1.2.2 Criteria Analysis**

2 **Overall Protection of Human Health and the Environment**

5 Institutional actions would not treat or destroy any of the contaminants; however, they
6 would isolate the contamination in a restricted area. Future site work within the restricted
7 area would require PPE. Therefore, if executed properly, this alternative would reduce
8 human exposure to the contaminants to acceptable risk levels, meeting the first RAO. Proper
9 execution includes ensuring worker safety both during and after the construction phase, as
10 well as periodic maintenance of the fence. Risks to the environment would be unaffected;
11 however, ecological risks were found to be minimal. The other two RAOs would not be met
12 under this alternative. Groundwater monitoring would also aid in the protection of human
13 health and the environment in that it would be used to evaluate potential contaminant
14 migration. This would influence a decision to take additional action, if necessary.

15 **Compliance with ARARs**

18 The surface soils would still fail the TSCA level for PCBs under this alternative,
19 which is a chemical-specific ARAR (see Table 2-1). A waiver application should be
20 performance based, i.e., if properly executed, the human health risks may be reduced to a
21 level nearly equivalent with Alternatives A3, A4, and A6. Future use of the site would
22 necessarily be limited. No location-specific ARARs would be triggered (see Table 5-14). No
23 action-specific ARARs would be triggered.

25 **Reduction of Toxicity, Mobility, or Volume through Treatment**

27 Provisions under this alternative would have no effect on toxicity, mobility, or
28 volume of contamination. Monitoring, however, would detect contaminant migration over
29 time.

31 **Long-term Effectiveness and Permanence**

33 This alternative is intended to reduce potential exposure routes, and residual risks
34 would be minimal if implemented properly. However, because this alternative does not
35 include any treatment of surface soils, long-term effectiveness depends on adequate
36 maintenance. Fencing and monitoring wells are susceptible to damage over time. If the
37 controls (i.e., fencing and development restrictions) or wells are not maintained, then the
38 residual risk could become equivalent with current risks. Therefore, this alternative does not
39 satisfy the preference for treatment and permanence.

41 **Short-term Effectiveness**

43 There would be no short-term effects on the community or the environment under this
44 alternative. Exposure to the workers installing the controls or performing sampling activities
45 would be controlled through respiratory and dermal protection. Minimal time, probably less

Feasibility Study: Fort Devens FA II
Section No.: 5
Revision No.: 2
Date: January 1997

1 than 1 week, would be required to complete the field activities, meeting the first RAO.
2 Groundwater sampling could be performed in a few days per sampling event.

3

4 Implementability

5

6 Institutional actions do not present any technical implementability obstacles.
7 Monitoring and/or future remedial action would be easily applied. However, the failure to
8 comply with ARARs poses a potentially difficult administrative obstacle. Because human
9 exposure, and therefore, human health risks would be reduced, a waiver to ARARs could
10 potentially be obtained.

11

12 Costs

13

14 Capital costs associated with this alternative involve fenceline changes,
15 mobilization/demobilization, and health and safety costs. Approximately 840 feet of fence
16 along the eastern and western edges of the east yard would have to be moved to widen the
17 area of enclosure. An additional 60 feet of fence would have to be added to the existing line.
18 The costs associated with this alternative are presented in Table 5-3 and include semiannual
19 inspection and maintenance of the fenceline, as well as site evaluation and groundwater
20 sampling every 5 years. It is assumed that existing wells will be sampled, and no new wells
21 will be installed. The estimated capital costs are \$17,950. The present worth of O&M and
22 monitoring costs combined, assuming these activities continue every 5 years for 30 years, is
23 approximately \$64,880. The approximate total present worth of Alternative A2 is \$103,690.

24

25 5.1.3 Alternative A3: Containment via Capping

26

27

28 5.1.3.1 Detailed Description

29 Under this alternative, direct contact with the contaminated soils and asphalt around
30 the east DRMO Yard would be eliminated through the installation of an impermeable cap.
31 The cap would also reduce surface water infiltration through the contaminated soil and would
32 serve to minimize the generation of contaminated groundwater.

33 The first element of this alternative would be the excavation and consolidation of the
34 contaminated soils to minimize the area requiring capping. Excavation would be performed
35 using conventional earth-moving equipment, such as backhoes, bulldozers, dump trucks, etc.
36 Currently, the contaminated soils are found in four areas: the area in the southern portion of
37 the tire storage area, adjacent to the northern border of the east DRMO Yard; the area in the
38 center of the east DRMO Yard; the drainage swale along the western edge of the yard; and,
39 the drainage swale along the eastern edge of the yard. Clearing and grubbing of these areas
40 would not be required since the areas are not vegetated. Capping these areas directly is
41 inadvisable because the cap would consist of four long, thin sections. This would not only
42 complicate the installation of the cap, but would also reduce the cap's ability to prevent
43 leachate generation and groundwater contamination.

1 Therefore, it is proposed that the soils in the eastern and western drainage swales be
2 excavated and placed on and in between the other two areas of contamination. On the eastern
3 swale, only the southern half (south of the contaminated area in the center of the yard) would
4 need to be excavated. The width of contamination is assumed to be 15 feet. On the western
5 swale, it would be necessary to excavate the entire length. Consolidation of the southern
6 portion would be to minimize the area requiring capping, as discussed above. The northern
7 half would also need to be excavated due to its proximity to Cook Street. Excavation
8 would make room for a new drainage swale that would be required beyond the edge of the
9 impermeable cap. This new swale would be needed to help drain the cap area. The swale
10 cannot be underlain with impermeable material and must be no steeper than a 3:1 slope.
11 Moving the contaminated soils approximately 15 feet from the road would provide enough
12 space for the new swale. These excavated soils would require toxicity characteristic leaching
13 procedure (TCLP) testing in order to determine if RCRA action-specific ARARs would apply.
14 Figure 5-1 presents a depiction of the excavated areas. These excavated areas will be
15 backfilled from either on-site or off-site stockpiles.

16
17 Based on these assumptions and a depth of contamination of 1 foot, approximately
18 9,675 cubic feet (360 cubic yards) of soil would have to be excavated along the edges of the
19 east DRMO Yard. The area of the cap would be approximately 49,400 square feet (see
20 Figure 5-1). Therefore, the excavated soils would rise to an average of 0.20 feet, or about
21 2.4 inches. It is more likely that these soils would be piled higher in the center of the capped
22 area to help achieve the required slope off of the top of the cap.

23
24 During the soils excavation, verification sampling would be required to ensure
25 achievement of cleanup goals. This sampling would consist of collecting soil samples from
26 the bottom and edges of excavation areas for laboratory analysis for the contaminants with
27 site-specific cleanup goals (PCBs, pesticides, lead, and cadmium). Actual sampling
28 procedures and protocols would be outlined as part of the remedial design process. When
29 verification sampling indicates that soil remaining at the bottom and edges of excavation pits
30 meets cleanup goals, the excavation for that area would be considered complete, and it would
31 be cleared for backfilling. If the results are not acceptable, then additional soil would be
32 excavated. The excavation would then be resampled and this cycle repeated until sampling
33 and analytical testing indicate that the cleanup goals were met.

34
35 The cap would be multilayered. Following Massachusetts landfill cover
36 requirements, the cap would consist of 18 inches of clay with a permeability of 10^{-7} cm/sec,
37 covered by 6 inches of a drainage layer soil with a minimum permeability of 10^{-3} cm/sec, 6
38 inches of loam subsoil, and a final 6 inch layer of topsoil seeded with vegetative cover. (The
39 low permeability clay could be substituted with a 40 mil high density polyethylene (HDPE)
40 synthetic liner (Murphy 1994). However, only the clay alternative is developed and costed.)
41 The cover would be vegetated to stabilize the soil capping material and prevent erosion. The
42 slight northerly slope of the swales on the eastern and western sides of the east DRMO Yard
43 would be maintained to allow for continued drainage to the storm water line. The asphalt that
44 currently covers almost all of the contaminated area does not allow for very much infiltration.
45 Therefore it is not expected that the impermeable cap will greatly increase the expected
46 runoff. Currently, flow to the catch basin to the north is slight, only observed during very

Feasibility Study: Fort Devens FA II
Section No.: 5
Revision No.: 2
Date: January 1997

1 heavy rain events. For these reasons, it is not anticipated that additional storm water control
2 measures, such as deeper swales or retention ponds, will be necessary. However, minimal
3 controls such as rip-rap may be employed to facilitate flow to the catch basin. The effects of
4 runoff and the need for a drainage study on the area will be further analyzed and evaluated
5 during the design phase.

6
7 The southern portion of the east DRMO Yard could be used as a decontamination pad
8 for the excavation and capping equipment. Wastewater generated from decontamination
9 procedures could be contained, and treated and disposed of, if necessary. The 6-foot high
10 chain-linked, barbed wire fence surrounding the east DRMO and tire yards would be removed
11 during capping activities, then re-installed around the cap. The fence would serve as
12 additional protection against human and wildlife exposure as well as against cap deterioration
13 caused by "trespassing" wildlife.

14
15 To ensure worker safety during the construction process, site work would be
16 conducted in Level C PPE to provide for protection against inhalation, ingestion, and dermal
17 exposure. Dust control measures may be required during soils excavation and before
18 placement of the cap. Soils around the perimeter of the cap area will be sampled to verify
19 that the cover is sufficient. Finally, annual operating and maintenance activities will be
20 conducted for 30 years. This would include cap inspection and maintenance, and, in order to
21 evaluate contaminant migration, groundwater monitoring. Cap maintenance activities would
22 include repair of holes (made by burrowing animals, for example) and any necessary
23 revegetation to reduce the possibility of erosion. These maintenance activities would also be
24 performed in dermal and respiratory protection.

25
26 **5.1.3.2 Criteria Analysis**

27
28 **Overall Protection of Human Health and the Environment**

29
30 Under this alternative, contaminants would not be treated or destroyed. However,
31 they would be isolated from the surface by an impermeable cover. This would satisfy all
32 three RAOs. Dermal, ingestion, and inhalation exposure routes would be eliminated, for both
33 human and ecological receptors; however, the ecological risk assessment concluded that only
34 minimal risks exist with the current situation. Contaminant migration to surface water and
35 groundwater media would be significantly reduced, if not eliminated. The fence around the
36 cap would provide additional protection against exposure. Groundwater monitoring would
37 also aid in the protection of human health and the environment in that it would be used to
38 evaluate potential contaminant migration. This would influence a decision to take additional
39 action, if necessary.

40
41 **Compliance with ARARs**

42
43 This alternative could bring the site into compliance if the contaminated soils were
44 subsequently considered as subsurface soils. The maximum PCB detection, 9.3 $\mu\text{g}/\text{g}$ would
45 be below the TSCA level for subsurface soils of 10 $\mu\text{g}/\text{g}$. If the contamination were still
46 considered surficial, then a waiver application would be required. The likely rationale would

1 be that this alternative provides equivalent or nearly equivalent performance, with respect to
2 human health risks, as Alternatives A4 and A6. Lead and cadmium concentrations do not
3 exceed any chemical-specific ARARs; however, if the excavated soils were found to exhibit
4 the hazardous characteristic of toxicity due to lead and/or cadmium (or any other
5 contaminant), then moving, consolidating, and capping these soils would violate RCRA
6 action-specific ARARs. However, the Extraction Procedure (EP) toxicity test was applied to
7 the sample with the highest level of lead and cadmium found during the SI, and this showed
8 only low levels of solubility for these metals. No location-specific ARARs would be violated
9 by this alternative (see Table 5-14).

10

11 Reduction of Toxicity, Mobility, or Volume through Treatment

12

13 This alternative is not technically a treatment technique, and the toxicity and volume
14 of contamination would not be affected. However, the potential for contaminant mobility,
15 both in surface water and groundwater, would be significantly reduced, if not eliminated. If
16 the cap is breached significantly, or if the cover erodes, migration of contaminants could
17 occur. However, regular cap maintenance should prevent this situation (see section on long-
18 term effectiveness) and monitoring would detect it.

19

20 Long-term Effectiveness and Permanence

21

22 As long as the cap and fence are properly maintained, this alternative should be
23 effective over the long term, both in reducing the mobility of, and in preventing direct contact
24 with the contamination. Regular inspection and maintenance of the fence, cap, and
25 monitoring wells would be required. This would ensure that the vegetation is intact (to
26 prevent erosion of cap materials), to evaluate whether other causes, such as burrowing
27 animals, have compromised the cap's integrity, and to ensure the fence is secure. Future site
28 usage would be necessarily limited to further ensure the cap's integrity. This alternative is
29 not considered permanent because it does not treat the contamination. However, if the cap
30 and fence are maintained properly, residual risk would be minimal, and management/
31 maintenance controls should be adequate to maintain the risk at minimal levels.

32

33 Short-term Effectiveness

34

35 This alternative would create temporary increases in dust production, while the soil
36 excavation is taking place and potential dust and runoff problems for the brief period before
37 the excavated soil is covered with the cap. If excessive dust production was determined,
38 through continuous air monitoring activities, to pose a hazard to the community or ecological
39 receptors, dust and rainwater control measures (such as using a temporary impermeable
40 plastic cover) may be required. Site workers involved with excavation activities would be
41 required to use Level C PPE to prevent inhalation, ingestion, and dermal exposure.
42 Groundwater sampling activities would also require that respiratory and dermal protection be
43 worn to reduce risk of exposure. Excavation could probably be accomplished in
44 approximately 1 week. Capping activities, which could take several months, would not pose
45 the same degree of dust generation problems as soil excavation. However, it is likely that site
46 workers would remain in Level C PPE during this phase. Removing and re-installing the

Feasibility Study: Fort Devens FA II
Section No.: 5
Revision No.: 2
Date: January 1997

1 fence would take a few days and would also be performed with dermal and respiratory
2 protection. Groundwater sampling could be performed in a few days per sampling event.
3 This alternative would not pose additional risks to the environment.

4

5 **Implementability**

6

7 This alternative would be relatively easy to implement, assuming the soils do not fail
8 TCLP tests. Remedial contractors are available to provide the necessary services, and cap
9 installation could be accomplished in a matter of months. Groundwater monitoring should
10 effectively evaluate if contaminant mobility has been reduced. However, additional remedial
11 actions would be costly, due to materials handling relating to the cover material. If, after
12 capping, it was determined that the site was not in compliance with TSCA, there could be
13 some administrative difficulties. However, because human exposure, and therefore, human
14 health risks would be dramatically reduced, a waiver to ARARs could likely be obtained.
15 Future site use would also be limited. In the event the excavated soils fail TCLP tests, these
16 soils would have to be transported to a RCRA-certified landfill. Only the soils that remain in
17 place would be able to be capped, in this case.

18

19 **Costs**

20

21 The costs associated with Alternative A3 are presented in Table 5-4. Capital costs
22 including mobilization/demobilization, site services, health and safety, excavation,
23 consolidation, backfill, construction of the cover, verification and TCLP sampling and
24 analysis, and fenceline changes are estimated at \$470,320. Annual O&M costs, including
25 maintenance and groundwater monitoring, are estimated at \$26,650. The approximate present
26 worth of O&M activities, assuming annual monitoring over 30 years, is \$366,200. This
27 assumes that only existing wells will be sampled. The approximate total present worth of
28 Alternative A3 is \$836,520.

29

30 **5.1.4 Alternative A4: Excavation, Solidification, and On-site Disposal**

31

32 **5.1.4.1 Detailed Description**

33

34 This alternative includes the excavation, on-site treatment via solidification, and on-
35 site disposal of contaminated soils. A treatability study would be required to determine
36 whether solidification is likely to be successful and to determine the optimal solidification
37 technique (USEPA 1989a). First, the waste and contaminants would be screened to select the
38 most appropriate method of solidification. A cement-based technique would probably be
39 chosen because it has been demonstrated to work on waste containing lead, cadmium, PCBs,
40 and pesticides. Second, the waste is further characterized to identify potential inhibitors to the
41 solidification process, such as oxidizing salts or low pH. Third, bench-scale testing is
42 performed. Different mixtures are tested, and the optimum waste-to-binder ratio is based
43 primarily on leachability and durability tests. In particular, TCLP testing may be necessary to
44 determine if a waiver would be required to dispose of the solidified material on site. In
45 addition, the treatability study must examine the solidification of asphalt. Asphalt would
46 probably not inhibit the solidification capacity of the cement; in fact, because asphalt has

1 some binding capacity of its own, it may enhance the encapsulation. The study should
2 examine both the handling of the asphalt separately from the soils, and the mixing of the two
3 together. The optimal size of the pieces of asphalt would also be a parameter for study. The
4 decision regarding the asphalt will be made in the remedial design, based on performance in
5 bench-scale testing. If possible, pilot scale testing could be performed to determine if bulk-
6 mixing would sufficiently mix the waste and binding agent, or if the use of a pug mill would
7 be required (see description of mixing techniques, below). Finally, site conditions are
8 evaluated to account for site-specific concerns such as stockpiling and waste transport,
9 drainage, and access routes.

10
11 The treatment process itself includes the following tasks: excavation of the waste,
12 transport to a temporary storage area, waste/binder mixing, material curing, and transport to a
13 final disposal location. Each of these processes is discussed briefly below.

14
15 Based on interpretation of soil sampling data collected during the RI, approximately
16 35,100 cubic feet (1,300 cubic yards) would be subject to excavation. This volume corre-
17 sponds to the estimated areas and depths of contaminated soils as presented in Figure 5-2.
18 Since the contaminated material is not in a vegetated area, clearing and grubbing would not be
19 required. Excavation of contaminated soils would be conducted using conventional earth-
20 moving equipment such as backhoes, bulldozers, dump trucks, etc. During excavation (and
21 mixing, see below), dust generation would have to be controlled to acceptable levels. The
22 specific means and methods of excavation and dust control would be determined during the
23 remedial design. Level C PPE would be required for site workers to prevent inhalation,
24 ingestion, and dermal exposure routes. The contaminated asphalt in the center portion of the
25 east yard would be excavated using earth moving equipment and would have to be broken into
26 pieces small enough for handling. This could probably be accomplished with the backhoes
27 and bulldozers as well. Based on the results of the treatability study (see above), the asphalt
28 may have to be broken into smaller pieces and/or piled separately from the soils.

29
30 During excavation of the soils, verification sampling, as previously detailed in Section
31 5.1.3.1, would be performed. The excavated soils and asphalt would then be transported to
32 the on-site staging area to await treatment. The southern portion of the east DRMO Yard
33 could be used for this purpose. It would first have to be covered with a plastic liner, and,
34 after emplacement of the soil and asphalt, covered with an impermeable plastic cover to
35 prevent direct contact, wind erosion, and stormwater runoff. This portion of the yard could
36 also be used as a decontamination pad for the excavation equipment. Waste water generated
37 from decontamination procedures would be contained, and treated and disposed of, if
38 necessary. The southern half of the yard is 72,900 square feet, easily large enough to handle
39 both decontamination and temporary storage. The proximity of the contaminated soils to the
40 temporary storage areas will significantly reduce transport costs.

41
42 The contaminated material would then be mixed with the solidification agent, most
43 likely portland cement, and water. The exact mixture of waste, cement, and water which
44 would produce the strongest monolith, reduce leachability, and keep volume to a minimum,
45 would be determined in the treatability study mentioned above. The optimal solidification of
46 the asphalt would also be determined in the treatability study.

Feasibility Study: Fort Devens FA II
Section No.: 5
Revision No.: 2
Date: January 1997

1 Two general methods exist for the mixing of the waste and the binding agent. The
2 simpler method is known as "bulk mixing." The binding agent is delivered to the stockpile
3 area and mixed with the waste directly. Conventional earth moving equipment, such as
4 backhoes, are used to mix the materials. No quality assurance/quality control (QA/QC)
5 program has been established to determine when the mixing is complete, so this is generally
6 left to the operator. Complete mixing is difficult using this method. The second method
7 involves the use of more specialized mixing equipment, of which "pug mills" are the most
8 common. Pug mills consist of two screws, one of which delivers the waste, the other, the
9 binding agent. The two streams are then mixed, and fed to the pug mill. Bulk mixing is less
10 expensive than the use of a pug mill, and it does not require the use of specialized equipment.
11 If a pug mill were used, it would either have to be mobilized on site, or the waste would have
12 to be transported off site. The method of mixing will be determined during the remedial
13 design, based on results of the treatability study (see above). However, because the volume
14 of waste is relatively small, the soil contaminants (PCBs, pesticides, lead, and cadmium) do
15 not have a strong tendency to leach, and there is sufficient area to mix in bulk, it is unlikely
16 that the advantages of pug milling could justify the increased cost.

17
18 Regardless of the mixing technique, the waste/binder mixture would have to be placed
19 in forms and allowed to cure for up to a month (the curing period will also be examined in
20 the treatability study) to achieve full strength. However, for handling purposes, it is generally
21 preferred to dispose of the cured concrete before it is fully set. Final disposal (see below) of
22 the material would be considered when configuring the forms. During the curing period, any
23 water passing over or through the forms would have to be collected for treatment and/or
24 disposal. After the curing period, TCLP tests would be conducted prior to final disposal, to
25 determine if RCRA action-specific ARARs would apply. TCLP testing would have to include
26 PCBs as an analytical parameter. However, because no regulatory level exists for PCB TCLP
27 analysis, an action level would have to be negotiated.

28
29 Finally, the monoliths would be disposed of on site. The probable location for
30 disposal would be the northern DRMO yard and southern tire recycling area, from which
31 much of the excavated soils would come. If other remedial actions on Fort Devens require
32 soils disposal, then a central disposal area would be considered, to determine if site-wide cost
33 savings could be achieved. Because of the addition of cement and water, the total volume of
34 material after treatment will likely be greater than before treatment. This final volume
35 depends on pretreatment porosity of the waste, and on the extent of compaction possible after
36 treatment. It is therefore probable that the final grade would be higher than it was initially.
37 Some further excavation may be required, based on the shape of the forms. After the semi-
38 cured monoliths are placed in the ground, they would be covered with approximately six
39 inches of topsoil. The topsoil would then be seeded to promote vegetation, thereby
40 preventing erosion and subsequent exposure of the solid masses. In addition, at some point
41 during the design phase, a means to control precipitation infiltration must be addressed.
42 Otherwise, problems with frequent saturation of the overlying topsoil will likely result.

43
44 A groundwater monitoring program would be established to evaluate potential
45 contaminant migration. Wells will be sampled on an annual basis for a period of 30 years.
46

Feasibility Study: Fort Devens FA II
Section No.: 5
Revision No.: 2
Date: January 1997

5.1.4.2 Criteria Analysis

Overall Protection of Human Health and the Environment

Under this alternative, the contaminants would be treated and contained, but not removed from the site. Nevertheless, it would satisfy all three RAOs. Solidification is primarily intended to handle inorganic contaminants in soil. Metals such as lead and cadmium react chemically with the cement and become chemically bound up in the monolithic matrix. Organic constituents, on the other hand, do not react with the cement. Rather, they are physically bound in the matrix. This does not completely prevent their leaching out with infiltrating water. However, the matrix has a low permeability, and the physical binding of large organics like PCBs and pesticides results in a drastic reduction in the risk of exposure. Groundwater monitoring would also aid in the protection of human health and the environment in that it would detect and evaluate potential contaminant migration. This would influence a decision to take additional action, if necessary.

Compliance with ARARs

Currently, the soils exceed the TSCA chemical-specific ARAR for PCBs. After treatment, the PCBs will be essentially contained within the blocks, thus removing the exposure route. Therefore, it may be considered that this alternative complies with cleanup goals based on regulatory and calculated risk levels. If the treated soil is still considered to be in violation of the TSCA ARAR, a waiver application would be based on this alternative providing an equivalent level of protection as Alternative A6. No location-specific ARARs will be violated by this alternative (see Table 5-14).

The concentrations of lead and cadmium do not exceed any chemical specific ARARs. However, if any soils were found to exhibit the hazard characteristic of toxicity due to lead and/or cadmium (or any other contaminant), then disposal of the solidified soil on site would violate RCRA action-specific ARARs. However, no soils are expected to exceed the TCLP criteria after solidification, especially as the EP toxicity characteristic did not identify soluble toxic metals in soil during the SI.

Reduction of Toxicity, Mobility, or Volume through Treatment

Because both lead and cadmium will be chemically bound to the cement, there would be a reduction in lead- and cadmium-related toxicity. Furthermore, its mobility would be practically eliminated. PCBs and pesticides would only be encapsulated physically, so their toxicity would not be changed. However, their mobility would be significantly reduced. Although there is some chance that the PCBs and pesticides could be mobilized to some degree over the long-term, this possibility is not considered likely and would be verified through groundwater monitoring. Therefore, this alternative satisfies the statutory preference for the permanent reduction of mobility through treatment. The total volume of contaminated material will likely increase to some extent due to the addition of cement.

1 Feasibility Study: Fort Devens FA II
2 Section No.: 5
3 Revision No.: 2
4 Date: January 1997

1
2 **Long-term Effectiveness and Permanence**

3 The lead and cadmium would be virtually immobilized within the cement matrix.
4 Since they would be chemically bound to the cement, they could be considered to be
5 permanently removed, thus eliminating exposure routes and human health risks. However,
6 there is the possibility that organic constituents could leach out of the matrix based on
7 monitoring results, over the long-term. It would be difficult to control residual risks
8 associated with this possibility. However, if care is taken during the treatability study, then
9 this residual risk should be very low, especially considering that PCBs and pesticides are of
10 low mobility to begin with. Therefore, this alternative could be considered effective over the
11 long-term, and even permanent, with respect to PCBs and pesticides. Monitoring wells would
12 require proper inspection and maintenance under this alternative.

13
14 **Short-term Effectiveness**

15 There would be some short term increase in exposure, particularly to the workers
16 involved. Therefore, all work would be carried out in Level C PPE. In addition, continuous
17 air monitoring activities would be required during excavation. As with other excavation
18 alternatives, dust control would be required to protect on-site workers and the community.
19 Because of the requirement to perform verification sampling, there would be a significant
20 interim period during which contaminated soils would be staged in the temporary area. This
21 could expose the community and the environment to additional short-term risks. Therefore,
22 during the storage phase, it would be required that some measures be taken to reduce
23 exposure to the soils, such as daily covering with an impermeable plastic liner to prevent
24 direct contact, wind erosion, and runoff from precipitation. Site workers involved in
25 groundwater sampling would also use respiratory and dermal protection to prevent exposure.
26 It is estimated that this alternative would take between 3 and 5 months to complete.
27 However, the time could be decreased if verification sampling can be accelerated (using field
28 analysis, for example). Groundwater sampling could be performed in a few days per
29 sampling event.

30
31 **Implementability**

32 Contractors to provide the described treatment services are readily available, and the
33 treatment technique is considered reliable for both lead and cadmium as well as PCBs and
34 pesticides. It should not be difficult to obtain regulatory approval. However, it will be very
35 difficult to monitor the effectiveness. The groundwater monitoring program will be used to
36 assess subsequent contaminant migration. The contaminants are not particularly mobile in the
37 aqueous phase to begin with, and these contaminants are not considered a groundwater
38 problem. Therefore, it is unlikely that groundwater sampling would reveal leaching from the
39 solidified mass. Additional remedial action on the monoliths themselves would be difficult,
40 particularly if they become completely solidified into concrete. However, the area could be
41 covered with an impermeable cap if leaching were deemed to be a problem. Finally, this
42 alternative would require more time to complete than other alternatives, and future use of the
43 site would be limited because the contaminated material would remain, and because the
44 presence of the monoliths could obstruct future excavation and development.

Feasibility Study: Fort Devens FA II
Section No.: 5
Revision No.: 2
Date: January 1997

1 Costs
2

3 The cost of Alternative A4 would be more accurately predicted after the treatability
4 study is complete. The breakdown of estimated costs for this alternative for the contaminated
5 soils and asphalt at the DRMO Yard is presented in Table 5-5. Capital costs include
6 mobilization/demobilization, site services, health and safety, a treatability study, soils
7 excavation and handling, solidification, verification, TCLP sampling, backfilling, grading, and
8 restoration, totaling an estimated \$490,870. The total approximate present value of O&M
9 costs, associated with monitoring, is \$287,270. This assumes only existing wells will be
10 sampled annually for 30 years. The approximate total present worth for Alternative A4 is
11 \$778,140.

12
13 **5.1.5 Alternative A6: Excavation and Off-Site Disposal**

14
15 **5.1.5.1 Detailed Description**

16
17 Under this alternative, all soil identified above as being contaminated would be
18 excavated and disposed of off site. The excavation would be exactly as described in
19 Alternative A4. Level C PPE would be required for site workers to prevent inhalation,
20 ingestion, or dermal exposure routes. Dust control measures would be employed as well.
21 However, it would not be required to stage the soils in a temporary area. Rather, they would
22 be transported immediately to an off-site non-hazardous landfill. Because only low levels of
23 PCBs (less than 50 ppm) were detected the soil should not have to go to a TSCA-regulated
24 landfill. However, it is possible that the soils could fail TCLP tests for lead based on the
25 detected concentrations of this metal in the soil. In this case, the soils would be classified as
26 RCRA hazardous wastes and would require disposal at an off-site RCRA-regulated landfill.
27 Soils are not expected to fail TCLP tests for cadmium, based on sampling results. As
28 discussed above, a total of 1,300 cubic yards of soil will be excavated (see Figure 5-2).
29 Verification sampling, as discussed in Section 5.1.3.1, of the soil would be performed to
30 ensure that all of the contamination had been removed. Finally, the excavated areas would be
31 regraded or backfilled to grade with clean soils and revegetated for stabilization. The
32 southern portion of the east DRMO Yard could be used as a decontamination pad for the
33 excavation equipment. Waste water generated from decontamination procedures would be
34 contained, and treated and disposed of, if necessary. Because the source of contamination
35 would be removed from the site, no long-term monitoring would be required. However, a
36 review of site conditions, including groundwater sampling, would be conducted in 5 years to
37 ensure no contaminant migration from unidentified sources. Appropriate action would be
38 considered at that time.

39
40 **5.1.5.2 Criteria Analysis**

41
42 **Overall Protection of Human Health and the Environment**

43
44 This alternative would not treat or destroy the contaminants, but it would completely
45 remove them from the site. All three RAOs would be achieved, permanently. Therefore, this
46 alternative would provide for the complete protection of human health and the environment.

1 To verify this, groundwater would be sampled from this location 5 years after excavation and
2 disposal.

3

4 **Compliance with ARARs**

5

6 Chemical-specific ARARs at the site would be met with the soils removal. However,
7 RCRA action-specific ARARs could apply, if the soils fail the TCLP criteria for lead,
8 cadmium, or any other contaminant. This is not expected, based on the EP toxicity test run
9 on the sample with the highest lead and cadmium found during the SI, which showed low
10 levels of solubility for these metals. No location-specific ARAR will be violated by this
11 alternative (see Table 5-14).

12

13 **Reduction of Toxicity, Mobility, or Volume through Treatment**

14

15 Because this alternative does not include treatment, the volume and toxicity of the
16 waste would be unchanged. Contaminant mobility would be controlled in a certified landfill.
17 However, this alternative does not satisfy the EPA preference for on-site treatment over off-
18 site disposal. Monitoring would detect any residual contaminant migration over time.

19

20 **Long-term Effectiveness and Permanence**

21

22 Assuming the contaminated soils are removed completely from the DRMO Yard,
23 there would be essentially no residual risk associated with this alternative. Therefore, there
24 would be no long-term management or monitoring needs. Monitoring would only be
25 performed once, 5 years after implementation of this alternative, in order to verify its
26 effectiveness in removing all the contamination. Because the waste would be completely
27 removed from the site, this alternative would be considered permanent.

28

29 **Short-term Effectiveness**

30

31 As with other excavation alternatives, there would be a short-term increase in human
32 health risk, mostly to site workers, due to direct contact and dust creation. Therefore, all
33 excavation and removal activities would be performed in Level C PPE. Groundwater
34 sampling would also be performed in level C PPE to prevent dermal exposure and ingestion
35 and inhalation of contaminants. In addition, air monitoring activities would be required
36 during excavation. There could be some increase in risk to the community due to dust
37 creation and possible runoff during storms. Therefore, dust control activities would have to
38 be performed, which may involve covering the excavation with a temporary water-proof cover
39 after each day's work. No more than 2 months would be required to achieve RAOs.
40 Groundwater sampling, scheduled to be performed approximately 5 years after implementation
41 of this alternative, would only take a few days.

42

43 **Implementability**

44

45 Alternative A6 is easily implementable, assuming the soils do not fail TCLP criteria.
46 If they did fail, a waiver to dispose of the material in a sanitary landfill would be difficult to

Feasibility Study: Fort Devens FA II
Section No.: 5
Revision No.: 2
Date: January 1997

1 obtain, and the soil would have to be transported to a RCRA-certified landfill. There are no
2 technical difficulties associated with this alternative, and many contractors would be able to
3 perform the work. Additional remedial action on the DRMO Yard would not be impeded in
4 any way.

5 Costs

8 The estimated costs associated with Alternative A6 are listed in Table 5-6. Capital
9 costs are estimated at \$543,696 and include mobilization/demobilization, site services, health
10 and safety, excavation, soil handling and loading, verification and TCLP sampling, transport,
11 backfilling, restoration, and disposal. The present worth of monitoring activities, including
12 the one sample event in 5 years, is approximately \$19,850. The approximate total present
13 worth of Alternative A6 is \$563,550.

14 5.1.6 Comparative Analysis of Alternatives

17 Table 5-1 summarizes the detailed analysis of alternatives presented above:
18 Alternative A1, No Further Action; Alternative A2, Institutional Actions; Alternative A3,
19 Containment via Capping; Alternative A4, Excavation, Solidification, and On-Site Disposal;
20 and Alternative A6, Excavation and Off-Site Disposal. These remedial alternatives are
21 compared to the EPA criteria of overall protection of human health and the environment;
22 compliance with ARARs; reduction of toxicity, mobility, or volume; long and short term
23 effectiveness; implementability; and cost.

25 Overall Protection of Human Health and the Environment

27 Alternative A1 would not provide any additional protection than that which already
28 exists in the current zoning, fencing, and land use plans for the site. Alternatives A2, A3,
29 and A4 would minimize the exposure routes to human and environmental receptors, thus
30 reducing risks to acceptable levels. Alternative A6 would remove contaminated soils to an
31 off-site landfill, eliminating contamination at the site. All alternatives would involve some
32 duration of monitoring in order to detect potential contaminant migration.

34 Compliance with ARARs

36 The PCB chemical-specific ARAR would be exceeded in all alternatives except for
37 Alternative A6 and possibly Alternative A4. However, minimizing the exposure routes via
38 Alternatives A2 and A3 would minimize risks for the TSCA ARAR for PCBs, the RCRA
39 action levels for pesticides and cadmium, and the human health risk assessment calculated
40 cleanup goals for lead. Also, Alternatives A1, A2, and A3 would eliminate the possibility
41 that the RCRA action-specific ARAR would apply. No location-specific ARAR would be
42 violated by this alternative (see Table 5-14).

1
2
3
4
5
6
7
8
9
10
11
12
13
14
15
16
17
18
19
20
21
22
23
24
25
26
27
28
29
30
31
32
33
34
35
36
37
38
39
40
41
42
43
Feasibility Study: Fort Devens FA II
Section No.: 5
Revision No.: 2
Date: January 1997

Reduction of Toxicity, Mobility, or Volume through Treatment

Alternatives A1 and A2 do not involve treatment, and would not reduce toxicity, mobility, or volume of contamination. Alternatives A3 and A6 would not provide for a reduction in toxicity or volume, but they would reduce the mobility of contamination. Of these two, Alternative A6 would be more effective in this reduction. Neither satisfies the preference for on-site treatment. Alternative A4 would reduce the toxicity of lead and cadmium contamination, but not of PCBs or pesticides. It would drastically reduce the mobility of these contaminants, but would likely increase the volume. Alternative A4 is the only option that would satisfy the regulatory preference for on-site treatment. Monitoring, under all alternatives, would serve to verify reduction in contaminant migration.

Long-term Effectiveness and Permanence

Alternatives A1, A2, A3, and A4 all require continued institutional controls. Alternatives A1 and A2 require continued control of access to the DRMO Yard, and thus are not considered effective in the long-term. Alternative A3 requires maintenance of the integrity of the cap along with fence maintenance, and Alternative A4 requires protection of the buried monoliths. Of these alternatives, A4 would be more effective in the long-term. In Alternative A6, the burden of responsibility shifts to the off-site landfill operator to ensure the landfill integrity is upheld. However, the site risks would be eliminated in the long-term. All alternatives would require monitoring well inspection and maintenance.

Short-term Effectiveness

On a short term basis, only Alternative A1 would cause no disturbance of surface soils which may endanger human health. Alternative A2 would cause brief disturbance to the surface soils while fencing was installed. Alternatives A3, A4, and A6 would involve extensive short term earth moving and remedial activities, which would require Level C PPE to prevent worker exposure and dust control and runoff control activities to prevent community exposure. In addition, these three alternatives would require air monitoring during excavation activities. Under all alternatives, groundwater sampling would be performed in dermal and respiratory protection in order to minimize exposure risks.

Implementability

None of the alternatives face any technical obstacles to implementation. However, Alternatives A1, A2, and A3 would require waivers from the PCB ARAR. On the other hand, alternatives A4 and A6 would create the possibility that the RCRA action-specific ARARs for lead and cadmium would apply. Alternative A4 would require the longest time to implement, at approximately 4 to 5 months. All of the alternatives except for A6 would require future site use restrictions.

1 Feasibility Study: Fort Devens FA II
2 Section No.: 5
3 Revision No.: 2
4 Date: January 1997

1
2 **Costs**

3 Table 5-7 presents a summary of the costs of the five alternatives at the DRMO Yard.
4 Alternative A1 requires annual monitoring costs, totaling approximately \$80,380. Alternative
5 A2 requires minimal work, and an estimated \$103,690 to implement. Alternative A3 would
6 require consolidation and capping of the soil which could be implemented relatively easily at
7 an estimated cost of \$836,520. Alternative A4 would require slightly more time for
8 solidification and burial, at an estimated cost of \$778,140. Alternative A6 would be easily
9 implementable and could be accomplished quickly for an estimated cost of \$563,550.

10
11 **5.2 UST 13 GROUNDWATER OPERABLE UNIT (AOC 32)**

12 Three alternatives for remediation of UST 13 groundwater were retained from the
13 initial screening (Section 4). These are described in detail in this section and analyzed with
14 respect to the criteria presented by the EPA. The three alternatives discussed below are:
15

16
17 Alternative B1: No Further Action
18 Alternative B2: Institutional Actions
19 Alternative B3: Intrinsic Remediation (with long-term monitoring).

20
21 **5.2.1 Alternative B1: No Further Action**

22
23 **5.2.1.1 Detailed Description**
24
25 The "No Further Action" alternative is developed and evaluated to establish a baseline
26 for comparison with other remedial alternatives. Under this alternative, no remedial action of
27 any type would be undertaken. Neither the soils or groundwater in the vicinity of the former
28 UST would be removed, contained, or treated in any way. It is assumed that the
29 contamination would remain in its present state and pose the same risks as currently exist.

30
31 Groundwater monitoring would be performed annually for 5 years under this
32 alternative. After 5 years the need for continued monitoring will be reviewed.

33
34 **5.2.1.2 Criteria Analysis**

35
36 **Overall Protection of Human Health and the Environment**

37
38 The "No Further Action" alternative would neither contain, treat, nor destroy the
39 contaminants in the groundwater near UST 13. No measures, either remedial or institutional,
40 would be taken to protect human health or the environment, and RAOs would not be met.
41 Monitoring, however, would be performed in order to detect contaminant migration. This
42 would influence a decision to take additional action, if necessary.

Feasibility Study: Fort Devens FA II
Section No.: 5
Revision No.: 2
Date: January 1997

Compliance with ARARs

The groundwater would still exceed SDWA based ARARs for chlorobenzenes. Therefore, a waiver would have to be granted to pursue this alternative. If future site use is planned to be restricted to industrial use, the threat of exposure to this contamination may be deemed acceptable by regulators. Future site use would be necessarily limited. Table 5-15 sets out the Federal and State ARARs as they apply to groundwater in the area of the POL Storage Area/DRMO Yard (AOCs 32 and 43A).

Reduction of Toxicity, Mobility, or Volume through Treatment

The "No Further Action" alternative would have no effect on the toxicity, mobility, or volume of contamination. However, as discussed in Section 1, the contaminants are practically immobile and the volume is relatively small. Monitoring would detect any contaminant migration over time.

Long-term Effectiveness and Permanence

Because the "No Further Action" alternative will not meet the RAOs, the residual risk is equivalent to the existing risks. The potential for human or ecological exposure to contaminants in groundwater would endure, as would the potential for the contamination of other media. This alternative does not satisfy the preference for treatment and permanence. However, based on the small area involved, the very slow migration of contamination, and the lack of drinking water wells, the exposure is deemed to be minimal. Groundwater monitoring will assess long-term contamination migration and human health risks, allowing appropriate actions to be taken if conditions change.

Short-term Effectiveness

The "No Further Action" alternative will have no impact on existing site conditions. Groundwater sampling would be performed wearing PPE to prevent dermal exposure to and ingestion and inhalation of contaminants.

Implementability

The "No Further Action" alternative does not present any technical implementability obstacles. Monitoring and/or future remedial action would be easily applied. However, the failure to comply with ARARs poses a potentially difficult administrative obstacle.

Costs

There are no capital costs associated with this alternative. O&M costs, as presented in Table 5-8, are associated with the groundwater sampling events, to be conducted for 5 years. It is assumed that existing wells would be sampled and no new wells installed. The approximate total present worth of the "No Further Action" alternative is \$75,820, assuming no further monitoring is required after 5 years.

1 **5.2.2 Alternative B2: Institutional Actions**

2 **5.2.2.1 Detailed Description**

3
4 No remediation would occur under this alternative; activity would be limited to
5 minimal measures intended to reduce exposure to contaminated media. Deed restrictions
6 would limit land use and development. The land would be limited to restricted development,
7 including a ban on drinking well installation, through deed restrictions. The land is currently
8 slated for industrial land use by the Massachusetts Land Bank, which will control development
9 upon Army release of the property, thus no further zoning alterations would be required.
10 Because there is no surficial contamination, fencing would not further reduce risks to human
11 health or the environment.

12
13 Groundwater monitoring would also be performed under this alternative. Every 5
14 years for a period of 30 years, the site conditions would be reviewed to determine the extent
15 of contaminant migration. A groundwater sampling event will be performed for each of these
16 reviews. In addition, exposure scenarios will be revisited based on site use at the time of
17 each review. If warranted, additional action will be considered at these times.

18
19 **5.2.2.2 Criteria Analysis**

20 **Overall Protection of Human Health and the Environment**

21
22 Institutional actions would not treat or destroy any of the contaminants; however, they
23 would isolate the contamination in an area restricted to development. Therefore, if executed
24 properly, institutional actions under this alternative would reduce human exposure to the
25 contaminants to acceptable risk levels. Risks to the environment would be unaffected;
26 however, ecological risks were found to be minimal. Groundwater monitoring would also aid
27 in the protection of human health and the environment in that it would be used to evaluate
28 potential contaminant migration. This would influence a decision to take additional action, if
29 necessary.

30
31 **Compliance with ARARs**

32
33 The groundwater would still exceed SDWA based ARARs for chlorobenzenes.
34 Therefore, a waiver would have to be granted to pursue this alternative. If future site use is
35 planned to be restricted to rail, industrial, or trade-related uses, the threat of exposure to this
36 contamination may be deemed acceptable by regulators.

37 **Reduction of Toxicity, Mobility, or Volume through Treatment**

38
39 Provisions under this alternative would have no effect on toxicity, mobility, or
40 volume of contamination. However, as discussed in Section 1, the contaminants are
41 practically immobile and their volume is relatively small. Monitoring would serve to detect
42 contaminant migration over time.

Feasibility Study: Fort Devens FA II
Section No.: 5
Revision No.: 2
Date: January 1997

1 Long-term Effectiveness and Permanence

2

3 Because Institutional Actions will not meet the RAOs, the residual risk is equivalent
4 to the existing risks. The potential for human or ecological exposure to contaminants in
5 groundwater would endure, as would the potential for the contamination of other media. This
6 alternative does not satisfy the preference for treatment and permanence. However, based on
7 the very slow migration of contamination and the lack of drinking water wells, this exposure
8 is deemed to be minimal. A review of site conditions every 5 years, including a groundwater
9 sampling event, would be required to assess long-term risks. Appropriate action would be
10 taken at these times based on the review.

11 Short-term Effectiveness

12

13 The Institutional Actions alternative will have no impact on existing site conditions.
14 Personnel performing groundwater sampling activities would use PPE to prevent dermal
15 exposure to and inhalation of contaminants. This sampling could be done in a few days per
16 sampling event.

17 Implementability

18

19 Institutional Actions do not present any technical implementability obstacles.
20 Monitoring and/or future remedial action would be easily applied. However, the failure to
21 comply with ARARs poses a potentially difficult administrative obstacle.

22 Costs

23

24 There are no capital costs associated with this alternative. O&M costs, as presented
25 in Table 5-9, are associated with the groundwater sampling events every 5 years for 30 years.
26 It is assumed that only existing wells would be sampled and no new wells would be installed.
27 The approximate total present worth of Alternative B2 is \$81,950.

28 5.2.3 Alternative B3: Intrinsic Remediation

29

30 5.2.3.1 Detailed Description

31 The principal component of this alternative is the assumed natural attenuation and
32 bioremediation taking place at this site, which is proposed to reduce contaminant levels to
33 below ARARs before contaminants in the groundwater can leave the controlled area.

34 The key components of this alternative are:

35

- 36 • institutional control to prevent intrusion into or installation of wells
37 into the known area of contamination in the bedrock;
- 38 • intrinsic remediation by naturally occurring microorganisms in the
39 groundwater within the bedrock;

- installation of additional groundwater monitoring wells (for costing purposes, three shallow bedrock wells are proposed);
- collection of additional field data and incorporation of the data into groundwater flow and contaminant transport models;
- long-term monitoring and reports of groundwater quality;
- reviews of field data, modeling predictions and compliance with ARARs, at 5-year intervals; and
- review of the need for continued monitoring or of the need for additional action, at 5-year intervals.

5.2.3.2 Criteria Analysis

Overall Protection of Human Health and the Environment

The intrinsic remediation alternative will not directly treat, contain, destroy, or reduce the mobility of contaminants at the UST 13 groundwater area. The institutional restrictions will, if properly executed, prevent exposure to contaminants and reduce potential risks to human health to below acceptable levels. It will also provide good data on contaminant migration and the potential for human health risks to occur outside the controlled area.

Compliance with ARARs

Groundwater would not comply with ARARs for a long time. Prediction of the estimated time to achieve ARARs would depend on calibration and verification of the groundwater models, which would require a number of years of continued monitoring. There will be a certain degree of uncertainty in modeling the fractured bedrock aquifer at this site.

Reduction of Toxicity, Mobility, or Volume Through Treatment

This alternative does not offer any direct reduction of toxicity, mobility, or volume through treatment. The naturally occurring bioremediation is expected to reduce the compounds present in the bedrock beneath the site to protoplasm, carbon dioxide, water, and chlorides, by reductive dechlorination and metabolism of non-chlorinated constituents. This "remedy" proposes more intensive site characterization and monitoring to ensure that the expected results are, or are not, achieved.

Long-Term Effectiveness and Permanence

If performed as proposed and found to be effective, intrinsic remediation will be a permanent and effective long-term remediation of the site, which will restore groundwater to contaminant levels that represent an acceptable risk to human health and the environment.

1 Feasibility Study: Fort Devens FA II
2 Section No.: 5
3 Revision No.: 2
4 Date: January 1997

1 **Short-Term Effectiveness**
2

3 The proposed "remedy" will have little impact on site conditions in the short term.
4 Groundwater quality may, or may not, have improved by the time the additional field
5 investigation is completed and the existing wells are resampled.

6 **Implementability**
7

8 The intrinsic remediation alternative is readily implementable, both for additional well
9 installation, sampling, and modeling. Since the ultimate objective is compliance with ARARs,
10 no administrative obstacles appear to be likely.

11 **Costs**
12

13 Capital costs are involved for installation of additional wells and the creation of a site-
14 specific calibrated flow and contaminant transport model. O&M costs will consist of
15 sampling, analysis, and data interpretation, including possibly model adjustment, will occur
16 yearly. Costs are presented in Table 5-10. The approximate total present worth of the
17 "intrinsic remediation" alternative, assuming three additional shallow bedrock wells is
18 \$170,910. Costs are calculated annually for the first 5 years, when the entire remedial
19 process will be reviewed and revised, extended, or canceled. Thereafter, costs are calculated
20 for 5-year intervals until 30 years.

21 **5.2.4 Comparative Analysis of Alternatives**
22

23 Two of these alternatives, No Further Action and Institutional Actions, are essentially
24 equivalent. Neither involves any remedial action. The only difference is that Alternative B1
25 would provide annual monitoring for 5 years, whereas B2 provides for seven monitoring
26 events at 5 year intervals. Therefore, Alternative B2 would provide for monitoring of the
27 long-term potential for human health risk. However, as discussed in Section 2, the current
28 human health risks are minimal. Alternative B3, Intrinsic Remediation, provides for greater
29 safeguards to human health and the environment in that the distribution of contaminants is
30 more extensively characterized and monitored than in the preceding two alternatives. Models
31 of groundwater flow and of contaminant transport are also created and calibrated to provide
32 predictive capability, and then verified or modified as the result of long-term monitoring.
33 Because this alternative ensures that the site ultimately complies with ARARs, it appears that
34 there will be no administrative obstacles to implementing this alternative.

35 **5.3 POL STORAGE AREA/DRMO YARD GROUNDWATER OPERABLE UNIT**
36 **(AOC 32, 43A)**
37

38 Three alternatives for remediation of the POL Storage Area/DRMO Yard
39 groundwater were retained from the initial screening (Section 4). These are described in
40 detail in this section and analyzed with respect to the criteria presented by the EPA. The
41 three alternatives discussed below are:
42

1 Feasibility Study: Fort Devens FA II
2 Section No.: 5
3 Revision No.: 2
4 Date: January 1997

1 Alternative C1: No Further Action
2 Alternative C2: Institutional Actions
3 Alternative C3: Intrinsic Remediation

4

5 **5.3.1 Alternative C1: No Further Action**

6

7 **5.3.1.1 Detailed Description**

8

9 The "No Further Action" alternative is developed and evaluated to establish a baseline
10 for comparison with other remedial alternatives. Under this alternative, no remedial action of
11 any type would be undertaken. Neither the soils or groundwater in the vicinity of the POL
12 Storage Area/DRMO Yard would be removed, contained, or treated in any way. It is
13 assumed that the contamination would remain in its present state and pose the same risks as
14 currently exist.

15

16 Groundwater monitoring would be performed annually for 5 years under this
17 alternative. After 5 years the need for continued monitoring will be reviewed.

18

19 **5.3.1.2 Criteria Analysis**

20

21 **Overall Protection of Human Health and the Environment**

22

23 The "No Further Action" alternative would neither contain, treat, nor destroy the
24 contaminants in the groundwater under and downgradient of the POL Storage Area/DRMO
25 Yard. No measures, either remedial or institutional, would be taken to protect human health
26 or the environment, and RAOs would not be met. Monitoring, however, would be performed
27 in order to detect contaminant migration. This would influence a decision to take additional
28 action, if necessary.

29

30 **Compliance with ARARs**

31

32 The groundwater would still exceed ARARs for trichloroethene and 2-
33 methylnaphthalene, and a TBC for petroleum hydrocarbons. Therefore, a waiver would have
34 to be granted to pursue this alternative. If future site use is planned to be restricted to
35 industrial use, the threat of exposure to this contamination may be deemed acceptable by
36 regulators.

37

38 **Reduction of Toxicity, Mobility, or Volume through Treatment**

39

40 The "No Further Action" alternative would have no effect on the toxicity, mobility,
41 or volume of contamination. However, as discussed in Section 1, the contaminants occur in
42 only two isolated wells at relatively low levels. Monitoring would detect any contaminant
43 migration over time.

1 **Long-term Effectiveness and Permanence**

2
3 Because the "No Further Action" alternative will not meet the RAOs, the residual risk
4 is equivalent to the existing risks. The potential for human or ecological exposure to
5 contaminants in groundwater would endure, as would the potential for the contamination of
6 other media. This alternative does not satisfy the preference for treatment and permanence.
7 However, based on the three wells affected and the lack of drinking water wells, the exposure
8 is deemed to be minimal. Groundwater monitoring will assess long-term contamination
9 migration and human health risks, allowing appropriate actions to be taken if conditions
10 change.

11 **Short-term Effectiveness**

12
13 The "No Further Action" alternative will have no impact on existing site conditions.
14 Sampling could be performed in a few days per sampling event and represents minimal risk to
15 sampling personnel.

16 **Implementability**

17
18 The "No Further Action" alternative does not present any technical implementability
19 obstacles. Monitoring and/or future remedial action would be easily applied. However, the
20 failure to comply with ARARs poses a potentially difficult administrative obstacle.

21 **Costs**

22
23 There are no capital costs associated with this alternative. O&M costs, as presented
24 in Table 5-11, are associated with the groundwater sampling events, to be conducted for 5
25 years. It is assumed that existing wells would be sampled and no new wells installed. The
26 approximate total present worth of the "No Further Action" alternative is \$84,840, assuming
27 no further monitoring is required after 5 years.

28 **5.3.2 Alternative C2: Institutional Actions**

29 **5.3.2.1 Detailed Description**

30
31 No remediation would occur under this alternative; activity would be limited to
32 minimal measures intended to reduce exposure to contaminated media. Deed restrictions
33 would limit land use and development. The land would be limited to restricted development,
34 including a ban on drinking well installation, through deed restrictions. The land is currently
35 slated for rail, industrial, and trade-related uses by the Massachusetts Government Land Bank
36 (November 1996 Devens Reuse Plan), which will control development upon Army release of
37 the property, thus no further zoning alterations would be required. Because there is no
38 surficial contamination, fencing would not further reduce risks to human health or the
39 environment.

1 Groundwater monitoring would also be performed under this alternative. Every 5
2 years for a period of 30 years, the site conditions would be reviewed to determine the extent
3 of contaminant migration. A groundwater sampling event will be performed for each of these
4 reviews. In addition, exposure scenarios will be revisited based on site use at the time of
5 each review. If warranted, additional action will be considered at these times.

6

7 5.3.2.2 Criteria Analysis

8

9 **Overall Protection of Human Health and the Environment**

10

11 Institutional actions would not treat or destroy any of the contaminants; however, they
12 would isolate the contamination in an area restricted to development. Therefore, if executed
13 properly, institutional actions under this alternative would reduce human exposure to the
14 contaminants to acceptable risk levels. Risks to the environment would be unaffected;
15 however, ecological risks were found to be minimal. Groundwater monitoring would also aid
16 in the protection of human health and the environment in that it would be used to evaluate
17 potential contaminant migration. This would influence a decision to take additional action, if
18 necessary.

19

20 **Compliance with ARARs**

21

22 The groundwater would still exceed ARARs and TBCs. Therefore, a waiver would
23 have to be granted to pursue this alternative. If future site use is planned to be restricted to
24 industrial use, the threat of exposure to this contamination may be deemed acceptable by
25 regulators.

26

27 **Reduction of Toxicity, Mobility, or Volume through Treatment**

28

29 Provisions under this alternative would have no effect on toxicity, mobility, or
30 volume of contamination. However, as discussed in Section 1, the contaminants are scattered
31 and at relatively low levels. Monitoring would serve to detect contaminant migration over
32 time.

33

34 **Long-term Effectiveness and Permanence**

35

36 Because Institutional Actions will not meet the RAOs, the residual risk is equivalent
37 to the existing risks. The potential for human or ecological exposure to contaminants in
38 groundwater would endure, as would the potential for the contamination of other media. This
39 alternative does not satisfy the preference for treatment and permanence. However, based on
40 the lack of drinking water wells, this exposure is deemed to be minimal. A review of site
41 conditions every 5 years, including a groundwater sampling event, would be required to
42 assess long-term risks. Appropriate action would be taken at these times based on the review.

Feasibility Study: Fort Devens FA II
Section No.: 5
Revision No.: 2
Date: January 1997

1 **Short-term Effectiveness**
2

3 The Institutional Actions alternative will have no impact on existing site conditions.
4 Sampling could be done in a few days per sampling event and represents minimal risk to
5 sampling personnel.

6 **Implementability**
7

8 Institutional Actions do not present any technical implementability obstacles.
9 Monitoring and/or future remedial action would be easily applied. However, the failure to
10 comply with ARARs poses a potentially difficult administrative obstacle.

11 **Costs**
12

13 There are no capital costs associated with this alternative. O&M costs, as presented
14 in Table 5-12, are associated with the groundwater sampling events every 5 years for 30
15 years. It is assumed that only existing wells would be sampled and no new wells would be
16 installed. The approximate total present worth of Alternative C2 is \$69,460.

17 **5.3.3 Alternative C3: Intrinsic Remediation**
18

19 **5.3.3.1 Detailed Description**
20

21 The principal component of this alternative is the assumed natural attenuation and
22 bioremediation taking place at this site, which is proposed to reduce contaminant levels to
23 below ARARs before contaminants in the groundwater can leave the controlled area.

24 The key components of this alternative are:
25

- 26 • institutional control to prevent intrusion into or installation of wells
27 into the known area of contamination in the bedrock;
- 28 • intrinsic remediation by naturally occurring microorganisms in the
29 groundwater within the bedrock;
- 30 • installation of additional groundwater monitoring wells (for costing
31 purposes, three shallow bedrock wells are proposed);
- 32 • collection of additional field data and incorporation of the data into
33 groundwater flow and contaminant transport models;
- 34 • long-term monitoring and annual reports of groundwater quality;
- 35 • reviews of field data, modeling predictions and compliance with
36 ARARs, at 5-year intervals; and

Feasibility Study: Fort Devens FA II
Section No.: 5
Revision No.: 2
Date: January 1997

- review of the need for continued monitoring or of the need for additional action, at 5-year intervals.

5.3.3.2 Criteria Analysis

Overall Protection of Human Health and the Environment

The intrinsic remediation alternative will not treat, contain, destroy, or reduce the mobility of contaminants at the POL Storage Area/DRMO Yard groundwater operable unit. The institutional restrictions will, if properly executed, prevent exposure to contaminants and reduce potential risks to human health to below acceptable levels. It will also provide good data on contaminant migration and the potential for human health risks to occur outside the controlled area.

Compliance with ARARs

Groundwater would not immediately comply with ARARs. Prediction of the estimated time to achieve ARARs would depend on calibration and verification of the groundwater models, which would require a number of years of continued monitoring, by which time ARARs may no longer be exceeded.

Reduction of Toxicity, Mobility, or Volume Through Treatment

This alternative does not offer any direct reduction of toxicity, mobility, or volume through treatment. The naturally occurring bioremediation is expected to reduce the compounds present in the aquifer beneath the site to protoplasm, carbon dioxide, water, and chlorides, by reductive dechlorination and metabolism of non-chlorinated constituents. This "remedy" proposes more intensive site characterization and monitoring to determine if the expected results are, or are not, achieved.

Long-Term Effectiveness and Permanence

If performed or proposed and found to be effective, intrinsic remediation will be a permanent and effective long-term remediation of the site, which will restore groundwater to contaminant levels that represent an acceptable risk to human health and the environment.

Short-Term Effectiveness

The proposed "remedy" will have little impact on site conditions in the short term. Groundwater quality may, or may not, have improved by the time the additional field investigation is completed and the new and existing wells are resampled.

1 Feasibility Study: Fort Devens FA II
2 Section No.: 5
3 Revision No.: 2
4 Date: January 1997

1
2 **Implementability**
3

4 The intrinsic remediation alternative is readily implementable, both for additional well
5 installation, sampling, and modeling. Since the ultimate objective is compliance with ARARs,
6 no administrative obstacles appear to be likely.

7 **Costs**
8

9 Capital costs are involved for installation of additional wells and the creation of a site-
10 specific calibrated flow and contaminant transport model. O&M costs will consist of
11 sampling, analysis, and data interpretation, including possibly model adjustment, to occur
12 yearly. Costs are presented in Table 5-13. The approximate total present worth of the
13 "intrinsic remediation" alternative, assuming one additional bedrock well and four deeper (50
14 to 60 feet) overburden wells, is \$258,870. Costs are calculated annually for the first 5 years,
15 when the entire remedial process will be reviewed and revised, extended, or canceled.
16 Monitoring will continue at 5-year intervals until 30 years, and costs are calculated for these,
17 assuming that the program is carried to its maximum duration.

18
19 **5.3.4 Comparative Analysis of Alternatives**
20

21 Two of these alternatives, No Further Action and Institutional Actions, are essentially
22 equivalent. Neither involves any remedial action. The only difference is that Alternative C1
23 would provide annual monitoring for 5 years, whereas C2 provides for seven monitoring
24 events at 5 year intervals and controls exposure to groundwater. Therefore, Alternative C2
25 would provide for monitoring of the long-term potential for human health risk. However, as
26 discussed in Section 2, the current human health risks are minimal. Alternative B3, Intrinsic
27 Remediation, provides for greater safeguards to human health and the environment in that the
28 distribution of contaminants is more extensively characterized and monitored than in the
29 preceding two alternatives. Models of groundwater flow and of contaminant transport are
30 also created and calibrated to provide predictive capability, and then verified or modified as
31 the result of long-term monitoring. Because this alternative ensures that the site ultimately
32 complies with ARARs, it appears that there will be no administrative obstacles to
33 implementing this alternative.




Figure 5-1 ALTERNATIVE A3: AREAS OF EXCAVATION AND CAP




Figure 5-2 ALTERNATIVES A4 AND A6: AREAS OF EXCAVATION

Table 5-1

DETAILED ANALYSIS OF ALTERNATIVES
FOR DRMO YARD SOILS OPERABLE UNIT

Alternatives	Overall Protection	Compliance with ARARs	Reduction of Toxicity, Mobility, or Volume	Long Term Effectiveness	Short Term Effectiveness	Implementability	Capital Costs	O&M Present Worth Costs	Total Cost
A1: No Further Action (with groundwater monitoring) No additional protection to human health over the present state. There are no current ecological risks.	Surface soil ARAR (TSCA) for PCBs would be exceeded.	No reduction of toxicity, mobility, or volume is achieved in this alternative.	No additional protection in the long term would be provided. Existing zoning for restricted industrial use must be enforced. EPA's preference for permanent treatment would not be met under this alternative.	No additional protection would be provided in the short term.	An ARARs waiver would be required to implement this alternative.	\$0	\$80,380	\$80,380	
A2: Institutional Actions If implemented properly, Alternative A2 would isolate and contain contaminants, eliminating exposure routes and providing for protection of human health. There are no current ecological risks.	The exceedance, as in Alternative A1, would remain, but elimination of exposure pathways, yet there is no reduction of toxicity, mobility, or volume.	The toxicological risks are reduced by elimination of exposure pathways, yet there is no reduction of toxicity, mobility, or volume.	If fencing and access restrictions are properly maintained, this alternative may provide protection but, because no treatment is employed, this alternative would not necessarily be effective over the long term. EPA's preference for permanent treatment would not be met under this alternative.	Site workers constructing the fence would wear dermal and respiratory protection to avoid dust and contaminant exposure, but the alternative could be initiated immediately.	This alternative is easily implemented in a few weeks and would require minimal coordination and start up time. However, a waiver of ARARs would be required to leave the TSCA-regulated PCB contamination in place.	\$17,950	\$85,740	\$103,690	

Table 5-1

DETAILED ANALYSIS OF ALTERNATIVES
FOR DRMO YARD SOILS OPERABLE UNIT

Alternatives	Overall Protection	Compliance with ARARs	Reduction of Toxicity, Mobility, or Volume	Long Term Effectiveness	Short Term Effectiveness	Implementability	Capital Costs	O&M Present Worth Costs	Total Cost
A3: Containment Via Capping	Direct contact would be eliminated through the installation of an impermeable cap and a surrounding fence, eliminating exposure routes to humans. There are no current ecological risks.	The exceedance, as in the above alternatives, could still apply, but exposure routes would be eliminated. If the excavated soil to be capped is found to exhibit the toxicity characteristic due to lead, cadmium, or other contaminant, capping of these excavated soils would violate RCRA action-specific ARARs.	There is no reduction of toxicity or volume, yet mobility is reduced by prevention of surface water infiltration.	This alternative would require continuous maintenance and institutional actions to protect the capped area. Cap deterioration could potentially limit its long-term effectiveness. EPA's preference for permanent treatment would not be met under this alternative.	Human health risks may exist from dust and runoff over the short term, during earth moving and cap construction. Therefore dust control and runoff control activities would be required, as would dermal and respiratory protection for permanent workers.	Contractors are available to perform this remedy. However, untreated TSCA-regulated PCB-contaminated soils would remain on site. Thus an ARARs waiver could be required. Also future use of the site would be restricted. These two issues limit the implementability of this alternative.	\$470,320	\$366,200	\$836,520

Table 5-1

DETAILED ANALYSIS OF ALTERNATIVES
FOR DRMO YARD SOILS OPERABLE UNIT

Alternatives	Overall Protection	Compliance with ARARs	Reduction of Toxicity, Mobility, or Volume	Long Term Effectiveness	Short Term Effectiveness	Implementability	Capital Costs	O&M Present Worth Costs	Total Cost
A4: Excavation, Solidification, and On-Site Disposal	Direct contact would be eliminated through immobilization and containment of the soils, eliminating exposure routes to humans. There are no current ecological risks.	As the TSCA-regulated PCB-contaminated soil would be treated, ARARs would be complied with. If the solidified soil was found to exhibit the toxicity characteristic due to lead, cadmium, or other contaminants, then disposal of this solidified soil on site would violate RCRA action-specific ARARs.	There is a reduction of toxicity for lead and cadmium, but not for PCBs or pesticides. The mobility of the contaminants will be drastically reduced. The volume of waste will most likely, however, be increased.	Treatment of the soil would provide a good measure of long-term effectiveness. As neither PCPs nor pesticides would be chemically bound in the solidified matrix, some organics may eventually leach out.	Human health risks to workers and the community may exist from dust and runoff during earth moving and solidification activities.	Contractors are available to perform this work. However, future use of the site would be restricted due to monolith storage. Also, it will be difficult to evaluate its effectiveness or to implement additional remedial action.	\$490,870	\$287,270	\$778,140

Table 5-1

**DETAILED ANALYSIS OF ALTERNATIVES
FOR DRMO YARD SOILS OPERABLE UNIT**

Alternatives	Overall Protection	Compliance with ARARs	Reduction of Toxicity, Mobility, or Volume	Long Term Effectiveness	Short Term Effectiveness	Implementability	Capital Costs	O&M Present Worth Costs	Total Cost
A6: Excavation and Off-Site Disposal	This alternative would remove contaminants from the site, resulting in protection of human health at the site. There are no current ecological risks.	By removing TSCA-regulated PCB-contaminated soil, the PCB cleanup ARAR would be satisfied. If any soils were found to exhibit the hazard characteristic of toxicity due to lead, cadmium, or any other contaminant, they would have to be treated and/or disposed of in a RCRA-regulated facility.	There is no reduction of toxicity or volume. Soil is transported to a landfill, where its mobility will be controlled by landfill authorities.	This alternative would provide long term effectiveness, as long as the landfill continued to be monitored and regulated. It is a permanent solution to the on-site problem, but does not satisfy EPA preference for permanent treatment.	Human health risks to site workers and the community may exist during earth moving activities from dust and runoff. Therefore, dust control and runoff control activities would be required, as would dermal and respiratory protection for workers.	This alternative is readily implementable, assuming the soils do not fail TCLP tests. If they did, they would require disposal in a RCRA-certified landfill, as a waiver to dispose of the soils in a sanitary landfill would be difficult to obtain.	\$543,696	\$19,850	\$563,550

Table 5-2

DRMO YARD SOILS
ALTERNATIVE A1: NO FURTHER ACTION COSTS

Monitoring Costs**Interest rate (%): 6****Operation and Maintenance (years): 5**

Description	Quantity/ Year	Units	Unit Cost	Annual Cost
Groundwater monitoring (5 existing wells)				
Sampling equipment (containers, coolers, bailers, etc.)	1	lump sum	\$1,510	\$1,510
Safety equipment (monitoring devices, clothing)	1	lump sum	\$510	\$510
Shipping (equipment, protective clothing, samples)	550	lb.	\$1.50	\$830
Sample collection-labor (two-man team)	1	lump sum	\$400	\$400
Travel expenses (air fares, per diem (meals), van rental, fuel)	1	lump sum	\$1,250	\$1,250
Sample analysis costs (VOCs, PCBs/pest., metals-filtered and unfiltered; includes duplicate, trip blank, and rinsate blank samples)	1	lump sum	\$9,880	\$9,880
Data validation	20	hr.	\$470	\$470
Summary Report and Site Evaluation	1	lump sum	\$1,090	\$1,090
Subtotal Monitoring				\$15,940
10% legal, administrative, and engineering fees				\$1,594
10% contingencies				\$1,594
Total Monitoring Costs for 1 Year				\$19,130
Total Monitoring Present Worth (Annual for 5 years)				\$80,380
Total Present Worth - Alternative A1				\$80,380

Note: Costs were rounded to the nearest \$10.




Table 5-3

DRMO YARD SOILS
ALTERNATIVE A2: INSTITUTIONAL ACTIONS COSTS

Description	Quantity	Unit	Unit Cost	Cost
Summary of Capital Costs				
Mobilization	4	per person	\$61.84	\$250
Demobilization (3% of the capital costs)	1	lump sum	\$500	\$500
Health and safety (PPE)	1	lump sum	\$3,550	\$1,250
Fence Moving	840	linear foot	\$14.55	\$12,220
Addition of new fencing	60	linear foot	\$12.35	\$740
Subtotal Capital				\$14,960
10% legal, administrative, and engineering fees				\$1,496
10% contingencies				\$1,496
Total Capital Costs				\$17,950
Operation and Maintenance Costs				
Interest rate (%):	6			
Operation and Maintenance (years):	30			
Fence maintenance	50	linear foot	\$12.60	\$630
Subtotal O&M				\$630
10% legal, administrative, and engineering fees				\$63
10% contingencies				\$63
Total Annual O&M Costs				\$760
Total O&M Present Worth (every 6 months for 30 years)				\$20,860
Total Capital Costs (above)				\$17,950
Total Present Worth, Monitoring (see table below)				\$64,880
Total Present Worth - Alternative A2				\$103,690

Table 5-3 (continued)

DRMO YARD SOILS
ALTERNATIVE A2: INSTITUTIONAL ACTIONS COSTS

Monitoring Costs**Interest rate (%): 6****Operation and Maintenance (years): 30**

Description	Quantity/Year	Units	Unit Cost	Annual Cost
Groundwater Monitoring (5 existing wells)				
Sampling equipment (containers, coolers, bailers, etc.)	1	lump sum	\$1,510	\$1,510
Safety equipment (monitoring devices, clothing)	1	lump sum	\$510	\$510
Shipping (equipment, protective clothing, samples)	550	lb.	\$1.50	\$830
Sample collection - labor (2-man team)	1	lump sum	\$400	\$400
Travel expenses (air fare, per diem [meals], van rental, fuel)	1	lump sum	\$1,250	\$1,250
Sample analysis costs (VOCs, PCBs/pest, metals - filtered and unfiltered; includes duplicate, trip blank, and rinsate blank samples)	1	lump sum	\$10,760	\$10,760
Data Validation	40	hr.	\$23.50	\$940
Summary Report	1	lump sum	\$1,190	\$1,190
Site Evaluation every 5 years	1	lump sum	\$4,750	\$4,750
Subtotal Monitoring				\$22,140
10% legal, administrative, and engineering fees				\$2,214
10% contingencies				\$2,214
Total Future Monitoring Costs				\$26,570
Total Monitoring Present Worth (every 5 years for 30 years)				\$64,880

Note: Costs were rounded to the nearest \$10.

Table 5-4

DRMO YARD SOILS
ALTERNATIVE A3: CONTAINMENT VIA CAPPING COSTS

Description	Quantity	Unit	Unit Cost	Cost
Summary of Capital Costs				
Mobilization	6	per person	\$61.84	\$370
Demobilization (3% of the capital costs)	1	lump sum	\$12,640	\$12,640
Site services (utilities, survey, etc.)	1	lump sum	\$19,240	\$19,240
Health and safety (PPE)	1	lump sum	\$36,920	\$36,920
Excavation, Backfill and Consolidation (Ditches)	360	cubic yard	\$9.38	\$3,380
Temporary Cover	5,425	square yard	\$0.07	\$660
Cap:				
Regrading	5,425	square yard	\$1.36	\$7,380
18-inch clay layer	2,713	cubic yard	\$16.10	\$43,680
6-inch sand drainage layer	904	cubic yard	\$9.79	\$8,850
6-inch topsoil	904	cubic yard	\$24.71	\$22,340
Seeding	1.13	acre	\$1,488.73	\$1,680
Rip-Rap	904	cubic yard	\$28.50	\$25,760
Verification Sampling	1	lump sum	\$3,810	\$3,810
Verification Analysis	106	each	\$792.16	\$83,970
TCLP Sampling	1	lump sum	\$3,810	\$3,810
TCLP Analysis	106	each	\$866.37	\$91,840
Fence Moving	840	linear feet	\$14.55	\$12,220
Addition of New Fencing	60	linear feet	\$12.35	\$740
Subtotal Capital				\$391,930
10% legal, administrative, and engineering fees				\$39,193
10% contingencies				\$39,193
Total Capital Costs				\$470,320
Total O&M Present Worth (see table below)				\$366,200
Total Present Worth - Alternative A3				\$836,520

Table 5-4 (continued)

DRMO YARD SOILS
ALTERNATIVE A3: CONTAMINANT VIA CAPPING COSTS

Operation and Maintenance and Monitoring Costs**Interest rate (%): 6****Operation and Maintenance (years): 30**

Description	Quantity/Year	Units	Unit Cost	Annual Cost
Groundwater Monitoring (5 existing wells)				
Sampling equipment (containers, coolers, bailers, etc.)	1	lump sum	\$1,510	\$1,510
Safety equipment (monitoring devices, clothing)	1	lump sum	\$510	\$510
Shipping (equipment, protective clothing, samples)	550	lb.	\$1.50	\$830
Sample collection - labor (2-man team)	1	lump sum	\$400	\$400
Travel expenses (air fare, per diem [meals], van rental, fuel)	1	lump sum	\$1,250	\$1,250
Sample analysis costs (VOCs, PCBs/pest., metals - filtered and unfiltered; includes duplicate, trip blank, and rinsate blank samples)	1	lump sum	\$10,760	\$10,760
Data Validation	40	hr.	\$23.50	\$940
Summary Report	1	lump sum	\$1,190	\$1,190
Maintenance:				
Cap	1	lump sum	\$4,190	\$4,190
Fence	50	linear foot	\$12.60	\$630
Subtotal O&M				\$22,210
10% legal, administrative, and engineering fees				\$2,221
10% contingencies				\$2,221
Total Annual O&M and Monitoring Costs				\$26,650
Total O&M and Monitoring Present Worth (every year for 30 years)				\$366,200

Note: Costs were rounded to the nearest \$10.

Table 5-5

DRMO YARD SOILS

ALTERNATIVE A4: EXCAVATION, SOLIDIFICATION, AND ON-SITE DISPOSAL

Description	Quantity	Unit	Unit Cost	Cost
Summary of Capital Costs				
Mobilization	6	per person	\$61.84	\$370
Demobilization (3% of the capital costs)	1	lump sum	\$14,030	\$14,030
Site service (utilities, survey, etc.)	1	lump sum	\$24,330	\$24,330
Health and safety (PPE)	1	lump sum	\$49,230	\$49,230
Treatability Study	1	lump sum	\$25,000	\$25,000
Soil Excavation	1,300	cubic yard	\$2.62	\$3,410
Backfill	1,300	cubic yard	\$1.51	\$1,960
Soil Loading and Handling	1,300	cubic yard	\$1.38	\$1,790
Temporary Cover	3,940	square yard	\$0.07	\$280
Soil Treatment	1	lump sum	\$72,240	\$72,240
Verification sampling	1	lump sum	\$3,810	\$3,810
Verification analysis	106	each	\$792.16	\$83,970
TCLP sampling	1	lump sum	\$3,810	\$3,810
TCLP analysis	106	each	\$866.37	\$91,840
Additional soil excavation	325	cubic yard	\$2.62	\$850
Backfilling and Compaction of Treated Soil	1,625	cubic yard	\$5.00	\$8,130
Grading	3,940	square yard	\$1.36	\$5,360
6-inch Topsoil	660	cubic yard	\$24.71	\$16,310
Seeding	0.81	acre	\$1,488.73	\$1,210
Subtotal Capital				\$409,060
10% legal, administrative, and engineering fees				\$40,906
10% contingencies				\$40,906
Total Capital Costs				\$490,870
Total Monitoring Present Worth (see table below)				\$287,270
Total Present Worth - Alternative A4				\$778,140

Table 5-5 (continued)

DRMO YARD SOILS
ALTERNATIVE A4: EXCAVATION, SOLIDIFICATION, AND ON-SITE DISPOSAL

Monitoring Costs**Interest rate (%): 6****Operation and Maintenance (years): 30**

Description	Quantity/Year	Units	Unit Cost	Annual Cost
Groundwater Monitoring (5 existing wells)				
Sampling equipment (containers, coolers, bailers, etc.)	1	lump sum	\$1,510	\$1,510
Safety equipment (monitoring devices, clothing)	1	lump sum	\$510	\$510
Shipping (equipment, protective clothing, samples)	550	lb.	\$1.50	\$830
Sample collection - labor (2-man team)	1	lump sum	\$400	\$400
Travel expenses (air fare, per diem [meals], van rental, fuel)	1	lump sum	\$1,250	\$1,250
Sample analysis costs (VOCs, PCBs/pest., metals - filtered and unfiltered; includes duplicate, trip blank, and rinsate blank sample)	1	lump sum	\$10,760	\$10,760
Data Validation	40	hr.	\$23.50	\$940
Summary Report	1	lump sum	\$1,190	\$1,190
Subtotal Monitoring				\$17,390
10% legal, administrative, and engineering fees				\$1,739
10% contingencies				\$1,739
Total Annual Monitoring Costs				\$20,870
Total Monitoring Present Worth (every year for 30 years)				\$287,270

Note: Costs were rounded to the nearest \$10.

Table 5-6

DRMO YARD SOILS
ALTERNATIVE A6: EXCAVATION AND OFF-SITE DISPOSAL COSTS

Description	Quantity	Unit	Unit Cost	Cost
Summary of Capital Costs				
Mobilization	4	per person	\$61.84	\$250
Demobilization (3 % of the capital costs)	1	lump sum	\$14,120	\$14,120
Site services (utilities, survey, etc.)	1	lump sum	\$14,140	\$14,140
Health and safety (PPE)	1	lump sum	\$19,090	\$19,090
Soil Excavation	1,300	cubic yard	\$2.62	\$3,410
Soil Handling/Loading	1,300	cubic yard	\$1.38	\$1,790
Temporary Cover	3,940	square yard	\$0.07	\$280
Transportation (100 mi. round trip)	70	dump truck	\$683.63	\$47,850
Disposal	1,300	cubic yard	\$111.31	\$144,700
Verification sampling	1	lump sum	\$3,810	\$3,810
Verification analysis	106	each	\$792.16	\$83,970
TCLP sampling	1	lump sum	\$3,810	\$3,810
TCLP analysis	106	each	\$866.37	\$91,840
Backfill and compaction	1,300	cubic yard	\$5.00	\$6,500
6-inch Topsoil	660	cubic yard	\$24.71	\$16,310
Seeding	0.81	acre	\$1,488.73	\$1,210
Subtotal Capital				\$453,080
10% legal, administrative, and engineering fees				\$45,308
10% contingencies				\$45,308
Total Capital Costs				\$543,696
Total Monitoring Present Worth (see table below)				\$19,850
Total Present Worth - Alternative A6				\$563,550

Table 5-6 (continued)

DRMO YARD SOILS
ALTERNATIVE A6: EXCAVATION AND OFF-SITE DISPOSAL COSTS

Monitoring Costs**Interest rate (%): 6****Operation and Maintenance (years): 5**

Description	Quantity/Year	Units	Unit Cost	Annual Cost
Groundwater Monitoring (5 existing wells)				
Sampling equipment (containers, coolers, bailers, etc.)	1	lump sum	\$1,510	\$1,510
Safety equipment (monitoring devices, clothing)	1	lump sum	\$510	\$510
Shipping (equipment, protective clothing, samples)	550	lb.	\$1.50	\$830
Sample collection - labor (2-man team)	1	lump sum	\$400	\$400
Travel expenses (air fare, per diem [meals], van rental, fuel)	1	lump sum	\$1,250	\$1,250
Sample analysis costs (VOCs, PCBs/pest., metals - filtered and unfiltered; includes duplicate, trip blank, and rinsate blank samples)	1	lump sum	\$10,760	\$10,760
Data Validation	40	hr.	\$23.50	\$940
Summary Report	1	lump sum	\$1,190	\$1,190
Site Evaluation after 5 years	1	lump sum	\$4,750	\$4,750
Subtotal Monitoring				\$22,140
10% legal, administrative, and engineering fees				\$2,214
10% contingencies				\$2,214
Total Future Monitoring Costs				\$26,568
Total Monitoring Present Worth (1 event in 5 years)				\$19,850

Note: Costs were rounded to the nearest \$10.

Table 5-7 DRMO YARD SOILS ALTERNATIVE COST SUMMARY			
Alternative	Capital Cost	O&M and Monitoring Present Worth Costs	Total Present Worth Cost
A1: No Further Action	\$0	\$80,380	\$80,380
A2: Institutional Actions	\$17,950	\$85,740	\$103,690
A3: Containment Via Capping	\$470,320	\$366,200	\$836,520
A4: Excavation, Solidification, and On-site Disposal	\$490,870	\$287,270	\$778,140
A6: Excavation and Off-site Disposal	\$543,696	\$19,850	\$563,550

Table 5-8

**UST-13 GROUNDWATER COST SUMMARY
ALTERNATIVE B1: NO FURTHER ACTION**

Interest rate (%): 6

Operation and Maintenance (years): 5

Description	Annual Cost
Groundwater Monitoring (4 existing wells)	
Sampling equipment (Labor, ODCS)	\$4,320
Sample analysis costs (VOCs, PCBs/pest., metals - filtered and unfiltered; includes duplicate, trip blank, and rinsate blank samples)	\$9,320
Summary Report and Site Evaluation	\$1,366
Subtotal Monitoring	\$15,006
20% legal, administrative, and engineering fees/contingency	\$3,000
Total Monitoring Costs for 1 Year	\$18,000
Total Monitoring Present Worth (Annual for 5 years)	\$75,820
Total Present Worth - Alternative B1	\$75,820

Note: Costs were rounded to the nearest \$10.

Table 5-9

UST-13 GROUNDWATER COST SUMMARY
ALTERNATIVE B2: INSTITUTIONAL ACTIONS

Interest rate (%): 6**Operation and Maintenance (years): 30**

Description	Years	Annual Cost
Groundwater Monitoring (4 existing wells)		
Sampling (labor, ODCs)	0, 5, 10, 15, 20, 25, 30	\$4,320
Sample analysis costs (VOCs, PCBs/pest., metals - filtered and unfiltered; includes duplicate, trip blank, and rinsate blank samples)	0, 5, 10, 15, 20, 25, 30	\$9,320
Summary Report and Site Evaluation	0, 5, 10, 15, 20, 25, 30	\$6,195
Subtotal Monitoring Cost (every 5 years)		\$19,840
20% legal, administrative, and engineering fees/contingency		\$3,968
Total Monitoring Cost (every 5 years)		\$23,810
Subtotal Costs for 30 years - every 5 years (7 times)		\$166,670
Total Monitoring Present Worth (every 5 years for 30 years)		\$81,950
Total Present Worth - Alternative B2		\$81,950

Note: Costs were rounded to the nearest \$10.

Table 5-10

**UST-13 GROUNDWATER COST SUMMARY
ALTERNATIVE B3: INTRINSIC REMEDIATION**

Interest rate (%): 6

Operation and Maintenance (years): 30

Description	Quantity/Year	Annual Cost
Well installation	4 wells/Year 1	\$5,870
Sampling (labor, other direct costs (ODCs))	Year 1	\$6,580
Analytical Costs	Year 1	\$6,980
Report, Modeling, Site Evaluation	Year 1	\$32,710
Fees and Contingency (20%)	Year 1	\$6,542
Subtotal	Year 1	\$58,682
Total Present Worth	Year 1	\$55,360
Sampling Wells (labor, ODCs)	Years 2 to 4 (ea)	\$6,580
Analytical Costs	Years 2 to 4 (ea)	\$6,980
Report, Site Evaluation	Years 2 to 4 (ea)	\$3,680
Fees and Contingency (20%)	Years 2 to 4 (ea)	\$3,448
Subtotal Yearly Cost	Years 2 to 4 (ea)	\$20,688
Total Present Worth	Years 2 to 4 (all)	\$52,170
Sampling Wells (labor, ODCs)	Year 5	\$6,580
Analytical Costs	Year 5	\$6,980
Report, Site Evaluation	Year 5	\$8,070
Fees and Contingency (20%)	Year 5	\$4,326
Subtotal Cost	Year 5	\$25,956
Total Present Worth	Year 5	\$19,395
Annual Cost	Years 10, 15, 20, 25, and 30	\$25,956
Subtotal Cost	Years 10, 15, 20, 25, and 30	\$129,780
Total Present Worth	Years 10, 15, 20, 25, and 30	\$43,985
Total Present Worth	Years 1 through 30	\$170,910

Note: Costs were rounded to the nearest \$10.

Table 5-11

**POL STORAGE AREA/DRMO YARD GROUNDWATER
COST SUMMARY
ALTERNATIVE C1: NO FURTHER ACTION**

Interest rate (%): 6

Operation and Maintenance (years): 5

Description	Year	Annual Cost
Groundwater Monitoring (11 existing wells)		
Sampling (labor, other direct costs (ODCs))	1 to 5 Years	\$4,460
Analytical Cost	1 to 5 Years	\$10,760
Report and Site Evaluation	1 to 5 Years	\$1,560
Fee and Contingency (20%)	1 to 5 Years	\$3,360
Subtotal Yearly Cost		\$20,140
Total Monitoring Present Worth	Annual for 5 Years	\$84,840
Total Present Worth - Alternative 1		\$84,840

Note: Costs were rounded to the nearest \$10.

Table 5-12

**POL STORAGE AREA/DRMO YARD GROUNDWATER COST SUMMARY
ALTERNATIVE C2: INSTITUTIONAL CONTROLS**

Interest rate (%): 6

Operation and Maintenance (years): 30

Description	Years	Annual Cost
Groundwater Monitoring (11 existing wells)		
Sampling (labor, other direct costs (ODCs))	0, 5, 10, 15, 20, 25, 30	\$4,500
Analytical Cost	0, 5, 10, 15, 20, 25, 30	\$10,760
Report and Site Evaluation	0, 5, 10, 15, 20, 25, 30	\$1,560
Fees and Contingency (20%)	0, 5, 10, 15, 20, 25, 30	\$3,360
Subtotal Monitoring Cost (every 5 years)		\$20,180
Subtotal costs for 30 years - every 5 years (7 times)		\$141,260
Total Monitoring Present Worth	30 Years Monitoring	\$69,460
Total Present Worth - Alternative 2		\$69,460

Note: Costs were rounded to the nearest \$10.

Table 5-13

**POL STORAGE AREA/DRMO YARD GROUNDWATER COST SUMMARY
ALTERNATIVE C3: INTRINSIC REMEDIATION**

Interest rate (%): 6

Operation and Maintenance (years): 30

Description	Quantity/Year	Annual Cost
Well installation	5 wells/Year 1	\$10,350
Sampling (labor, other direct costs (ODCs))	5 wells/Year 1	\$11,260
Analytical Costs	5 wells /Year 1	\$11,460
Report, Site Modeling, and Evaluation	Year 1	\$41,280
Fee and Contingency (20%)	Year 1	\$14,870
Subtotal Year 1		\$89,220
Present Worth Year 1		\$84,170
Sampling (labor, ODCs)	Years 2 to 4 (ea)	\$11,260
Analytical Costs	Years 2 to 4 (ea)	\$11,460
Report, Site Evaluation	Years 2 to 4 (ea)	\$4,830
Fees and Contingency (20%)	Years 2 to 4 (ea)	\$5,510
Subtotal Years 2 to 4 (ea)		\$33,060
Present Worth Years 2 to 4 (total)		\$83,370
Sampling (labor, ODCs)	Year 5	\$11,260
Analytical Costs	Year 5	\$11,460
Report, Site Evaluation	Year 5	\$8,450
Fee and Contingency (20%)	Year 5	\$6,230
Subtotal Year 5		\$37,400
Present Worth Year 5		\$27,950
Sampling/Site Evaluation	Years 10, 15, 20, 25, and 30	\$187,000
Present Worth Years 10, 15, 20, 25, and 30		\$63,380
Total Present Worth Years 1 through 30		\$258,870

Note: Costs were rounded to the nearest \$10.

Table 5-14**ARARS AND TBCS FOR SOILS REMEDIAL ALTERNATIVES (DRMO YARD)**

Federal Regulation	Medium Regulated	Specific Requirements
Chemical-Specific ARARs/TBCs (see Table 2-1)		
Toxic Substance Control Act (TSCA) 40 CFR 761.125(c)(4)	Surface Soil (0 to 10 inches) Subsurface Soil (below 10 inches)	Unrestricted Access less than 1 mg/kg PCBs. Unrestricted Access less than 10 mg/kg PCBs.
To Be Considered (TBC)		
EPA Region III Risk-Based Concentration Table	Soil	Exposure levels to numerous chemicals under specific scenarios.
Resource Conservation and Recovery Act (RCRA) Corrective Action Levels 55 FR 30798, July 1990	Soil	To establish the need for a corrective measures study. Numerous chemicals.
Revised Interim Soil Lead Guidance for CERCLA Sites and RCRA Corrective Action Facilities. EPA OSWER Directive 9355.4-12, July 1994	Soil	Health-based soil lead screening value of 400 mg/kg for residential areas.
Background levels for metals	Soil	Candidate Cleanup goal not to be below background.
Massachusetts Contingency Plan (MCP) 310 CMR 40.09705(6)(a)	Soil	Total Petroleum Hydrocarbons not to exceed 500 mg/kg.
Federal and State Regulation Location-Specific ARARs		
There are no location-specific ARARs for the DRMO Yard (AOC 32). See Table 2-4)	Not Applicable	None
Federal and State Regulation Action-Specific ARARs		
If specific remedial actions generate hazardous waste or dispose of hazardous waste (53 FR 51437), then action-specific ARARs may specify particular performance standards or technology under a number of Federal laws (RCRA, CAA, CWA, SDWA, TSCA, etc)	All	None established. No hazardous waste is expected to be generated or identified in the DRMO Soils Operable Unit.
Massachusetts Hazardous Waste Management Rules (310 CMR 30.00) would also have to be complied with	All	None established. No hazardous waste is expected to be generated from DRMO Soils Operable Unit.

Table 5-15

**FEDERAL AND STATE ARARS FOR AOCS 32 AND 43A
POL STORAGE AREAS/DRMO YARD GROUNDWATER**

Authority	Medium Regulated	Specific Requirements
Federal Regulatory Authority (Location-Specific)	Groundwater	No location-specific ARARs identified.
Federal Regulatory Authority SDWA - National Primary Drinking Water Standards, MCLs (40 CFR 141.11 to 141.16 and 141.50 to 141.53) (Chemical-Specific)	Potential Drinking Water Supplies (at AOCs)	MCLs have been established for many inorganics and organics which may not be exceeded in public drinking water supplies. Monitoring is required to ensure ARARs (MCLs) not exceeded.
Federal Regulatory Authority (Action-Specific)	Groundwater in place	If monitoring only, no action-specific ARARs must be met (action-specific ARARs apply to extraction/treatment).
State Regulatory Authority (Location-Specific) [314 CMR 6.00]	Groundwater classified as Class 1 (potential source of potable water)	Groundwater quality shall be maintained and protected in all Class 1 aquifers.
Massachusetts Groundwater Quality Standards [314 CMR 6.00] (Chemical-Specific)	Groundwater classified as Class 1 (potential source of potable water)	Standards have been set for many inorganics and organics which may not be exceeded in Class 1 aquifers unless from naturally occurring sources. Often equivalent to MCLs, but may differ.
State Regulatory Authority (Action-Specific)	Groundwater in place.	If monitoring only, no action-specific ARARs must be met (action-specific ARARs apply to extraction and treatment).

1 Feasibility Study: Fort Devens FA II
2 Section No.: 6
3 Revision No.: 2
4 Date: January 1997

5
6 **6. REFERENCES**
7
8
9

10 ABB Environmental Services, Inc., 1996, *Draft Radiological Survey and Remediation Report,*
11 *DRMO Yard*, Contract No. DACA31-94-D-0061, July 1996, Wakefield,
12 Massachusetts.
13
14 ABB, 1993, *Final Site Investigation Report Fort Devens*, Groups 2,7, and Historic Gas
15 Stations, Contract No. DAAA15-91-D-0008, December 1993, Portland, Maine.
16
17 Berry, W.E., 1988, personal communication from chief Property Disposal Officer, Fort
18 Devens.
19
20 Butler, Brian O., 1993, Personal communication regarding Blanding's Turtle Study, Fort
21 Devens.
22
23 Czarnecki, R.C., 1989, Hot Mix Asphalt Technology and the Cleaning of Contaminated
24 Soils, E.J. Calabrese and P.T. Kostecki, eds., Lewis Publishers, Inc., Chelsea,
25 Michigan.
26
27 Ecology and Environment, Inc. (E & E), 1994, *Remedial Investigations Report for Functional*
28 *Area II Fort Devens, Massachusetts*, Contract No. DAAA15-90-D-0012, Arlington,
29 Virginia.
30
31 E & E, 1992, *Final Site Investigations Report for Study Areas 15, 24, 25, 26, 32, and 48*,
32 Fort Devens, Massachusetts, Contract No. DAAA15-90-D-0012, December 1992,
33 Arlington, Virginia.
34
35 Environmental Applications, Inc. (EA), 1990, *Fort Devens Tank Replacement Project Final*
36 *Report*.
37
38 Massachusetts, Commonwealth of, 1993, *Massachusetts Contingency Plan (MCP)*, 310 CMR
39 40.000, Boston, Massachusetts, 30 July.
40
41 Massachusetts, Commonwealth of, 1992, *Massachusetts Drinking Water Standards and*
42 *Guidelines*, 310 CMR 22, Boston, Massachusetts.
43
44 Massachusetts Department of Environmental Protection (MDEP), 1992, *Documentation for*
45 *the Risk Assessment Shortform Residential Scenario*, Commonwealth of
Massachusetts, October 1992.
46
47 Massachusetts Government Land Bank, 1996, *Devens Reuse Plan*, November.

Feasibility Study: Fort Devens FA II
Section No.: 6
Revision No.: 2
Date: January 1997

1 Massachusetts Natural Heritage and Endangered Species Program (MNHESP), 1993, *Atlas of*
2 *Estimated Habitats of State-Listed Rare Wetlands Wildlife*, Massachusetts Division of
3 Fisheries and Wildlife.

4 Murphy, David, 1994, Massachusetts Department of Environmental Protection, personal
5 communication with David Bailey, 15 September 1994, E & E, Arlington, Virginia.

6 United States Department of the Defense (USDOD), 1993, *BRAC Cleanup Plan (BCP)*
7 *Guidebook*, Fall 1993.

8 United States Environmental Protection Agency (USEPA), 1994, *Revised Interim Soil Lead*
9 *Guidance for CERCLA Sites and RCRA Corrective Action Facilities*, Office of Solid
10 Waste and Emergency Response Directive, OSWER 9355.4-12, July 1994.

11 USEPA, 1993, *Risk Concentration Table, Fourth Quarter, 1993*, EPA Region III.

12 USEPA, 1992a, *Guidelines for Exposure Assessment*, Final Rule, Federal Register 57, 22888,
13 29 May 1992.

14 USEPA, 1992b, *National Oil and Hazardous Substances Pollution Contingency Plan (The*
15 *NCP*), Publication 9200.2-14, Office of Emergency and Remedial Response,
16 Washington, D.C.

17 USEPA, 1992c, *National Oil and Hazardous Substances Pollution Contingency Plan (The*
18 *NCP*), Publication 9200.2-14, Office of Emergency and Remedial Response,
19 Washington, D.C.

20 USEPA, 1991a, *Update on OSWER Soil Lead Cleanup Guidance*, OSWER Directive
21 9355.4-02a, 29 August 1991.

22 USEPA, 1991b, *National Primary Drinking Water Regulations*, Final Rule, FR:56 3578-3596,
23 30 January 1991.

24 USEPA, 1990, *RCRA Corrective Action for Solid Waste Management Units at Hazardous*
25 *Waste Management Facilities*, Federal Register FR 55, 27 July 1990.

26 USEPA, 1989a, *Stabilization/Solidification of CERCLA and RCRA Wastes*, Center for
27 Environmental Research Information, Cincinnati, Ohio, May 1989.

28 USEPA, 1988a, *CERCLA Compliance with Other Laws Manual*, EPA/540/G-89/006.

29 USEPA, 1988b, *Guidance for Conducting Remedial Investigations and Feasibility Studies*
30 *under CERCLA*, EPA-540/G-89-004, OSWER Directive 9355.3-01, October.

31 USEPA, 1986, *Guideline for Groundwater Classification*, 55 FR 8732, December.

APPENDIX A


**PARTICLE TRACKING SIMULATION RESULT FOR FORT DEVENS
MAIN POST: FROM POL STORAGE YARD TO THE MACPHERSON WELL
(PERFORMED BY ENGINEERING TECHNOLOGIES ASSOCIATES, INC.)**

Engineering Technologies Associates, Inc.

Engineers • Planners • Surveyors



3458 Ellicott Center Drive, Suite 101
Ellicott City, MD 21043



Baltimore Area (410) 461-9920
Washington Area (301) 621-4690
FAX: (410) 750-8565

June 27, 1995

Robert King
Ecology & Environment, Inc.
1700 N. Moore St.
Arlington, VA 22209

Re: Particle tracking simulation result for Fort Devens Main Post:
from POL storage yard to the MacPherson well.

Dear Bob:

Engineering Technologies Associates, Inc. (ETA) was retained by the Ecology and Environment, Inc. to perform the particle tracking analysis for the ground water flow system of the POL storage yard at Fort Devens, Massachusetts. The objective of the analysis is to define the flow path and to estimate the travel time from the POL storage yard to the MacPherson well under a Zone II delineation flow field. This letter serves as a short technical report of ETA's analysis.

ETA has previously performed detailed flow modeling and Zone II delineation at the Main and North Post of Fort Devens. Zone II delineations were made using three different procedures. The POL storage yard was within the Zone II area of the MacPherson well when the revised MADEP procedure was used (ETA, 1995). The particle tracking analysis estimated the travel time and flow path from POL storage yard to MacPherson well.

In the particle analysis, the hydraulic head output from the regional transient flow model was utilized to calculate the ground water velocity vectors through a postprocessor program, PREMOD3D. (ETA, 1994). The calculated velocity data were then input into the RAND3D, a three dimensional ground water, solute transport model (ETA, 1993), to trace the flow path and to estimate the particle migration time. The same input packages used in the flow model were used in the calculation of the velocity. In the particle tracking analysis, the same effective porosity's of 0.2 for layers one and two, and 0.05 for the bedrock used in the previous transport model were employed.

Ten particle points were placed within the designated area to simulate the tracer. The starting point of each particle is at the water table. No retardation or biotransformation effects were taken into account during the particle transport process. All the particles migrate toward

the MacPherson well on a similar path. The particle transport slowly at the beginning due to the long distance from the pumping well. It took thirteen years for the first particle to migrate to the pumping well and seventeen years for the last particle to reach the pumping well. The following figures show the particle flow paths and locations at different time intervals. Figure one indicates the flow paths and particle locations after five years. Figures 2 to 13 show particle paths at one year intervals.

The analysis is unrealistic for a number of reasons. The pumping scenario used was unrealistic. It assumed the MacPherson well was pumping at 1,000 gallons per minute (gpm) during the model steady state simulation. Recharge was then assumed to be zero and the MacPherson well continued pumping at 1,000 gpm during a six month transient simulation. The analysis used the flow stream lines at the end of the six month transient simulation. The MacPherson well normally pumps about 700 gpm for short periods. The average pumpage for 1993 was 70 gpm (ETA, 1995).

The analysis ignores the effect of adsorption. Adsorption of hydrophobic organic chemicals will retard the travel of any contamination.


The analysis ignores the impact of biodegradation on organic chemicals that are in ground water beneath the POL yard.

The analysis shows that a conservative tracer would take between thirteen and seventeen years to travel from the POL yard to the MacPherson well under one set of conditions dictated by the MADEP for Zone II well head protection zone analysis.

The above is the analysis of the particle tracking simulation for this project. Please feel free to call us should you have any questions.

Truly yours,


Song Jiang
Hydrogeologist


Don Koch, P.E.
Vice President

Attachment

Reference List

Engineering Technologies Associates, Inc. 1993, A Three Dimensional, Ground Water, Solute Transport Model, Users' Manual, Contract DAAA15-89-D-0009/0003.

Engineering Technologies Associates, Inc. 1994, A RAND3D Preprocessor to Prepare Input From MODFLOW, Users' Manual.

Engineering Technologies Associates, Inc. 1995, Detailed Flow Model for Main and North Post, Fort Devens, Massachusetts, Final Report, Contract DACA31-92-D-0045/0004.

Figure 1 (Five years after particle release)




Figure 2 (Six years after particle release)




Figure 3 (Seven years after particle release)




Figure 4 (Eight years after particle release)




Figure 5 (Nine years after particle release)




Figure 6 (Ten years after particle release)




Figure 7 (Eleven years after particle release)




Figure 8 (Twelve years after particle release)




Figure 9 (Thirteen years after particle release)




Figure 10 (Fourteen years after particle release)




Figure 11 (Fifteen years after particle release)




Figure 12 (Sixteen years after particle release)






Figure 13 (Seventeen years after particle release)



All figures have the same scale of approximate 1"=1100'.



APPENDIX B

BACK-UP COST CALCULATIONS

B.1 DRMO YARD BACK-UP COST CALCULATIONS

MONITORING COSTS

DRYDO YARD
MONITORING OF SOILS REMEDIATION
SAMPLING EQUIPMENT COSTS

recycled paper

	Unit	Unit Cost	Quantity	Cost	Source
Well Development Equipment Rental (pH, Temp, Conductivity, Turbidity, meters)	Day	\$115.37	3	\$346.11	A
2 inch submersible pump	Day	\$61.84	3	\$185.52	A
5 kW Generator	Day	\$55.66	3	\$166.98	A
40 mL VOC vials	Each	\$1.53	20	\$30.60	A
1 L plastic metals bottle	Each	\$2.88	9	\$25.92	A
1 Gal. glass container	Each	\$9.59	17	\$163.03	A
1 7/8 inch teflon bailers	Each	\$48.23	10	\$482.30	A
48 qt. coolers (shipping)	Each	\$39.52	2	\$79.04	A
1/4 inch cotton rope	100 feet	\$10.70	3	\$32.10	B
				<u>\$1,511.60</u>	

Notes:
A: Environmental Restoration Assemblies/Unit Cost, Book
B: Hector's Hardware 2/96 rate

Assumptions:
1. 3-day rental (1 day each to mob, use, and demob except.)

2. 100' of 5/8" C-O-C forms, etc.
3. Assume 20% greater containers than will actually be needed to account for breakage/errors, etc...
4. Assume 8' rope needed per well to account for loss
5. 2 bailers per well to account for loss
6. 2 coolers needed for sample shipment

**DRHO YARD
MONITORING OF SOILS REMEDIATION
SAFETY EQUIPMENT COSTS**

	Unit	Unit Cost	Quantity	Cost	Source
Organic Vapor Analyzer	Day	\$123.68	3	\$371.04	A
Gas Monitor	Day	\$15.46	3	\$46.38	A
Tyvek Suit	Each	\$8.06	8	\$64.48	A
Reusable Butyl Outer Gloves	Pair	\$2.86	4	\$11.44	A
Latex Inner Gloves	Pair	\$0.30	16	\$4.80	A
Disposable Tyvek Boots	Pair	\$1.42	8	\$11.36	A
				\$509.50	

Notes: A: Environmental Restoration Assemblies/Unit Cost Book
1995-Environmental Cost Handling Options and Solutions

Assumptions:

1. 3-day rental (1 day each to mob, use, and demob. expt.)
2. One person work team
3. One full day of work
4. Each person to go through 4 tyvek suits per day
5. One pair each of outer gloves per person; and one extra pair per person in the event of tears/rips
6. Each person to go through 8 pairs of inner gloves per day
7. Each person has as part of their gear a full-face respirator, cartridges, a hard hat, leather steel-toed boots and safety glasses
8. Each person to go through 4 pairs of disposable boots per day

**DRDO YARD
MONITORING OF SOILS REMEDIATION**

SHIPPING COSTS	Unit	Unit Cost	Quantity	Cost
Sampling Equipment	lb.	\$1.50	300	\$450.00
Safety Equipment	lb.	\$1.50	100	\$150.00
Samples	lb.	\$1.50	150	\$225.00
				<u>\$825.00</u>

Notes: A: Federal Express 2/96 shipping rates

Assumptions:
1: Sampling equipment weighs 300 lbs.
2: Safety equipment weighs 100 lbs.
3: Samples weigh 150 lbs. When ready for shipment

DRUM YARD
MONITORING OF SOILS REMEDIATION

LABOR RATES FOR SAMPLE COLLECTION, DATA VALIDATION, SUMMARY REPORT, AND SITE EVALUATION

<u>SAMPLE COLLECTION</u>		Unit	Unit Cost	Quantity	Cost	Source
Health and Safety Officer	Hr.		\$18.55	12	\$222.60	A
Field Technician	Hr.		\$14.84	12	\$178.08	A
					<u>\$400.68</u>	
<u>DATA VALIDATION</u>						
Senior Chemist	Hr.		\$23.50	20	\$470.00	A
<u>SUMMARY REPORT</u>						
Staff Engineer	Hr.		\$23.50	20	\$470.00	A
Word Processing/Clerical	Hr.		\$12.37	10	\$123.70	A
					<u>\$593.70</u>	
<u>SITE EVALUATION</u>						
Senior Project Manager	Hr.		\$49.47	10	\$494.70	A
					<u>\$494.70</u>	

Notes:

A: 1995 Environmental Restoration Assemblies/Unit Cost Book
and Solutions

Assumptions:

1. Sample collection team members work a full 12 hour day by labor levels shown
2. Data validation requires 20 hours to complete by labor level shown
3. Summary report requires 10 hours to be written by labor level shown
4. Word processing and editing time by labor level shown
5. Site evaluation requires 10 hours to conduct by labor level shown

DRUM YARD
MONITORING OF SOILS REMEDIATION

TRAVEL EXPENSES	Unit	Quantity	Unit Cost	Cost	Source
Air Fare	Per Person	2	\$554.00	\$1,108.00	A
Meals	Per Person	2	\$30.00	\$60.00	B
Van Rental	Day	1	\$69.99	\$69.99	C
Fuel	Gal.	10	\$1.22	\$12.20	D
				<u>\$1,250.19</u>	

Notes:

- A: US Air 2/8/96 R/T air fare from Washington Int'l Airport to Logan Int'l
- B: Ecology & Environment 2/96 per diem (meals only) rate
- C: Hertz 2/8/96 7-passenger mini-van rate - pick up and drop off at Logan Int'l.
- D: Leominster, Mass. Shell Oil Gas 2/8/96 regular unleaded fuel rate

Assumptions:

- 1. 2-person work team
- 2. On site and depart from site same day
- 3. Use 1/6 gal. fuel

**DRUM YARD
MONITORING OF SOILS REMEDIATION**

SAMPLE ANALYTICAL COSTS

	Unit	Unit Cost	Quantity	Cost	Source
VOCS	Sample	\$324.66	16	\$5,194.56	A
PCBs/Pesticides	Sample	\$213.96	7	\$1,497.72	A
TAL Metals	Sample	\$290.64	14	\$4,068.96	A
				<u>\$10,761.24</u>	

Notes: A: 1995 Environmental Restoration Assemblies/Unit Cost Book Options and Solutions

Assumptions:

- 1: Unfiltered sample taken of each contaminant group per each of the 5 wells
- 2: 1 volt samples taken per each of the 5 wells
- 3: 1 duplicate sample taken of each contaminant group
- 4: Unfiltered sample taken of each metals
- 5: Rinsate blank taken of each contaminant group of the metals filter
- 6: Rinsate blank (VOCS only) taken of each contaminant group of the metals filter
- 7: Army Boes not require MSD samples to be taken
- 8: Each well has a dedicated bather, therefore, no rinsate on bather needed

B.2 DRMO YARD BACK-UP COST CALCULATIONS

ALTERNATIVE CAPITAL AND O&M COSTS

DRMO AREA - ALTERNATIVE 2: INSTITUTIONAL ACTIONS

CAPITAL COSTS	Unit	Unit Cost	Quantity	Cost	Source
MOBILIZATION COSTS	perper person	\$61.84	4	\$247.36	A
DEMobilIZATION COSTS	3% of capital costs		-	\$500.00	A
HEALTH AND SAFETY COSTS:					
Organic Vapor Analyzer	Day	\$123.68	5	\$618.40	A
Gas Monitor	Day	\$15.46	5	\$77.30	A
Tyvek Suit	Each	\$8.06	48	\$386.88	A
Reusable Butyl Outer Gloves	Pair	\$2.86	24	\$68.64	A
Latex Inner Gloves	Pair	\$0.30	96	\$28.80	A
Disposable Tyvek Boots	Pair	\$1.42	48	\$68.16	A
				<u>\$1,248.18</u>	
FENCE MOVING	Linear foot	\$14.55	840	\$12,222.00	B
ADDITION OF NEW FENCING	Linear foot	\$12.35	60	\$741.00	B
OPERATION AND MAINTENANCE COSTS					
FENCE MAINTENANCE	Linear Foot	\$12.60	50	\$630.00	

Notes: A: Environmental Restoration Assemblies/Unit Cost Book
 B: Means Site Work & Landscape Cost Data-1996-1997 Edition

Assumptions:

1. 5-day equipment rental (1 day to mobilize, 3 days to use, and 1 day to demobilize.)
2. 4 person work team for fence work (used to calculate mobilization and de-mobilization costs)
3. Each person to go through 4 tyvek suits per day
4. One pair of outer gloves per person per day; and one extra pair per person per day in the event of tears/rips
5. Each person to go through 8 pairs of inner gloves per day
6. Each person has as part of their gear a full-face respirator, cartridges, a hard hat, leather steel-toed boots and 200 feet of passes
7. Costs include replacing 200 feet of fencing semiannually
8. Assuming 3 days of initial site work
9. Each person to go through 4 pairs of disposable boots per day

DRMO AREA - ALTERNATIVE 3: CONTAINMENT VIA CAPPING

Capital Costs	Unit	Unit Cost	Quantity	Cost	Source
MOBILIZATION COSTS	per person				
DEMobilization COSTS	3% of capital costs				
HEALTH AND SAFETY COSTS:					
Organic Vapor Analyzer	Day	\$123.68	6	\$371.04	A
Gas Monitor	Month	\$309.20	-	\$12,635.70	A
Tyvek Suit	Each	\$8.06			
Reusable Butyl Outer Gloves	Pair	\$2.86	2160	\$7,409.60	A
Latex Inner Gloves	Pair	\$0.30	1080	\$3,088.80	A
Disposable Tyvek Boots	Pair	\$1.42	4320	\$1,296.00	A
			2160	\$3,067.20	A
				<u>\$36,920.40</u>	
SITE SERVICES:					
Survey	Day	\$789.71	5	\$3,948.55	A
Electric	KWH	\$0.06	900	\$55.62	A
Water	KGAL	\$6.18	27	\$166.97	A
Fuel (diesel)	Gal	\$1.24	12150	\$15,066.00	A
				<u>\$19,237.14</u>	
EXCAVATION, BACKFILL, AND CONSOLIDATION OF DITCHES:					
Excavation	CY	\$2.62	360	\$943.20	B
Backfill	CY	\$1.51	360	\$543.60	B
Consolidation	CY	\$5.25	360	\$1,890.00	B
				<u>\$3,376.80</u>	
TEMPORARY COVER:					
Reinforced Tarpaulin	SY	\$0.07	5425	\$379.75	B
CAP:					
Reggrading	SY	\$1.36	5425	\$7,378.00	B
18-inch clay layer	CY	\$16.10	2713	\$43,679.30	A
6-inch sand drainage layer	CY	\$9.79	904	\$88,850.16	A
6-inch topsoil	CY	\$24.71	904	\$22,337.84	A

DRMC AREA - ALTERNATIVE 3: CONTAINMENT VIA CAPPING (cont'd)

		Unit	Unit Cost	Quantity	Cost	Source
SEEDING (VEGETATIVE COVER)	Acre	\$1,488.73		1.13	\$1,682.26	A
RIP-RAP	CY	\$28.50		904	\$25,764.00	B
VERIFICATION SAMPLING:						
Sampling Equipment:						
Hand Auger	Day	\$59.07	5		\$295.35	
40 ml. glass vials	Each	\$1.53	256		\$391.68	A
8 oz. glass jar	Each	\$2.76	256		\$706.56	A
48 oz cooler (for shipping)	Each	\$39.52	8		\$316.16	A
Labor:						
Health and Safety Officer	Hr.	\$18.55	36		\$667.80	A
Field Technician	Hr.	\$14.84	36		\$534.24	A
Sample Shipment to Lab	lb.	\$1.50	600		\$900.00	A
					<u>\$3,811.79</u>	
VERIFICATION ANALYSIS:						
VOCs	Each	\$324.66	106		\$34,413.96	
TAL metals	Each	\$253.54	106		\$26,875.24	A
PCBs/Pesticides	Each	\$213.96	106		\$22,679.76	A
TCLP SAMPLING:					<u>\$83,968.96</u>	
Sampling Equipment:						
Hand Auger	Day	\$59.07	5		\$295.35	
40 ml. glass vials	Each	\$1.53	256		\$391.68	A
8 oz. glass jar	Each	\$2.76	256		\$706.56	A
48 oz cooler (for shipping)	Each	\$39.52	8		\$316.16	A
Labor:						
Health and Safety Officer	Hr.	\$18.55	36		\$667.80	A
Field Technician	Hr.	\$14.84	36		\$534.24	A
Sample Shipment to Lab	lb.	\$1.50	600		\$900.00	A
					<u>\$3,811.79</u>	

DRMO AREA - ALTERNATIVE 3: CONTAINMENT VIA CAPPING (cont'd)

	Unit	Unit Cost	Quantity	Cost	Source
TCLP ANALYSIS:					
TCLP VOCs, Metals	Each	\$866.37	106	\$91,835.22	A
FENCE MOVING	Linear foot	\$14.55	840	\$12,222.00	B
ADDITION OF NEW FENCING	Linear foot	\$12.35	60	\$741.00	B
OPERATION AND MAINTENENCE:					
Fence	Linear foot	\$12.60	50	\$630.00	B
Cap:					
Mowing	Acre	\$21.47	1.13	\$24.26	A
Re-seeding	Acre	\$1,436.07	0.1	\$143.61	A
Replace topsoil	cy	\$22.67	90	\$2,040.30	A
Replace Rip-Rap	cy	\$21.97	90	\$1,977.30	A
				\$4,185.47	

Notes:
 A: Environmental Assemblies/Unit Cost Book
 B: Means Site Work & Landscape Cost Data- 1996- 15th Edition

Assumptions:

1. 90 days of site work
2. 6-member team for excavation/capping work
3. member survey team
4. 3 days of survey work
5. 3 days of year round sampling work
6. 90-hour work days
7. 10-hour work days
8. 90-day safety equipment rental
9. Each person to go through 4 tyvek suits per day
10. One pair of outer gloves per person per day; and one extra pair of each other day per person in the event of tears/rips
11. Each person to go through 8 pairs of inner gloves per day
12. Each person as part of their gear has a full-face respirator, cartridges, a hard hat, together with steel-toed boots and safety glasses
13. Using 700 kg of water (300 gal/day for 90 days)
14. Using 12150 gal of diesel fuel (135 gallons/day for 90 days)
15. Soak of capping materials obtained from on site stockpile
16. Backfill material obtained from on site stockpile
17. 1-day sampling equipment rental (1 day to mobilize, 3 days to use 1 day to demobilize)
18. VOC samples taken for each verification sampling and TCLP sampling location
19. metals samples taken for each verification sampling and TCLP sampling location
20. specific PCB sample taken for each verification sampling and TCLP sampling location
21. duplicate samples taken of each contaminant group for verification and TCLP sampling
22. rinsate blank sample taken of each auger for each contaminant group for verification and TCLP sampling

DRMO AREA - ALTERNATIVE 3: CONTAINMENT VIA CAPPING (cont'd)

26. Army does not require MS/MSD samples to be taken
27. 1 member team for verification and TCLP sampling work
28. 100 verification and TCLP sampling work
29. 2 jars required for each VOC sample; 1 jar required for each metals sample; location and 1 jar required for each metals sample with an additional 20% required for each PCB/pesticide sample; location for verification and TCLP sampling with an additional 20% added in the event of breakage/reampling
30. 8 coolers needed to ship verification samples; 8 needed to ship TCLP samples
31. No soil samples for TCLP tests
32. No soil samples for verification tests
33. 1000 linear feet of fence required annually
34. 1000 linear feet of rip-rap required annually
35. 1000 linear feet of rip-rap replacement annually
36. Each person to go through 4 pair of disposable boots per day

DRMO AREA - ALTERNATIVE 4: EXCAVATION, SOLIDIFICATION, AND ON-SITE DISPOSAL

Capital Costs	Unit	Unit Cost	Quantity	Cost	Source
MOBILIZATION COSTS	per person	\$61.84	6	\$371.04	A
DEMOBILIZATION COSTS	3% capital costs		-	\$14,094.00	A
HEALTH AND SAFETY COSTS:					
Organic Vapor Analyzer	Day	\$125.68	120	\$14,841.60	A
Gas Monitor	Month	\$309.20	4	\$1,236.80	A
Tyvek Suit	Each	\$8.06	2880	\$23,212.80	A
Reusable Butyl Outer Gloves	Pair	\$2.86	1440	\$34,118.40	A
Latex Inner Gloves	Pair	\$0.30	5760	\$1,728.00	A
Disposable Tyvek Boots	Pair	\$1.42	2880	\$4,089.60	A
				<u>\$49,227.20</u>	
SITE SERVICES:					
Survey	Day	\$789.71	5	\$3,948.55	A
Electric	KWH	\$0.06	1200	\$74.16	A
Water	KGAL	\$6.18	36	\$222.62	A
Fuel (diesel)	Gal	\$1.24	16200	\$20,088.00	A
				<u>\$26,333.33</u>	
SOIL EXCAVATION					
ADDITIONAL EXCAVATION	CY	\$2.62	1300	\$3,406.00	B
BACKFILL	CY	2.62	325	\$851.50	B
	CY	\$1.51	1300	\$1,963.00	B
BACKFILL AND COCOMPACTATION OF TREATED SOILS:					
Backfill	CY	\$1.51	1625	\$2,453.75	B
Compaction	CY	\$3.49	1625	\$5,671.25	B
				<u>\$8,125.00</u>	
GRADING	SY	\$1.36	3940	\$5,358.40	B
SOIL HANDLING/LOADING	SY	\$1.38	1300	\$1,794.00	A
TEMPORARY COVER:					
Reinforced Tarpaulin	SY	\$0.07	3940	\$275.80	

DRMO AREA - ALTERNATIVE 4:	EXCAVATION, SOLIDIFICATION, AND ON-SITE DISPOSAL (cont'd)	Unit	Unit Cost	Quantity	Cost	Source
6-INCH TOPSOIL SEEDING (VEGETATIVE COVER)	CY Acre		\$24.71 \$1,488.73	660 0.81	\$16,308.60 \$1,205.87	A A
VERIFICATION SAMPLING:						
Sampling Equipment:						
Hand Auger	Day	\$59.07		5	\$295.35	A
40 ml. glass vials	Each	\$1.53		256	\$391.68	A
8 oz. glass jar	Each	\$2.76		256	\$706.56	A
48 oz. cooler (for shipping)	Each	\$39.52		8	\$316.16	A
Labor:						
Health and Safety Officer	Hr.	\$18.55		36	\$667.80	A
Field Technician	Hr.	\$14.84		36	\$534.24	A
Sample Shipment to Lab	lb.	\$1.50		600	\$900.00	A
					<hr/>	
					\$3,811.79	
VERIFICATION ANALYSIS:						
VOCs	Each	\$324.66		106	\$34,413.96	A
TAL metals	Each	\$253.54		106	\$26,875.24	A
PCBs/Pesticides	Each	\$213.96		106	\$22,679.76	A
					<hr/>	
					\$83,968.96	

DRMO AREA - ALTERNATIVE 4:	EXCAVATION, SOLIDIFICATION, AND ON-SITE DISPOSAL (cont'd)	Unit	Unit Cost	Quantity	Cost	Source
TCLP SAMPLING:						
Sampling Equipment:						
Hand Auger	Day	\$50.07	5		\$295.35	A
40 ml. glass vials	Each	\$1.53	256		\$391.68	A
8 oz. glass jar	Each	\$2.76	256		\$706.56	A
48 oz cooler (for shipping)	Each	\$39.52	8		\$316.16	A
Labor:						
Health and Safety Officer	Hr.	\$18.55	36		\$667.80	A
Field Technician	Hr.	\$16.84	36		\$534.24	A
Sample Shipment to Lab	lb.	\$1.50	600		\$900.00	A
					<u>\$3,811.79</u>	
TCLP ANALYSIS:						
TCLP VOCs, Metals	Each	\$866.37	106		\$91,835.22	A
	CY	\$0.87	1300		\$1,131.00	A
TRANSPORTATION						
TREATMENT:						
Portland cement	Ton	\$68.02	423		\$28,772.46	A
Labor	Hr.	\$37.72	300		\$11,316.00	A
100 CY bulk mixing system	Mo.	\$12,023.82	1		\$12,023.82	A
Ancillary equipment	Lump sum	\$7,420.69	1		\$7,420.69	A
Mobilization/demobilization	Lump sum	\$12,259.60	1		\$12,259.60	A
Equipment/system maintenance	Mo.	\$446.38	1		\$446.38	A
					<u>\$72,238.95</u>	

Notes:

A: 1995- Environmental Assemblies Cos/Unit Cost Book and Solutions
 B: Means Site Work & Landscape Cost Data- 1996- 15th Edition

DRIVE AREA - ALTERNATIVE 4: EXCAVATION, SOLIDIFICATION, AND ON-SITE DISPOSAL (cont'd)

Assumptions:

DRMO AREA - ALTERNATIVE 6: EXCAVATION AND OFF-SITE DISPOSAL

CAPITAL COSTS		Unit	Unit Cost	Quantity	Cost	Source
MOBILIZATION COSTS		per person	\$61.84	4	\$247.36	A
DEMobilIZATION COSTS		3% of capital costs		-	\$14,120.00	A
HEALTH AND SAFETY COSTS:						
Organic Vapor Analyzer	Day	\$123.68		60	\$7,420.80	A
Gas Monitor	Month	\$309.20		2	\$618.40	A
Tyvek Suit	Each	\$8.06		960	\$7,737.60	A
Reusable Butyl Outer Gloves	Pair	\$2.86		480	\$1,372.80	A
Latex Inner Gloves	Pair	\$0.30		1920	\$576.00	A
Disposable Tyvek Boots	Pair	\$1.42		960	\$1,363.20	A
					<u>\$19,088.80</u>	
SITE SERVICES:						
Survey	Day	\$789.71		5	\$3,948.55	A
Electric	KWH	\$0.06		600	\$37.08	A
Water	KGAL	\$6.18		18	\$111.31	A
Fuel (diesel)	Gal	\$1.24		8100	\$10,044.00	A
					<u>\$14,140.94</u>	
SOIL EXCAVATION		CY	\$2.62	1300	\$3,406.00	B
BACKFILL AND COMPACTION:						
Backfill	CY	\$1.51		1300	\$1,963.00	B
Compaction	CY	\$3.49		1300	\$4,537.00	B
SOIL HANDLING/LOADING						
Temporary Cover:	SY	\$0.07		3940	\$275.30	B
Reinforced Tarpaulin	CY	\$24.71		660	\$16,308.60	A
6-INCH TOPSOIL	Acre	\$1,488.73		0.81	\$1,205.87	A
SEEDING (VEGETATIVE COVER)						

DRMO AREA - ALTERNATIVE 6: EXCAVATION AND OFF-SITE DISPOSAL (cont'd)

	Quantity	Unit Cost	Cost	Source
VERIFICATION SAMPLING:				
Sampling Equipment:				
Hand Auger	Day	\$59.07	\$295.35	A
40 ml. glass vials	Each	\$1.53	\$391.68	A
8 oz. glass jar	Each	\$2.76	\$706.56	A
48 oz cooler (for shipping)	Each	\$39.52	\$316.16	A
Labor:				
Health and Safety Officer	Hr.	\$18.55	\$667.80	A
Field Technician	Hr.	\$14.84	\$534.24	A
Sample Shipment to Lab	lb.	\$1.50	\$900.00	A
			<u>\$3,811.79</u>	
VERIFICATION ANALYSIS:				
VOCs	Each	\$324.66	\$34,413.96	A
TAL metals	Each	\$253.54	\$26,875.24	A
PCBs/Pesticides	Each	\$213.96	\$22,679.76	A
			<u>\$83,968.96</u>	
TCLP SAMPLING:				
Sampling Equipment:				
Hand Auger	Day	\$59.07	\$295.35	A
40 ml. glass vials	Each	\$1.53	\$391.68	A
8 oz. glass jar	Each	\$2.76	\$706.56	A
48 oz cooler (for shipping)	Each	\$39.52	\$316.16	A
Labor:				
Health and Safety Officer	Hr.	\$18.55	\$667.80	A
Field Technician	Hr.	\$14.84	\$534.24	A
Sample Shipment to Lab	lb.	\$1.50	\$900.00	A
			<u>\$3,811.79</u>	

DRUMM AREA - ALTERNATIVE 6: EXCAVATION AND OFF-SITE DISPOSAL (cont'd)

TCPL ANALYSIS:			
TCPL Vocs, Metals			
TRANSPORTATION			
Unit	Unit Cost	Quantity	Cost
Each	\$866.37	106	\$91,835.22
Dump truck	\$883.63	70	\$47,854.10
cy	\$111.31	1300	\$144,703.00

Notes


A: Environmental Assemblies/Unit Cost Book

88: Means Site Hook & Line Success Rate 100% - 15th Edition

Assumptions:

B.3 UST-13 GROUNDWATER AREA BACK-UP COST CALCULATIONS

MONITORING COSTS



UST-13 AREA 1: NO FURTHER ACTION

LABOR RATES FOR SAMPLE COLLECTION, DATA VALIDATION, SUMMARY REPORT, AND SITE EVALUATION

SAMPLE COLLECTION	Unit	Unit Cost	Quantity	Cost	Source
Health and Safety Officer	Hr.	\$18.55	12	\$222.60	A
Field Technician	Hr.	\$14.84	12	\$178.08	A
				<u>\$400.68</u>	
DATA VALIDATION					
Senior Chemist	Hr.	\$23.50	16	\$376.00	A
SUMMARY REPORT					
Staff Engineer	Hr.	\$23.50	20	\$470.00	A
Word Processing/Clerical	Hr.	\$12.37	10	\$123.70	A
				<u>\$593.70</u>	
SITE EVALUATION					
Senior Project Manager	Hr.	\$49.47	8	\$395.76	A

Notes:

A: Environmental Restoration Assemblies/Unit Cost Book
B-95-Environmental Cost Handling Options and Solutions

Assumptions:

- 1: Sample collection team members work a full 12 hour day by labor levels shown
- 2: Data validation requires 16 hours to complete by labor level shown
- 3: Summary report requires 20 hours to be written by labor level shown
- 4: Summary report requires 10 hours of word processing and editing time by labor level shown
- 5: Site evaluation requires 10 hours to conduct by labor level shown

UST-13 AREA 1: NO FURTHER ACTION

SAMPLE ANALYTICAL COSTS		Unit	Unit Cost	Quantity	Cost	Source
VOCS	Sample		\$324.66	14	\$4,545.24	A
PCBs/Pesticides	Sample		\$213.96	6	\$1,283.76	A
TAL Metals	Sample		\$290.64	12	\$3,487.68	A
					<u>\$9,316.68</u>	

Notes: A: Environmental Restoration Assemblies/Unit: Cost Book:
B: Environmental Cost Handling Options and Solutions

Assumptions:

1. 1 unfiltered sample taken of each contaminant group per each of the 5 wells
2. VOC samples taken per each of the 5 wells
3. Unfilled duplicate sample taken of each contaminant group
4. Filtered sample taken of TAL metals
5. Rinse tank taken of each contaminant group of the metals filter
6. Army Corps blank (VOCs only) taken
7. Army Corps not required to take samples to be taken
8. Each well has a dedicated bather, therefore, no rinse on bather needed

WST-13 AREA 1: NO FURTHER ACTION

TRAVEL EXPENSES

	Unit	Unit Cost	Quantity	Cost	Source
Air Fare	Per Person	\$554.00	2	\$1,108.00	A
Meals	Per Person	\$30.00	2	\$60.00	B
Van Rental	Day	\$69.99	1	\$69.99	C
Fuel	Gal.	\$1.22	10	\$12.20	D
				<u>\$1,250.19</u>	

Notes:

- A: US Air 2/8/96 R/T air fare from Washington Int'l Airport to Logan Int'l
- B: Ecology & Environment 2/96 per diem (meals only) rate
- C: Hertz 2/8/96 7-passenger mini-van rate - pick up and drop off at Logan Int'l.
- D: Leominster, Mass. Shell Oil Gas 2/8/96 regular unleaded fuel rate

Assumptions:

- 1. 2-person work team
- 2. Arrive and depart from site same day
- 3. Use 10 gal. fuel

UST-13 AREA 1: NO FURTHER ACTION

SHIPPING COSTS	Unit	Unit Cost	Quantity	Cost
Sampling Equipment	lb.	\$1.50	290	\$435.00
Safety Equipment	lb.	\$1.50	100	\$150.00
Samples	lb.	\$1.50	130	\$195.00
				<hr/> <u>\$780.00</u>

Notes: A: Federal Express 2/96 shipping rates

Assumptions:
1. Sampling equipment weighs 290 lbs.
2. Safety equipment weighs 100 lbs.
3. Samples weigh 130 lbs. when ready for shipment

UST-13 AREA
ALTERNATIVE 1: NO FURTHER ACTION

SAFETY EQUIPMENT COSTS

	Unit	Unit Cost	Quantity	Cost	Source
Organic Vapor Analyzer	Day	\$123.68	3	\$371.04	A
Gas Monitor	Day	\$15.46	3	\$46.38	A
Tyek Suit	Each	\$8.06	8	\$64.48	A
Reusable Butyl Outer Gloves	Pair	\$2.86	4	\$11.44	A
Latex Inner Gloves	Pair	\$0.30	16	\$4.80	A
Disposable Tyek Boots	Pair	\$1.42	8	\$11.36	A
				<u>\$509.50</u>	

Notes: A: Environmental Restoration Assemblies/Unit Cost Book Options

Assumptions:

1. 3-day rental (1 day each to mob, use, and demob. except.)
2. One full day of work
3. Each person to go through 4 tyvek suits per day
4. One pair each of outer gloves per person; and one extra pair per person in the event of tears/rips
5. Each person to go through 8 pair of inner gloves per day
6. Each person has as part of their gear a full-face respirator, cartridges, a hard hat, leather steel-toed boots and safety glasses
7. Each person to go through 4 pair of disposable boots per day
8. Each person to go through 4 pair of disposable boots per day

UST-13 AREA 1: NO FURTHER ACTION

SAMPLING EQUIPMENT COSTS

	Unit	Unit Cost	Quantity	Cost	Source
Well Development Equipment Rental (pH, Temp, Conductivity, Turbidity meters)	Day	\$115.37	3	\$346.11	A
2 inch submersible pump	Day	\$61.84	3	\$185.52	A
5 kW Generator	Day	\$55.66	3	\$166.98	A
40 ml. VOC vials	Each	\$1.53	17	\$26.01	A
1 L plastic metals bottle	Each	\$2.88	8	\$23.04	A
1 Gal. glass container	Each	\$9.59	15	\$143.85	A
1 7/8 inch teflon bailers	Each	\$48.23	8	\$385.84	A
48 Qt. coolers (shipping)	Each	\$39.52	2	\$79.04	A
1/4 inch cotton rope	100 feet	\$10.70	2	\$21.40	B
				<u>\$1,377.79</u>	

Notes: A: Environmental Restoration Assemblies/unit Cost Book
 B: 1985 Environmental Cost Handling Options and Solutions
 B: Hector's Hardware 2/86 rate

Assumptions:

- 1: 3 day rental (1 day each to mob, use, and demob eqpt.)
- 2: Labels 50-C forms, etc. inc. with bottles (containers)
- 3: Assumes 20% greater containers than will actually be needed to account for breakage/errors, etc...
- 4: 50 feet of rope needed per well
- 5: Assumes 2 bailers per well to account for loss
- 6: 2 coolers needed for sample shipment

UST-13 AREA 76, INSTITUTIONAL CONTROLS
YEARS 0, 5, 10, 15, 20, 25, 30

LABOR RATES FOR SAMPLE COLLECTION, DATA VALIDATION, SUMMARY REPORT, AND SITE EVALUATION

SAMPLE COLLECTION	Unit	Unit Cost	Quantity	Cost	Source
Health and Safety Officer	Hr.	\$18.55	12	\$222.60	A
Field Technician	Hr.	\$14.84	12	\$178.08	A
<hr/>					
DATA VALIDATION					
Senior Chemist	Hr.	\$23.50	16	\$376.00	A
<hr/>					
SUMMARY REPORT					
Staff Engineer	Hr.	\$23.50	20	\$470.00	A
Word Processing/Clerical	Hr.	\$12.37	10	\$123.70	A
<hr/>					
SITE EVALUATION					
Senior Project Manager	Hr.	\$49.47	8	\$395.76	A
<hr/>					

Notes:

A: Environmental Restoration Assemblies/Unit Cost Book

Assumptions: 1: Sample collection team members work a full 12 hour day by labor levels shown

- 2: Data validation requires 10 hours to complete by labor level shown
- 3: Summary report requires 10 hours to be written by labor level shown
- 4: Word processing and editing time by labor level shown
- 5: Site evaluation requires 10 hours to conduct by labor level shown

UST-13 AREA
YEARS 0, 5, 10, 15, 20, 25, 30
INSTITUTIONAL CONTROLS
SAMPLING EQUIPMENT COSTS

Well Development Equipment Rental (pH, Temp, Conductivity, Turbidity meters)	Unit	Unit Cost	Quantity	Cost	Source
2 inch submersible pump	Day	\$115.37	3	\$346.11	A
5 kW Generator	Day	\$61.84	3	\$185.52	A
40 mL VOC vials	Day	\$55.66	3	\$166.98	A
1 L plastic metals bottle	Each	\$1.53	17	\$26.01	A
1 Gal. glass container	Each	\$2.88	8	\$23.04	A
1 7/8 inch teflon bailers	Each	\$9.59	15	\$143.85	A
48 qt. coolers (shipping)	Each	\$48.23	8	\$385.84	A
1/4 inch cotton rope	100 feet	\$39.52	2	\$79.04	A
		\$10.70	2	\$21.40	B
				<u>\$1,377.79</u>	

Notes:

A: Environmental Restoration Assemblies/Unit Cost Book
B: 1995- Environmental Cost Handling Options and Solutions
B: Hector's Hardware 2/88 Rate

Assumptions:

- 1: 3-day rental (1 day each to mob, use, and demob eqpt.)
- 2: Labels 100-C forms, etc. incl. with bottles/containers
- 3: Assumes 20% greater containers than will actually be needed to account for breakage/errors, etc...
- 4: 20 feet of rope needed per well
- 5: Assumes 2 bailers per well to account for loss
- 6: 2 coolers needed for sample shipment

UST 13 AREA
YEARS 0, 5, 10, 15, 20, 25, 30
SAFETY EQUIPMENT COSTS

recycled paper

	Unit	Unit Cost	Quantity	Cost	Source
Organic Vapor Analyzer	Day	\$123.68	3	\$371.04	A
Gas Monitor	Day	\$15.46	3	\$46.38	A
Tyvek Suit	Each	\$8.06	8	\$64.48	A
Reusable Butyl Outer Gloves	Pair	\$2.86	4	\$11.44	A
Latex Inner Gloves	Pair	\$0.30	16	\$4.80	A
Disposable Tyvek Boots	Pair	\$1.42	8	\$11.36	A
				<u>\$509.50</u>	

Notes:

A: Environmental Restoration Assembly/Unit Cost Book

B: Environmental Cost Handling Options and Solutions

Assumptions:

1. 3-day rental (1 day each to mob, use, and demob. expt.)
2. 2-person work team
3. One full day of work
4. Each person to go through 4 tyvek suits per day
5. One pair of outer gloves per person, and one extra pair per person in the event of a break
6. Each person to go through 8 pairs of inner gloves per day
7. Each person has as part of the gear a full-face respirator, cartridges, a hard hat, leather steel-toed boots and safety glasses
8. Each person to go through 4 pair of disposable boots per day

UST-13 AREA 26, INSTITUTIONAL CONTROLS
YEARS 0, 5, 10, 15, 20, 25, 30

SHIPPING COSTS	Unit	Unit Cost	Quantity	Cost
Sampling Equipment	lb.	\$1.50	290	\$435.00
Safety Equipment	lb.	\$1.50	100	\$150.00
Samples	lb.	\$1.50	130	\$195.00
				<hr/> \$780.00

Notes: A: Federal Express 2/96 shipping rates

Assumptions:

1. Sampling equipment weighs 290 lbs.
2. Safety equipment weighs 100 lbs.
3. Samples weigh 130 lbs. When ready for shipment

UST-13 AREA
WESTERN
YEARS 0, 5, 10, 15, 20, 25, 30
INSTITUTIONAL CONTROLS

TRAVEL EXPENSES

	Unit	Unit Cost	Quantity	Cost	Source
Air Fare	Per Person	\$554.00	2	\$1,108.00	A
Meals	Per Person	\$30.00	2	\$60.00	B
Van Rental	Day	\$69.99	1	\$69.99	C
Fuel	Gal.	\$1.22	10	\$12.20	D
				<u>\$1,250.19</u>	

Notes:

- A: US Air 2/8/96 R/T air fare from Washington Int'l Airport to Logan Int'l
- B: Ecology & Environment 2/96 per diem (meals only) rate
- C: Hertz 2/8/96 7-passenger mini-van rate - pick up and drop off at Logan Int'l.
- D: Leominster, Mass. Shell Oil Gas 2/8/96 regular unleaded fuel rate

Assumptions:

- 1. 2-person work team
- 2. Arrive and depart from site same day
- 3. Use 10 gal. fuel

UST-13 AREA
YEARS 0, 5, 10, 15, 20, 25, 30
SAMPLE ANALYTICAL COSTS

	Unit	Unit Cost	Quantity	Cost	Source
VOCs	Sample	\$324.66	14	\$4,545.24	A
PCBs/Pesticides	Sample	\$213.96	6	\$1,283.76	A
TAL Metals	Sample	\$290.64	12	\$3,487.68	A
				<u>\$9,316.68</u>	

Notes: A: Environmental Restoration Assemblies/Unit Cost Book
B: Environmental Cost Handling Options and Solutions

Assumptions:

- 1: Unfiltered sample taken of each contaminant group per each of the 5 wells
- 2: VOC samples taken per each of the 5 wells the duplicate and the blanks
- 3: Unfiltered duplicate sample taken of each contaminant group
- 4: Filtered sample taken of TAL metals
- 5: Rinsate sample taken of each contaminant group of the metals filter
- 6: Blank (VOCs only) taken
- 7: Army does not require MS/MSD samples to be taken
- 8: Each well has a dedicated bather, therefore, no rinsate on bather needed

UST 13 (AOC 32) GROUNDWATER
YEAR

SAMPLING EQUIPMENT COSTS

	Unit	Unit Cost	Quantity	Cost	Source
Teflon tubing	Linear Foot	\$1.73	120	\$207.60	A
Well Development Equipment Rental (pH, Temp, Conductivity, O ₂ meter, Redox)	Day	\$115.37	4	\$461.48	B
Peristaltic pump	Day	\$61.84	4	\$247.36	B
5 kW generator	Day	\$55.66	4	\$222.64	B
40 mL VOC vials	Each	\$1.53	26	\$39.78	B
1 L plastic metals bottle	Each	\$2.88	55	\$158.40	B
1 L glass container	Each	\$9.59	12	\$115.08	B
48 Qt. coolers (shipping)	Each	\$39.52	6	\$237.12	B
Filter (barrel/pressure)	Day	\$15.00	3	\$45.00	C
				<u>\$1,734.46</u>	

WELL INSTALLATION

	Unit	Unit Cost	Quantity	Cost	Source
	Each	\$1,955.00	3	\$5,865.00	D

Notes:

A: Environmental Restoration Assemblies/Unit Cost Book
1986. Environmental Cost Handling Options and Solutions
B: Environmental Restoration Assemblies/Unit Cost Book
1986. Environmental Cost Handling Options and Solutions
C: Ecology & Environmental Cost Handling Options and Solutions
D: Competitive bids for similar wells in New York State

Assumptions:

- 1: 2-day rental (1 day to mob and demob equipment, 3 days field use)
- 2: Label's 50-c forms, etc. inc. with bottles/containers
- 3: Assumes 20% greater containers than will actually be needed to account for breakage/errors, etc...
- 4: ten coolers for sample shipment.

UST 13 (AOC 322) GROUNDWATER
INSTRUMENTATION 2.5 YEARS

SAMPLING EQUIPMENT COSTS		Unit	Unit Cost	Quantity	Cost	Source
Teflon tubing	Linear Foot	\$1.73	120		\$207.60	A
Well Development Equipment Rental (pH, Temp, Conductivity, O ₂ meter, Redox)	Day	\$115.37	4		\$461.48	B
Peristaltic pump	Day	\$61.84	4		\$247.36	B
5 kW Generator	Day	\$55.66	4		\$222.64	B
40 mL VOC vials	Each	\$1.53	26		\$39.78	B
1 L plastic metals bottle	Each	\$2.88	55		\$158.40	B
1 L glass container	Each	\$9.59	12		\$115.08	B
48 qt. coolers (shipping)	Each	\$39.52	6		\$237.12	B
Filter (barrel/pressure)	Day	\$15.00	3		\$45.00	C
TOTAL SAMPLING EQUIPMENT COSTS YEARS 2 - 5					\$1,734.46	

Notes:

- A: EDO 1996 Environmental Restoration Assemblies/Unit Cost Book
- B: EDO 1996 Environmental Restoration Options and Solutions
- C: EDO 1996 Environmental Restoration Assemblies/Unit Cost Book
- C: Ecology & Environment, Inc. 1996 Options and Solutions

Assumptions:

- 1: 5-day rental (1 day to mob and demob equipment with Bottles/3 days field use)
- 2: label's C-O-C forms etc.
- 3: ten coolers needed for sample shipment.

UST 13 (AOC 32) GROUNDWATER
INTRINSIC REMEDIATION
YEARS 1 - 5

TRAVEL EXPENSES		Unit	Unit Cost	Quantity	Cost	Source
Air Fare	Per Person		\$554.00	2	\$1,108.00	A
Meals	Per Person		\$30.00	6	\$180.00	B
Van Rental	Day		\$69.99	3	\$209.97	C
Fuel	Gal.		\$1.22	20	\$24.40	D
Lodging	day/person		\$48.00	6	\$288.00	E
TOTAL TRAVEL YEARS 1 - 5					\$1,810.37	

Notes:

- A: US Air 2/8/96 R/T air fare from Washington Int'l Airport to Logan Int'l
- B: Ecology & Environment 2/96 per diem (meals only) rate
- C: Hertz 2/8/96 7-passenger mini-van rate - pick up and drop off at Logan Int'l.
- D: Leominster, Mass. Shell Oil Gas 2/8/96 regular unleaded fuel rate
- E: Holiday Inn, Leominster, MA, 2/96 quote

Assumptions:

1. 2-person work team
2. Half-day mob and half-day demob, 2 days on-site

UST 13 (AOC 32) GROUNDWATER
INTRINSIC REMEDIATION
YEARS 1 - 5

SHIPPING COSTS	Unit	Unit Cost	Quantity	Cost	Source
Sampling Equipment	lb.	\$1.50	290	\$435.00	A
Safety Equipment	lb.	\$1.50	100	\$150.00	A
Samples	lb.	\$1.50	360	\$540.00	A
TOTAL SHIPPING YEARS 1 - 5					\$1,560.00

Notes: A: Federal Express 2/96 shipping rates

Assumptions:
1: Sampling equipment weighs 290 lbs.
2: Safety equipment weighs 100 lbs.
3: Samples weigh 650 lbs. when ready for shipment

UST 13 (AOC 322) GROUNDWATER
INSTRINSIC REMEDIATION

YEARS 1 - 5

SAFETY EQUIPMENT COSTS

	Unit	Unit Cost	Quantity	Cost	Source
Organic Vapor Analyzer	Day	\$123.68	4	\$494.72	A
Gas Monitor	Day	\$15.46	4	\$61.84	A
Tyvek Suit	Each	\$8.06	10	\$80.60	A
Reusable Butyl Outer Gloves	Pair	\$2.86	6	\$17.16	A
Latex Inner Gloves	Pair	\$0.30	20	\$6.00	A
Disposable Tyvek Boots	Pair	\$1.42	10	\$14.20	A
TOTAL SAFETY EQUIPMENT COSTS YEARS 1 - 5				\$674.52	

Notes:

A: 1995 Environmental Restoration Assemblies/Unit Cost Book

Assumptions: 1. Each person has as part of their gear a full-face respirator, cartridges, hard hat, leather steel-toed boots, and safety glasses

UST 13 (OC 32) GROUNDWATER
INTRINSIC REMEDIATION

YEARS 1 - 5

SAMPLE ANALYTICAL COSTS

	Unit	Unit Cost	Quantity	Cost	Source
Nitrate	Sample	\$35.68	11	\$392.48	A
Nitrite	Sample	\$35.68	11	\$392.48	A
Phosphate	Sample	\$29.73	11	\$327.03	A
Sulfate	Sample	\$14.27	11	\$156.97	A
Sulfide	Sample	\$55.90	11	\$614.90	A
Total Iron	Sample	\$20.00	11	\$220.00	B
Soluble Iron (ferric)	Sample	\$20.00	11	\$220.00	B
BTEX Volatiles	Sample	\$89.19	12	\$1,070.28	A
As, Fe, Mn (filtered)	Sample	\$150.00	11	\$1,650.00	B
Alkalinity	Sample	\$21.40	11	\$235.40	A
Ammonia-Nitrogen	Sample	\$41.63	11	\$457.93	A
TPHC	Sample	\$112.98	11	\$1,242.78	A
TOTAL ANALYTICAL YEARS 1 - 5				\$6,980.25	

Notes:

A: Environmental Restoration Assemblies/Unit Cost Book
1996-Environmental Cost Handling Options and Solutions
B: Ecology & Environment, Inc. 1996

Assumptions:

- 1: Total iron is unfiltered. Iron is filtered.
- 2: Ferric (soluble) iron and manganese are filtered.
- 3: Filtered arsenic, iron and manganese are filtered.
- 4: All other samples are filtered.
- 5: Disposable tubing is used for collection.
- 6: Only one triplicate BTEX VOA is taken.
- 7: One duplicate is taken + matrix spike and MS duplicate.
- 8: Assume USEPA protocols not USAEC.

US EPA 13 (AOC 32) GROUNDWATER
WATER ASSESSMENT/C REDICTION

YEAR 1
Recycled paper

LABOR RATES FOR SAMPLE COLLECTION, DATA VALIDATION, SUMMARY REPORT, AND SITE EVALUATION/GROUNDWATER MODEL

SAMPLE COLLECTION		Unit	Unit Cost	Quantity	Cost	Source
Health and Safety Officer	Hr.	\$18.55	24	\$445.20	A	
Field Technician	Hr.	\$14.84	24	\$356.16	A	
				<u>\$801.36</u>		
DATA VALIDATION						
Senior Chemist	Hr.	\$23.50	16	\$376.00	A	
SUMMARY REPORT						
Project Hydrogeologist	Hr.	\$29.74	48	\$1,427.52	B	
Staff Engineer	Hr.	\$23.50	48	\$1,128.00	A	
Word Processing/Clerical	Hr.	\$12.37	16	\$197.92	A	
				<u>\$2,753.44</u>		
Site Evaluation/Groundwater Model/Well Installation						
Senior Project Manager	Hr.	\$49.47	40	\$1,978.80	A	
Senior Project Hydrogeologist	Hr.	\$41.63	320	\$13,321.60	B	
Project Hydrogeologist	Hr.	\$29.74	480	\$14,275.20	B	
				<u>\$29,575.60</u>		
TOTAL LABOR YEAR 1						
				<u>\$33,506.40</u>		

ecology and environment
TOTAL LABOR YEAR 1

Notes:

A: EPA Environmental Restoration Assemblies/Unit Cost Book
B: EPA Environmental Restoration Assemblies/Unit Cost Book
Assumptions: Sample collection team members work 12-hour days.

UST 13 (AOC 322) GROUNDWATER
INSTRUMENT REMEDIATION
YEARS 2 - 4

LABOR RATES FOR SAMPLE COLLECTION, DATA VALIDATION, SUMMARY REPORT, AND SITE EVALUATION

	Unit	Unit Cost	Quantity	Cost	Source
SAMPLE COLLECTION					
Health and Safety Officer	Hr.	\$18.55	24	\$445.20	A
Field Technician	Hr.	\$14.84	24	\$356.16	A
				<u>\$801.36</u>	
DATA VALIDATION					
Senior Chemist	Hr.	\$23.50	16	\$376.00	A
				<u>\$376.00</u>	
SUMMARY REPORT					
Project Hydrogeologist	Hr.	\$29.74	16	\$475.84	B
Staff Engineer	Hr.	\$23.50	16	\$376.00	A
Word Processing/Clerical	Hr.	\$12.37	12	\$148.44	A
				<u>\$1,000.28</u>	
Site Evaluation/Groundwater Model					
Senior Project Manager	Hr.	\$49.47	12	\$593.64	A
Senior Project Hydrogeologist	Hr.	\$41.63	24	\$999.12	B
Project Hydrogeologist	Hr.	\$29.74	24	\$713.76	B
				<u>\$2,306.52</u>	
TOTAL LABOR YEARS 2 - 4					
				\$4,486.16	

Notes: A: Environmental Restoration Assemblies/Unit Cost Book
B: Environmental Restoration Assemblies/Unit Cost Book
Assumptions: 1. Sample collection team members work 12-hour days.

UST 13 (AOC 322) GROUNDWATER
YEAR 5

LABOR RATES FOR SAMPLE COLLECTION, DATA VALIDATION, SUMMARY REPORT, AND SITE EVALUATION

	Unit	Unit Cost	Quantity	Cost	Source
SAMPLE COLLECTION					
Health and Safety Officer	Hr.	\$18.55	24	\$445.20	A
Field Technician	Hr.	\$14.84	24	\$356.16	A
				<u>\$801.36</u>	
DATA VALIDATION					
Senior Chemist	Hr.	\$23.50	16	\$376.00	A
SUMMARY REPORT					
Project Hydrogeologist	Hr.	\$29.74	32	\$951.68	B
Staff Engineer	Hr.	\$23.50	20	\$470.00	A
Word Processing/Clerical	Hr.	\$12.37	10	\$123.70	A
				<u>\$1,545.38</u>	
Site Evaluation					
Senior Project Hydrogeologist	Hr.	\$41.63	64	\$2,664.32	A
Project Hydrogeologist	Hr.	\$29.74	64	\$1,903.36	B
Senior Project Manager	Hr.	\$49.47	32	\$1,583.04	B
				<u>\$6,150.72</u>	
TOTAL LABOR YEAR 5					
				\$8,873.46	

Notes: A: Environmental Restoration Assemblies/Unit Cost Book
B: Environmental Restoration Options and Solutions
Assumptions: 1. Sample collection team members work 12-hour days.

**B.4 POL STORAGE AREA/DRMO YARD GROUNDWATER AREA
BACK-UP COST CALCULATIONS**

POL AREA 1/2 MO. YARDS GROUNDWATER
YEARS 1-5: NO FURTHER ACTION
SAMPLING EQUIPMENT COSTS
recycled paper

	Unit	Unit Cost	Quantity	Cost	Source
Well Development Equipment Rental (pH, Temp, Conductivity, Turbidity meters)	Day	\$115.37	3	\$346.11	A
2 inch submersible pump	Day	\$61.84	3	\$185.52	A
5 kW Generator	Day	\$55.66	3	\$166.98	A
40 mL VOC vials	Each	\$1.53	2	\$3.06	A
1 L plastic metals bottle	Each	\$2.88	9	\$25.92	A
1 Gal. Glass container	Each	\$9.59	17	\$163.03	A
1 7/8 inch teflon bailers	Each	\$48.23	10	\$482.30	A
48 qt. coolers (shipping)	Each	\$39.52	2	\$79.04	A
1/4 inch cotton rope	100 feet	\$10.70	2	\$21.40	B
				<u>\$1,473.36</u>	

Notes:

A: Environmental Restoration Assembly/Unit Cost Book
B: Hector's Hardware 2/96 rate

Assumptions:

- 1: 3-day rental (1 day each to mob, use, and demob expt.)
- 2: 1 label's 50% forms, etc. inc. with bottles (containers)
- 3: Assumes 50% greater containers than will actual (they be needed to account for breakage/errors, etc...)
- 4: Assumes 2 ropes needed per well
- 5: Assumes 2 bailers per well to account for loss
- 6: 2 coolers needed for sample shipment

POL AREA/DRMO YARDS GROUNDWATER
YEARS 1-5: NO FURTHER ACTION

SAFETY EQUIPMENT COSTS

	Unit	Unit Cost	Quantity	Cost	Source
Organic Vapor Analyzer	Day	\$123.68	3	\$371.04	A
Gas Monitor	Day	\$15.46	3	\$46.38	A
Tyvek Suit	Each	\$8.06	8	\$64.48	A
Reusable Butyl Outer Gloves	Pair	\$2.86	4	\$11.44	A
Latex Inner Gloves	Pair	\$0.30	16	\$4.80	A
Disposable Tyvek Boots	Pair	\$1.42	8	\$11.36	A
				<u>\$509.50</u>	

Notes:

A: Environmental Restoration Assemblies/Unit Cost Book

Assumptions:

1. 1-day rental (1 day each to mob, use, and demob. expt.)
2. One full day of work
3. Each person to go through 4 tyvek suits per day
4. One pair of outer gloves per person; and one extra pair per person in the event of a gear rip
5. Each person to go through 8 pairs of inner gloves per day
6. Each person has as part of the gear a full-face respirator, cartridges, a hard hat,
7. Each person has leather steel-toed boots and safety glasses
8. Each person to go through 4 pair of disposable boots per day

**POL AREA/DRMO YARDS GROUNDWATER
YEARS 1 - 5: NO FURTHER ACTION**

SHIPPING COSTS	Unit	Unit Cost	Quantity	Cost
Sampling Equipment	lb.	\$1.50	300	\$450.00
Safety Equipment	lb.	\$1.50	100	\$150.00
Samples	lb.	\$1.50	150	\$225.00
				<hr/> \$825.00

Notes: A: Federal Express 2/96 shipping rates

POL AREA 4/5 MO. YARDS GROUNDWATER
YEARS 1 - 5: NO FURTHER ACTION

LABOR RATES FOR SAMPLE COLLECTION, DATA VALIDATION, SUMMARY REPORT, AND SITE EVALUATION

SAMPLE COLLECTION	Unit	Unit Cost	Quantity	Cost	Source
Health and Safety Officer	Hr.	\$18.55	12	\$222.60	A
Field Technician	Hr.	\$14.84	12	\$178.08	A
				<u>\$400.68</u>	
DATA VALIDATION					
Senior Chemist	Hr.	\$23.50	20	\$470.00	A
SUMMARY REPORT					
Staff Engineer	Hr.	\$23.50	20	\$470.00	A
Word Processing/Clerical	Hr.	\$12.37	10	\$123.70	A
				<u>\$593.70</u>	
SITE EVALUATION					
Senior Project Manager	Hr.	\$49.47	10	\$494.70	A

Notes:

A: 1995- Environmental Restoration Assmbly/Unit Cost Book
Cost Options and Solutions

Assumptions:

- 1: Sample collection team members work a full 12 hour day by labor levels shown
- 2: Data validation requires 20 hours to complete by labor level shown
- 3: Summary report requires 10 hours to be written by labor level shown
- 4: Word processing requires 10 hours of word processing and editing time by labor level shown
- 5: Site evaluation requires 10 hours to conduct by labor level shown

POL AREA/PRMO: YARDS GROUNDWATER
YEARS 1 - 5: NO FURTHER ACTION

TRAVEL EXPENSES	Unit	Unit Cost	Quantity	Cost	Source
Air Fare	Per Person	\$554.00	2	\$1,108.00	A
Meals	Per Person	\$30.00	2	\$60.00	B
Van Rental	Day	\$69.99	1	\$69.99	C
Fuel	Gal.	\$1.22	10	\$12.20	D
				<u>\$1,250.19</u>	

Notes:

- A: US Air 2/8/96 R/T air fare from Washington Int'l Airport to Logan Int'l
- B: Ecology & Environment 2/96 per diem (meals only) rate
- C: Hertz 2/8/96 7 passenger mini-van rate - pick up and drop off at Logan Int'l.
- D: Leominster, Mass. Shell Oil Gas 2/8/96 regular unleaded fuel rate

Assumptions:

- 1: 2-person work team
- 2: Arrive and depart from site same day
- 3: Use 10 gal. fuel

POL AREA/DRM 1: YARDS GROUNDWATER
YEARS 1 - 5: NO FURTHER ACTION

SAMPLE ANALYTICAL COSTS

	Unit	Unit Cost	Quantity	Cost	Source
VOCs	Sample	\$324.66	16	\$5,194.56	A
PCBs/Pesticides	Sample	\$213.96	7	\$1,497.72	A
TAL Metals	Sample	\$290.64	14	\$4,068.96	A
				<u>\$10,761.24</u>	

Notes:

A: Environmental Restoration Assemblies/Unit Cost Book
Environmental Cost Handling Options and Solutions

Assumptions:

1. Unfiltered sample taken of each contaminant group per each of the 5 wells
2. Metals taken per each of the 5 wells
3. Duplicate sample taken of each contaminant group
4. Filtered sample taken of TAL metals
5. Rinse blank (VOCs only) taken of each contaminant group of the metals filter
6. Army does not require MS/MS samples to be taken
7. Each well has a dedicated bailed, therefore, no rinsate on bailed needed

POL AREA DRILLING YARDS GROUNDWATER
YEARS 0, 5, 10, 15, 20, 25, 30

SAMPLING EQUIPMENT COSTS

Well Development Equipment Rental (pH, Temp, Turbidity, Conductivity, meters)	Unit	Unit Cost	Quantity	Cost	Source
2 inch submersible pump	Day	\$115.37	3	\$346.11	A
5 kW Generator	Day	\$61.84	3	\$185.52	A
40 mL VOC vials	Day	\$55.66	3	\$166.98	A
1 L plastic metals bottle	Each	\$1.53	20	\$30.60	A
1 Gal. glass container	Each	\$2.88	9	\$25.92	A
1 7/8 inch teflon bailers	Each	\$9.59	17	\$163.03	A
48 qt. coolers (shipping)	Each	\$48.23	10	\$482.30	A
1/4 inch cotton rope	Each	\$39.52	2	\$79.04	A
100 feet	Unit	\$10.70	3	\$32.10	B
				<u>\$1,511.60</u>	

Notes:

A: Environmental Restoration Assemblies/Unit Cost Book
B: 1995 Environmental Handling Options and Solutions
B: Hector's Hardware 2/96 rate

Assumptions:

- 1: 3-day rental (1 day each to mob, use, and demob except.)
- 2: 1 day's 20% forms, etc. Inc. to bottles (containers) than will actually be needed to account for breakage/errors, etc...
- 3: Assumes 20% greater container than will actually be needed to account for breakage/errors, etc...
- 4: 20 feet of rope needed per well to account for loss
- 5: Assumes 2 bailers per well to account for loss
- 6: 2 coolers needed for sample shipment

POLY(ANILINE) YARDS GROUNDWATER CONTROLS
YEARS 0, 5, 10, 15, 20, 25, 30

SAFETY EQUIPMENT COSTS

	Unit	Unit Cost	Quantity	Cost	Source
Organic Vapor Analyzer	Day	\$123.68	3	\$371.04	A
Gas Monitor	Day	\$15.46	3	\$46.38	A
Tyvek Suit	Each	\$8.06	8	\$64.48	A
Reusable Butyl Outer Gloves	Pair	\$2.86	4	\$11.44	A
Latex Inner Gloves	Pair	\$0.30	16	\$4.80	A
Disposable Tyvek Boots	Pair	\$1.42	8	\$11.36	A
				<u>\$509.50</u>	

Notes:

A: Environmental Restoration Assemblies/Unit Cost Booklets

Assumptions:

1. 3-day rental (1 day each to mob, use, and demob. expt.)
2. One person works each day of work.
3. One person to go through 4 tyvek suits per day.
4. One pair of outer gloves per person, and one extra pair per person in the event of tears/rips per person.
5. Each person to go through 8 pairs of inner gloves per day.
6. Each person has as part of their gear a full-face respirator, cartridges, a hard hat, leather steel-toed boots, and safety glasses.
7. Each person to go through 4 pairs of disposable boots per day.

POL AREA/DRMO YARDS GROUNDWATER
YEARS 0, 5, 10, 15, 20, 25, 30

SHIPPING COSTS	Unit	Unit Cost	Quantity	cost
Sampling Equipment	lb.	\$1.50	300	\$450.00
Safety Equipment	lb.	\$1.50	100	\$150.00
Samples	lb.	\$1.50	150	\$225.00
				<hr/> <u>\$825.00</u>

Notes: A: Federal Express 2/96 shipping rates

POL AREA/DRMO YARDS GROUNDWATER
YEARS 0, 5, 10, 15, 20, 25, 30
CONTROLS

LABOR RATES FOR SAMPLE COLLECTION, DATA VALIDATION, SUMMARY REPORT, AND SITE EVALUATION

SAMPLE COLLECTION	Unit	Unit Cost	Quantity	Cost	Source
Health and Safety Officer	Hr.	\$18.55	12	\$222.60	A
Field Technician	Hr.	\$14.84	12	\$178.08	A
				<u>\$400.68</u>	
DATA VALIDATION					
Senior Chemist	Hr.	\$23.50	20	\$470.00	A
SUMMARY REPORT					
Staff Engineer	Hr.	\$23.50	20	\$470.00	A
Word Processing/Clerical	Hr.	\$12.37	10	\$123.70	A
				<u>\$593.70</u>	
SITE EVALUATION					
Senior Project Manager	Hr.	\$49.47	10	\$494.70	A

Notes:

A: 1995- Environmental Restoration Assemblies/Unit Cost Book

Assumptions: 1. Sample collection team members work a full 12 hour day by labor levels shown

2. Data validation requires 20 hours to complete by labor level shown

3. Summary report requires 20 hours to be written by labor level shown

4. Word processing requires 10 hours of word processing and editing time by labor level shown

5. Site evaluation requires 10 hours to conduct by labor level shown

POLY AREA/DRMO YARDS GROUNDWATER CONTROLS
YEARS 0, 3, 10, 15, 20, 25, 30

TRAVEL EXPENSES	Unit	Quantity	Unit Cost	Cost	Source
Air Fare	Per Person	2	\$554.00	\$1,108.00	A
Meals	Per Person	2	\$30.00	\$60.00	B
Van Rental	Day	1	\$69.99	\$69.99	C
Fuel	Gal.	10	\$1.22	\$12.20	D
				<u>\$1,250.19</u>	

Notes:

- A: US Air 2/8/96 R/T air fare from Washington Int'l Airport to Logan Int'l
- B: Ecology & Environment 2/96 per diem (meals only) rate
- C: Hertz 2/8/96 7-passenger mini-van rate - pick up and drop off at Logan Int'l.
- D: Leominster, Mass. Shell Oil Gas 2/8/96 regular unleaded fuel rate

Assumptions:

- 1. 2-person work team
- 2. Depart from site same day
- 3. Use 10 gal. fuel

POLY AREA/DRMO YARDS GROUNDWATER CONTROLS
YEARS 0, 5, 10, 15, 20, 30

SAMPLE ANALYTICAL COSTS

	Unit	Unit Cost	Quantity	Cost	Source
VOCs	Sample	\$324.66	16	\$5,194.56	A
PCBs/Pesticides	Sample	\$213.96	7	\$1,497.72	A
TAL Metals	Sample	\$290.64	14	\$4,068.96	A
				<u>\$10,761.24</u>	

Notes: A: Environmental Restoration Assemblies/Unit Cost Book
1995-Environmental Cost Handling Options and Solutions

Assumptions:

- 1: Unfiltered sample taken of each contaminant group per each of the 5 wells
- 2: VOC samples taken per each of the 5 wells, the duplicate, and the blanks
- 3: Unfiltered duplicate sample taken of each contaminant group
- 4: Unfiltered sample taken of each metals filter
- 5: Rinsate blank (VOCs only) taken
- 6: Army does not require MSD samples to be taken
- 7: Each well has a dedicated bather, therefore, no rinsate on bather needed

POLY AREA & DRUM YARD
YEARS 1 - 5

SAMPLE ANALYTICAL COSTS

	Unit	Unit Cost	Quantity	Cost	Source
Nitrate	Sample	\$35.68	18	\$642.24	A
Nitrite	Sample	\$35.68	18	\$642.24	A
Phosphate	Sample	\$29.73	18	\$535.14	A
Sulfate	Sample	\$14.27	18	\$256.86	A
Sulfide	Sample	\$55.90	18	\$1,006.20	A
Total Iron	Sample	\$20.00	18	\$360.00	B
Soluble Iron (ferric)	Sample	\$20.00	18	\$360.00	B
BTEX Volatiles	Sample	\$89.19	20	\$1,783.80	A
As, Fe, Mn (filtered)	Sample	\$150.00	18	\$2,700.00	B
Alkalinity	Sample	\$21.40	18	\$385.20	A
Ammonia-Nitrogen	Sample	\$41.63	18	\$749.34	A
TPHc	Sample	\$112.98	18	\$2,033.64	A
TOTAL ANALYTICAL YEARS 1 - 5					
				\$11,456.66	

Notes: A: EPA/Environmental Restoration and Remediation Cost Booklets
B: Ecology & Environment, Inc. 1992 Options and Solutions

Assumptions:

- 1: Total iron is unfiltered.
- 2: Ferric (soluble) iron is filtered.
- 3: Filtered arsenic, iron and manganese are filtered.
- 4: All other samples are filtered.
- 5: One disposable tubing is used for collection.
- 6: Only one trip blank (BTEX VOA) is taken.
- 7: One duplicate is taken + matrix spike and MS duplicate.
- 8: Assume USEPA protocols not USEC.

POLY AREA/DRY YARD
YEAR 1
REMEDIAL REMEDIATION

SAMPLING EQUIPMENT COSTS

	Unit	Unit Cost	Quantity	Cost	Source
Teflon tubing	Linear Foot	\$1.73	420	\$726.60	A
Well Development Equipment Rental (pH/Temperature/Conductivity, O ₂ meter, Redox)	Day	\$115.37	5	\$576.85	B
Peristaltic pump	Day	\$61.84	5	\$309.20	B
5 kW Generator	Day	\$55.66	5	\$278.30	B
40 mL VOC vials	Each	\$1.53	40	\$61.20	B
1 L Plastic metals bottle	Each	\$2.88	90	\$259.20	B
1 L glass container	Each	\$9.59	18	\$172.62	B
48 qt. coolers (shipping)	Each	\$39.52	10	\$395.20	B
Filter (barrel/pressure)	Day	\$15.00	3	\$45.00	C
TOTAL SAMPLING EQUIPMENT COSTS YEAR 1				\$2,824.17	
WELL INSTALLATION	Each	\$2,069.00	5	\$10,345.00	D

Notes:

- A: EDOX Environmental Restoration Assembly/Unit Cost Book 1995
- B: EDOX Environmental Restoration Assembly/Unit Cost Options and Solutions 1995
- C: Ecology Environmental Cost Handling Options and Solutions
- D: Competitive bids for similar wells in New York State

Assumptions:

- 1: 5-day rental
- 2: 1-day to mobilize and demobilize with 3 days field use
- 3: 1-day to mobilize and demobilize with 3 days field use
- 4: assumes 50% greater containers than will actually be needed to account for breakage/errors, etc...

**POLYANILINE/PHENOL YARD
YEARS 2-5: REMEDIATION**

SAMPLING EQUIPMENT COSTS

Perlon tubing	Unit	Unit Cost	Quantity	Cost
Well Development Equipment Rental (pH, Temperature, Conductivity, Dissolved oxygen meter, Redox)	Linear foot	\$1.73	420	\$726.60
Peristaltic pump	Day	\$115.37	5	\$576.85
5 kW Generator	Day	\$61.84	5	\$309.20
40 mL VOC vials	Day	\$55.66	5	\$278.30
1 L plastic metals bottle	Each	\$1.53	40	\$61.20
1 L glass container	Each	\$2.88	90	\$259.20
48 Qt. coolers (shipping)	Each	\$9.59	18	\$172.62
Filter (barrel/pressure)	Each	\$39.52	10	\$395.20
	Day	\$15.00	3	\$45.00
TOTAL SAMPLING EQUIPMENT COSTS YEARS 2 - 5				\$2,824.17

Notes:

- A: FDX Environmental Restoration Assemblies/Unit Cost Book
- B: FDX Environmental Restoration Assemblies/Unit Cost Book
- C: Ecology & Environment, Inc. 1992 Handling Options and Solutions

Assumptions:

- 1: 5-day rental (1 day to mob and demob equipment, 3 days field use)
- 2: 1-gal. GC forms etc. with bottles/3 containers
- 3: Ten collars needed for sample shipment.

POL AREA/DRUM YARD
YEAR 1

LABOR RATES FOR SAMPLE COLLECTION, DATA VALIDATION, SUMMARY REPORT, AND SITE EVALUATION/GROUNDWATER MODEL

SAMPLE COLLECTION	Unit	Unit Cost	Quantity	Cost	Source
Health and Safety Officer	Hr.	\$18.55	72	\$1,335.60	A
Field Technician	Hr.	\$16.84	72	\$1,068.48	A
				<u>\$2,404.08</u>	
DATA VALIDATION					
Senior Chemist	Hr.	\$23.50	32	\$752.00	A
SUMMARY REPORT					
Project Hydrogeologist	Hr.	\$29.74	64	\$1,903.36	B
Staff Engineer	Hr.	\$23.50	64	\$1,504.00	A
Word Processing/Clerical	Hr.	\$12.37	20	\$247.40	A
				<u>\$3,654.76</u>	
Site Evaluation/Groundwater Model/Well Installation					
Senior Project Manager	Hr.	\$49.47	48	\$2,376.56	A
Senior Project Hydrogeologist	Hr.	\$41.63	400	\$16,652.00	B
Project Hydrogeologist	Hr.	\$29.74	600	\$17,844.00	B
				<u>\$36,870.56</u>	
TOTAL LABOR YEAR 1				<u>\$43,681.40</u>	

Notes: A: Environmental Restoration Assemblies/Unit Cost Book
B: Environmental Restoration Options and Solutions
Assumptions: 1. Sample collection team members work 12-hour days.

POL AREA/PRIMO YARD
INTRASTIC PREHEMPTION
YEARS 2 - 4

LABOR RATES FOR SAMPLE COLLECTION, DATA VALIDATION, SUMMARY REPORT, AND SITE EVALUATION

SAMPLE COLLECTION		Unit	Unit Cost	Quantity	Cost	Source
Health and Safety Officer	Hr.	\$18.55	72	72	\$1,335.60	A
	Hr.	\$14.84	72	72	\$1,068.48	A
					<u>\$2,404.08</u>	
DATA VALIDATION						
senior Chemist	Hr.	\$23.50	32	32	\$752.00	A
SUMMARY REPORT						
Project Hydrogeologist	Hr.	\$29.74	16	16	\$475.84	B
	Hr.	\$23.50	16	16	\$376.00	A
	Hr.	\$12.37	12	12	\$148.44	A
					<u>\$1,000.28</u>	
Site Evaluation/Groundwater Model						
Senior Project Manager	Hr.	\$49.47	16	16	\$791.52	A
	Hr.	\$41.63	32	32	\$1,332.16	B
	Hr.	\$29.74	32	32	\$951.68	B
					<u>\$3,075.36</u>	
TOTAL LABOR YEARS 2 - 4						
					\$7,231.72	

Notes:

A: Environmental Restoration Assemblies/Unit Cost Book
B: Environmental Restoration Options and Solutions
Assumptions: 1. Sample collection team members work 12-hour days.

POL AREA/DRY YARD
TRANSIT REMEDIATION
YEAR 5

LABOR RATES FOR SAMPLE COLLECTION, DATA VALIDATION, SUMMARY REPORT, AND SITE EVALUATION

SAMPLE COLLECTION	Unit	Unit Cost	Quantity	Cost	Source
Health and Safety Officer	Hr.	\$18.55	72	\$1,335.60	A
Field Technician	Hr.	\$14.84	72	\$1,068.48	A
				<u>\$2,404.08</u>	
DATA VALIDATION					
senior Chemist	Hr.	\$23.50	32	\$552.00	A
SUMMARY REPORT					
Project Hydrogeologist	Hr.	\$29.74	32	\$951.68	B
Staff Engineer	Hr.	\$23.50	20	\$470.00	A
Word Processing/Clerical	Hr.	\$12.37	10	\$123.70	A
				<u>\$1,545.38</u>	
SITE EVALUATION					
Senior Project Hydrogeologist	Hr.	\$41.63	64	\$2,664.32	A
Project Hydrogeologist	Hr.	\$29.74	64	\$1,903.36	B
Senior Project Manager	Hr.	\$49.47	32	\$1,583.04	B
				<u>\$6,150.72</u>	
TOTAL LABOR YEAR 5				<u>\$10,852.18</u>	

Notes: A: Environmental Restoration Assemblies/Unit Cost Book
B: Environmental Cost Handling Options and Solutions
Assumptions: 1. Sample collection team members work a full 12 hour day by labor levels shown

**POL AREA DEMO YARD
INTRASTIC REMEDIATION**

YEARS 1 - 5

TRAVEL EXPENSES		Unit	Unit Cost	Quantity	Cost	Source
Air Fare		Per Person	\$554.00	4	\$2,216.00	A
Meals		Per Person	\$30.00	16	\$480.00	B
Van Rental		Day	\$69.99	5	\$349.95	C
Fuel		Gal.	\$1.22	20	\$24.40	D
Lodging		day/person	\$48.00	12	\$576.00	E
TOTAL TRAVEL YEARS 1 - 5					\$3,646.35	

Notes:

- A: US Air 2/8/96 R/T air fare from Washington Int'l Airport to Logan Int'l
- B: Ecology & Environment 2/96 per diem (meals only) rate
- C: Hertz 2/8/96 7-passenger mini-van rate - pick up and drop off at Logan Int'l.
- D: Leominster, Mass. Shell Oil Gas 2/8/96 regular unleaded fuel rate
- E: Holiday Inn, Leominster, MA, 2/96 quote

Assumptions:

- 1: 4-person work team
- 2: 1-day mob, 3 days field work

POL AREA/DRMO YARD
YEARS 1 - 5

<u>SHIPPING COSTS</u>	Unit	Unit Cost	Quantity	Cost	Source
Sampling Equipment	lb.	\$1.50	290	\$435.00	A
Safety Equipment	lb.	\$1.50	100	\$150.00	A
Samples	lb.	\$1.50	650	\$975.00	A
TOTAL SHIPPING YEARS 1 - 5					\$1,560.00

Notes: A: Federal Express 2/96 shipping rates

Assumptions:
1: Sampling equipment weighs 290 lbs.
2: Safety equipment weighs 100 lbs.
3: Samples weigh 650 lbs when ready for shipment

POLY AREA/DRUM YARD
INTRINSIC REMEDIATION

YEARS 1 - 5

recycled paper

SAFETY EQUIPMENT COSTS

	Unit	Unit Cost	Quantity	Cost	Source
Organic Vapor Analyzer	Day	\$123.68	5	\$618.40	A
Gas Monitor	Day	\$15.46	5	\$77.30	A
Tyvek Suit	Each	\$8.06	10	\$80.60	A
Reusable Butyl Outer Gloves	Pair	\$2.86	10	\$28.60	A
Latex Inner Gloves	Pair	\$0.30	20	\$6.00	A
Disposable Tyvek Boots	Pair	\$1.42	10	\$14.20	A
TOTAL SAFETY EQUIPMENT COSTS YEARS 1 - 5				\$825.10	

Notes:

A: Environmental Restoration Assemblies/Unit Cost Book
1995-Environmental Cost Handling Options and Solutions

Assumptions: 1. Each person has a full-face respirator, cartridges, hard hat, leather steel-toed boots, and safety glasses.

APPENDIX C

RESPONSE TO COMMENTS RECEIVED ON THE DRAFT AND FINAL FEASIBILITY STUDY

Response to Comments
Final Feasibility Study for Functional Area II (AOCs 32, 43A)
Fort Devens, Massachusetts

United States Environmental Protection Agency Region I (New England)
November 8, 1996

General Comments

Comment 1: The range of remedial alternatives proposed for Functional Area II soils is adequate. For the groundwater however, we feel an additional alternative needs to be evaluated. Further, the remedial strategy for the groundwater needs to be reconsidered.

In regard to the above, EPA would propose evaluating an intrinsic remediation/long-term monitoring (IR/LTM) with a technical impracticability component for the UST 13 area. This remedial alternative should at a minimum, include: an evaluation as to whether additional source control actions are needed (UST 13 & POL Yard); expansion of the existing monitoring network; continuation of the groundwater modeling effort; and IR/LTM plan that follows the recently published "Technical Protocol for implementing Intrinsic Remediation with Long-Term Monitoring for Natural Attenuation of Fuel Contamination Dissolved in Groundwater" and the soon to be finalized (May 1997) "Draft Technical Protocol for evaluating Natural Attenuation of Chlorinated Solvents in Groundwater"; expansion of the contaminant list to include bioremediation indicator analytes and compounds; and consideration for setting a point at which action may need to be taken to protect the MADEP designated potentially productive aquifer which underlies the area.

Response: Agreed. The FS will be modified to incorporate intrinsic remediation as a remedial alternative.

Comment 1 continued: We also feel that it would make sense to treat the groundwater as one operable unit for the following reasons: We feel there is insufficient consideration, both in terms of data and analysis, in the RI/FS reports relative for the UST-13 area to potentially be the source of the low levels of chlorinated solvent contamination identified to the southwest, in DRMO and POL area monitoring wells. Also, there is insufficient information concerning the several fuel plumes which were delineated on the basis of screening samples. Although "confirmatory" samples generally did not confirm the presence of these plumes, it is highly questionable that the current monitoring well network is spatially placed in a fashion which would allow for confirmation. In fact, cross sections of the plumes presented in the RI indicate that the bottoms of the plumes were not identified. This information, as well as general water level fluctuations will require that additional screens be added to deeper portions of the overburden aquifer, which currently only contains monitoring well screens in the uppermost portion.

The amount and type of additional evaluation needed as a result of our interpretations will in part depend upon which remedial alternative is selected and can be discussed in greater detail once that selection is made. In order to keep the process moving along, any additional work that is required can be accomplished during the RD/RA phase of the project.

Response: The groundwater will be evaluated as two separate operable units (GWOU1 and GWOU2) as discussed during our meeting on 23 October 1996. The GWOU1 will contain the groundwater which flows under the east and west yards of the DRMO Yard, across Market Street and through the POL site area (AOC 43A). The GWOU1 will contain the groundwater under the UST 13 area, which is east of the groundwater divide.

Additional monitoring wells will be installed and analytical data will be collected to further characterize GWOU1 and GWOU2 to determine if natural attenuation is occurring. This information will be collected during the RD/RA phase of the project.

Since the USEPA reviewed, commented, and approved the RI workplans and the RI Report, the claim that "insufficient consideration" was given to both "data and analysis in the RI/FS reports relative for the UST 13 area..." seem inappropriate at this time. However, the Army does plan to collect additional information at both the UST 13 and DRMO Yard/POL Storage areas during the RD/RA phase as discussed during our meeting on 23 October 1996.

Comment 2: The ARARS Tables will need to be upgraded and expanded. Typically in an FS, separate ARARs Tables (action, chemical, & location-specific) are created for each alternative evaluated. Further, in rebuttal to your response on our previous ARAR table comment, Table 508 of the Final Shepley's Hill Landfill FS contains an acceptable format, as does the Final FSs for both Barnum Road Maintenance Yard and AOCs 43G & J. Please review these examples and include the proper format in the revised FS.

Response: Individual tables will be developed for each operable unit as requested, using examples from one of the FSs cited.

SPECIFIC COMMENTS

Comment 3: Page 1-12, Section 1.2.1.4: Please update the second paragraph based on the intended reuse for this area from the 1994 reuse plan.

Response: The text has been amended based on the November 1996 Reuse Plan.

Comment 4: Page 1-25, Section 1.3: POL Yard groundwater might need to be considered for remedial action because of the potential migration of CERCLA contaminants from DRMO Yard and possibly UST-13.

Response: An operable unit for POL Storage Area/DRMO Yard groundwater has been considered for remedial action, and text has been added to the study.

Comment 5: Page 2-7, Section 2.4.3: In that this is a CERCLA cleanup, the EPA Risk Range of 10E4 to 10E6 should have been used, not 10E5.

Response: The text has been modified to state that a 10E4 to 10E6 range has been used.

**Response to Comments on
DRAFT FEASIBILITY STUDY
FUNCTIONAL AREA II
AOC 32 AND AOC 43A
FORT DEVENS, MASSACHUSETTS
(March 1995)**

January 1996

Comments Received From:

**UNITED STATES ENVIRONMENTAL PROTECTION AGENCY (EPA)
MASSACHUSETTS DEPARTMENT OF ENVIRONMENTAL PROTECTION (MDEP)**

(NOTE: Comments were retyped exactly as submitted.)

EPA COMMENTS

C-9

11:UC4092/RC1579-01/16/97-D1

recycled paper

ecology and environment

GENERAL COMMENTS

Comment-1: During the review of the RI for Functional Area I & II, EPA provided a general comment that agreed with the conclusions and recommendations concerning AOC 43A, POL Storage Yard. However, as part of this agreement, EPA suggested that the remainder of the POL Area be paved to prevent further contamination of the surface/subsurface soils and exposures to site workers. The Army did not agree with these additional measures in their response. Even though the risks presented by 43A are acceptable, we still think it would be prudent for the Army to consider paving the remainder of POL Yard.

Response: Paving the POL area would have little or no impact on human health risks, which were found to be minimal. The risk assessment revealed only one pathway (unfiltered groundwater consumption by future site workers) which exceeded the current recommended EPA risk threshold of 10^{-4} . Paving the area would have no impact on a worker's exposure to groundwater. The exceedance of the threshold was slight (1.9×10^{-4}), and the scenario is so improbable that it is not worth consideration. Furthermore, the risk is based on beryllium, which was only detected once above the detection limit and was found at much lower concentrations (below the detection limit) in filtered samples. The beryllium levels almost certainly represent the natural presence of beryllium sorbed onto aquifer particles (the one sample with a beryllium level above the detection limit had high concentrations of a variety of metals).

Three additional pathways, all for soil, exceeded the 10^{-5} threshold, favored by MDEP, being used in the revised FS for the determination of cleanup goals. One of these pathways, future construction workers (performing excavations, etc.), would not be mitigated by paving. For the other two pathways, (current and future site workers), the risks were due almost entirely to incidental ingestion. These risks were based on the presence of five PAHs in one sample and arsenic in another sample. The PAHs were detected from 2 to 4 $\mu\text{g/g}$, below the candidate cleanup goal of 7 $\mu\text{g/g}$ (based on a 10^{-5} risk threshold) and well within the range normally found in areas near fossil fuel combustion sources. This sample is much more likely to reflect ambient conditions at Fort Devens than a source of contamination. Arsenic, which was consistently found in background samples, was detected at a high concentration (210 $\mu\text{g/g}$) in one sample. This detection level is ten times greater than background, which is the cleanup goal. This sporadic detection is much more likely to represent natural variation than site contamination. In summary, the risks from contamination detected in soils did not greatly exceed the MDEP threshold for any pathway and were due to the highly sporadic detection of a naturally occurring metal and the low level contamination of five organics which are commonly found in urban areas. It is not appropriate to perform any remedial action in response to these "risks".

Three pathways were identified as having a hazard index greater than 1. Two of them are for worker consumption of groundwater (filtered and unfiltered) both highly unlikely scenarios since area users are served by municipal wells. Moreover, the risks were due to manganese, which was detected at its highest concentration in a background well north of AOC 32 (indicating its natural presence) and lead, which had drastically reduced concentrations in filtered samples (indicating its presence as particulate matter).

United States Environmental Protection Agency Comments (continued)

The other pathway is future construction workers' exposure to soil, and the hazard index value is the result of arsenic, which is not considered a significant contaminant, as discussed above. Paving would have no impact on any of these pathways.

Comment-2: Section 2 is fairly comprehensive and presents a very logical approach to establishing clean-up goals. A narrative section on key ARARs - CERCLA, RCRA, HSWA, etc would be beneficial. Identification of areas and volume of environmental media based on the established clean-up goals would also be very helpful. Table 2-1 through 2-3 are very useful.

Response: Noted. A discussion of several key ARARs has been added to the revised FS. Areas and volumes of contamination are presented in Section 2 of the FS, in the discussion of cleanup goals and exceedances.

Comment-3: Section 4 - Based on the FS format established in the NCP, the screening stage should be based on effectiveness, implementability and relative costs. Although cost evaluation is the least important factor of the three at this stage, you do not present cost information in Section 4 as established by the NCP format.

Response: Section 4 has been reformatted to explicitly include discussions on effectiveness, implementability, and relative cost.

Comment-4: Section 5 - Back-up cost estimating calculations are not provided.

Response: More detail on the cost estimates, including back-up information, has been added to the revised FS.

Comment-5: The ARARs Tables and discussions need upgrading. Please see recent examples of EPA-approved FSs such as the Shepley's Hill Landfill FS.

Response: This comment is non-specific and is not explained by other comments. It seems to be inconsistent with general comment 2. It is unclear exactly what "upgrading" the commenter is hoping to see. Some detail regarding background information on key ARARs has been added to the revised FS. The ARAR discussion in the Shepley's Hill Landfill FS does not include any tables or discussion regarding ARAR selection and cleanup goal development.

United States Environmental Protection Agency Comments (continued)

SPECIFIC COMMENTS

Comment-1: Section 1.2.1.3, Page 1-3, Paragraph 4: The Nature and Extent of Contamination section frequently refers to "screening values" without clearly defining or explaining what they are. A brief explanation of these values would be appropriate.

Response: The following summary has been placed at the beginning of Section 1.2.1.3 and referenced in Section 1.2.2.3.

During the RI, screening values were compiled by E & E for each analyte for comparison against sampling results. Most screening values were based on chemical-specific ARARs identified for this project by Oak Ridge National Laboratories, although where no ARARs existed, other levels to be considered (TBCs) were used. E & E developed a set of numerical criteria, entered the values into the Site Master Database, and ran a comparison of analytical results for each medium against the screening values. Screening values are not intended to be cleanup goals, i.e. goals used to identify areas requiring remediation. These are developed in Section 2 of the FS. Screening values are merely used to identify areas where contamination may exceed regulatory levels and to assist in the nature and extent of contamination discussions.

A detailed discussion of the ARAR selection process and the development of screening values can be found in Section 7 of Volumes II and III of the Functional Area II RI report (E & E 1994). A summary of ARARs by medium is provided here:

- **Soils:** Massachusetts Contingency Plan (MCP) Method I was identified by Oak Ridge National Laboratories as an ARAR, and was used for the screening values of contaminants in soil. Where no values existed, the EPA Region III risk-based concentrations (RBCs) for commercial/industrial soils were used as screening values. For lead, the EPA Interim Guidance on Soil Lead Clean-up levels at Superfund sites was used.
- **Sediment:** There are no promulgated maximum allowable concentrations for chemicals in sediments under Massachusetts or Federal Law. Therefore, results were compared to screening values developed for soils.
- **Surface Water:** From surface water, the lowest of two levels identified in the Clean Water Act (CWA) Ambient Water Quality Criteria (AWQC) was chosen: one for the protection of human health from risks due to water and fish consumption, and a second for the protection of aquatic organisms in freshwater due to chronic effects. The AWQC criteria were identified as ARARs by Oak Ridge National Laboratory.

United States Environmental Protection Agency Comments (continued)

- **Groundwater:** Screening values in groundwater were based on the lowest of the following criteria: Safe Drinking Water Act (SDWA) Maximum Contaminant Levels (MCLs), the Massachusetts MCL (MMCL), MCP GW-1 water standards, the SDWA MCL Goal (MCLG) and Massachusetts Secondary MCL (SMCL). All were identified as chemical specific ARARs by Oak Ridge. Where no ARAR existed, SDWA SMCLs, EPA Office of Water Lifetime Health Advisories (HA), and Massachusetts Office of Research and Standards Guidelines (ORSG) were reviewed. Although these standards are only TBC guidance, the lowest value was selected.

Comment-2: Section 2.4.1, Page 2-3, last paragraph: The Massachusetts Contingency Plan (MCP) should be considered for applicability as an ARAR for the site. The February 1, 1995 MCP has soil and groundwater standards which may be relevant to the site.

Response: Subsequent to this comment being submitted, EPA has determined that the MCP should not be used as an ARAR.

Comment-3: Section 2.7.1, Page 2-8, last paragraph: The 210 mg/kg concentration of arsenic noted in this paragraph appears to significantly exceed the cleanup goal of 19 mg/kg specified for the site. Also the report focuses solely on lead and PCBs and dismisses other contaminants (arsenic, beryllium and PAHs) noted in Table 2.1 as exceeding cleanup goals. Please provide the rational for dismissing these contaminants. This further supports General Comment 1 and the request for additional measures at this site.

Response: The text has been amended to note that one detection of arsenic was significantly above the cleanup goal. The only contaminant detected above cleanup goals in AOC 43A soils was arsenic (PAHs no longer exceed cleanup goals, which are now based on an acceptable risk threshold of 10^{-5} , as favored by MDEP). Because only one arsenic detection greatly exceeded cleanup goals (the same detection was responsible for the identified risk) and there is no identifiable source of contamination, no remedial action is warranted for AOC 43A soils. Beryllium was responsible for the identified risk in groundwater. However, as described in the FS Section 1.2.2.4 and in the response to general comment 1, it is not appropriate to perform remedial action for this contaminant which is almost certainly naturally present. Furthermore, it does not exceed cleanup goals for either soil or groundwater.

The report focuses on lead, cadmium and pesticides (in the revised FS), and PCBs because these were the contaminants causing problems in AOC 32 soil (which is the only soil operable unit carried through the FS). The rationale for dismissing other contaminants detected above cleanup goals at AOC 32 is included in the revised text (Section 2.7.2.3). Essentially, arsenic did not significantly exceed the cleanup goals at AOC 32, and it appears that they are naturally occurring. Regardless, most of the areas where these detections occurred will be handled by the proposed remedial action anyway. The

United States Environmental Protection Agency Comments (continued)

pesticides above cleanup goals (DDT, DDD, and DDE) were detected in the northeast portion of the east yard and are considered in the revised FS.

Comment-4: Section 3.2.5.3, Page 3-5, 3rd paragraph: Asphalt batching should be considered a remedial action technology in this section. Asphalt batching would be a logical choice at this site based on the contaminants involved, the media contaminated (soil and asphalt) and the fact that asphalt batching has been successfully used as a remediation technique at Fort Devens.

Response: Asphalt batching has been added to Section 3.2.5.3.

Comment-5: Section 4.1.4, Page 4-3, 3rd paragraph: See comment above.

Response: In response to Comment-4 asphalt batching was added to Section 3.2.5.3 but was subsequently screened out based on implementability concerns and therefore is not included in any alternative in Section 4.

Comment-6: Section 5.1.3.1, Page 5-6, 4th paragraph: Consolidation of the material into a much smaller area would seem a more logical approach to minimize the area to be capped and minimize final cover costs.

Response: It is true that additional excavation of soils would reduce the size of the area requiring cover. However, this would have negative impacts on the short-term effectiveness of this alternative. It would result in increased dust production which could pose a hazard to the community. In addition, it may be preferable to minimize the higher grade resulting from the cap, in order to provide for sufficient runoff control while maintaining usage of Cook Street. Finally, although increased consolidation would reduce the capping costs, this savings would be significantly offset by the increased excavation and verification sampling costs.

Comment-7: Section 5.1.4.1, Page 5-11, 1st paragraph: TCLP testing would have to be modified to include PCBs as an analysis parameter since they are not included in the standard suite of parameters analyzed.

Response: The recommendation for TCLP testing has been amended to include analysis for PCBs. However, no regulatory level exists for PCB TCLP analysis. An action level for PCB leaching from the solidified mass would need to be negotiated between the EPA and the Army.

Comment-8: Section 5.1.4.1, Page 5-11, 2nd paragraph: Placing a layer of solidified material six inches below the ground surface without designing a means for controlling

United States Environmental Protection Agency Comments (continued)

precipitation infiltration will likely result in problems with frequent saturation of the overlying topsoil. This issue must be addressed at some point in the design process.

Response: Agreed. This section has been amended to introduce the issue of drainage and the need to address it in the design process.

Comment-9: Section 5.1.4.2, Page 5-12, 3rd paragraph: Please verify the last sentence in the paragraph is, in fact, intended to refer to PCBs regarding a permanent solution. The initial discussion indicated the permanent solution was for lead.

Response: The last sentence in this paragraph does, in fact, refer to PCBs (and pesticides). This alternative is certainly considered permanent for lead (and cadmium), which will bind chemically to the cement matrix, and therefore be essentially removed from the soils. Organic compounds will not bind chemically to the matrix, they will be physically bound. Therefore, if infiltrating rainwater were able to pass through the monolith, some organic constituents could potentially dissolve and be transported out of the matrix. However, PCBs (and pesticides) are highly insoluble and are noted for their extreme partitioning to solid particles. Therefore, it is very unlikely that detectable quantities of PCBs (and pesticides) would leach out of the cement matrix, even if considerable amount of rainwater were to percolate through. For these reasons, this alternative can be considered a permanent solution for PCBs (and pesticides). The discussion in Section 5.1.4.2 has been clarified to make this point.

Comment-10: Section 5.1.5.1, Page 5-13, last paragraph: Since TCLP testing has not been performed, it is premature to state that there are no RCRA hazardous wastes. It is possible that the soil could fail TCLP testing based on lead concentrations and be classified as a hazardous waste based on the Toxicity Characteristic.

Response: Extraction Procedure (EP) toxicity characteristics testing was performed on the most contaminated soils during the SI. All soils were negative for EP toxicity. It is therefore unlikely that they would fail TCLP. Nevertheless, this section has been revised to include the possibility that both lead and cadmium could fail TCLP tests.

Comment-11: Section 5.1.6, Page 5-15, 3rd paragraph: Alternative A2 does not eliminate exposure routes to the environment, although ecological risks are concluded to be low. The use of the word (as in EPA comment) "minimize" rather than "eliminate" with regard to risks would be more appropriate.

Response: Alternative A2 would not have any effect on ecological risks, although, as stated in the comment, ecological risks are minimal to begin with. A2 would, however, significantly reduce risks to human health. The word "eliminate" has been replaced with "minimize".

United States Environmental Protection Agency Comments (continued)

Comment-12: Section 5.1.6., Page 5-15, 4th paragraph: Explain how the no action alternative (A1) will eliminate the possibility that the RCRA action-specific ARAR would apply.

Response: The RCRA action-specific ARAR refers to the placement of excavated soils failing RCRA characteristics in RCRA-landfills. The No Further Action alternative, which does not include the excavation of soil, would eliminate the possibility that this ARAR could apply.

Comment-13: Section 5.1.6, Page 5-15, 5th paragraph: In the second to last sentence, based on the evaluation of Alternative A4 the "uncertain" effect on volume would be an increase.

Response: The text has been changed. However, as discussed in Section 5.1.4.1, it is not certain that the volume would increase.

Tables 5-3 through 5-9

The cost tables were reviewed and the following comments were noted:

- Additional details or backup information is necessary to fully review/check the tables. For example, sample analytical parameters associated with monitoring activities are important to accurately evaluate the costs.
- The validation costs appear to be low.
- The health and safety costs are low and do not appear to cover air monitoring equipment which can be a significant cost.
- PPE costs should be per person per day to be more accurate.
- The report text specifies an 18-inch thick cap layer while 24 inches is noted in Table 5-4.
- In Table 5-4, the Total O&M Present Worth is annual for 30 years, not 1 event in 5 years as noted on bottom line. Realistically, sampling frequency would probably decrease over time, if concentrations decreased.
- In Table 5-5, the Soil treatment unit cost of \$150 per cubic yard appears high if bulk mixing is being proposed.

United States Environmental Protection Agency Comments (continued)

Response: Additional details and back-up information have been included in the revised FS. The comments pertaining to validation, health and safety, PPE, total O & M present worth, and soil treatment unit costs have been reviewed, and the text and tables amended as necessary. In addition, the inconsistency between the text and Table 5-4 regarding the cap layer depth has been corrected.

APPENDIX A

Comment 7: Section 4 references to "No Action" should also be revised to "No Further Action" for consistency.

Response: This alternative has been changed to "No Further Action" throughout the text.

Comment 17: Protection of the community description should mention air monitoring activities proposed during excavation activities.

Response: The text has been amended to include air monitoring activities.

MDEP COMMENTS

C-19

11:UC4092/RC1579-01/16/97-D1

recycled paper

ecology and environment

GENERAL COMMENTS

Comment-1: The MADEP concurs with the development of and retention of a remedial alternative for the AOC 32 soils, containment via capping (A3). Although this remedial alternative is based upon the Toxic Substance Control Act (TSCA), the MADEP notes that the selection of this alternative would also meet MCP based cleanup goals.

Response: Note also that two other remedial actions were retained for AOC 32 soils, Excavation, Solidification, and On-site Disposal (A4), and Excavation and Off-Site Disposal (A6).

Comment-2: The MADEP maintains its position that 310 CMR 40.000 should be designated as an ARAR when it is the more stringent regulation consistent with the requirements of CERCLA 121 (d) (2) (A) (ii), especially where remediation of petroleum hydrocarbons is outside CERCLA purview. MCP Method 1, a previously acknowledged ARAR for oil contaminated sites, provides particular petroleum standards and 310 CMR 40.0996(5) provides upper concentration limits (UCL) for certain contaminants including those at FA II.

In light of the exceedences of the standards cited above, the lack of a retained remedial alternative for contaminated groundwater in the UST 13 grave should be readdressed. The Army's decision to not remediate groundwater at this location, based on low well yield, might be premature in that the feasibility of groundwater collection and treatment has not yet been examined. The analyzed presence of TPH, trichloroethylene and dichlorobenzene in excess of MCP standards is problematical.

The MADEP notes that the most recently available groundwater flow model indicates groundwater flow in the AOC 32 area to be towards the northeast which potentially allows the transport of AOC 32 contaminants to the Fort Devens Grove Pond Well Field. Historically these wells have shown some indication of impacts due to synthetic organic contaminants. In addition, the estimated lifetime cancer risk (ELCR) to a future site worker from the UST 13 groundwater of 5.2×10^{-3} exceeds the MCP ELCR of 1×10^{-5} promulgated in 310 CMR 40.0993(6).

Response: EPA has determined that the MCP is not an ARAR for these sites. The revised FS includes several alternatives which address the contaminated groundwater at UST 13. Groundwater flow at UST 13 is fairly complex, but it flows to the northeast toward Shepley's Hill Landfill and Plow Shop Pond and it cannot impact the Grove Pond well field at current rates of pumping.

Comment-3: The MADEP is concerned with the proximity of AOC 43A to the McPherson Well draft Zone II. The MADEP notes the potential for contaminated site soil, in excess of MCP upper concentration limits, to leach into the water table and impact the underlying aquifer. A review of the estimated excess cancer risks associated with AOC 43A detailed in the FA II remedial investigation note exceedences of the MCP promulgated ELCRs for both soil and groundwater exposures. The exceedences of the MCP ELCR limit combined with

Massachusetts Department of Environmental Protection Comments (continued)

the potential for further groundwater contamination require the consideration of remedial alternatives for the site.

Response: The response to specific comment 4 discusses the McPherson well and the most recent groundwater model. See responses to specific comments 6 and 7 for a discussion of the risk estimates at AOC 43A. The recently completed particle tracking model shows that the POL area could have only negligible impact on the McPherson well (see specific comment response no. 4). Therefore, no alternatives were developed for AOC 43A.

Massachusetts Department of Environmental Protection Comments (continued)

SPECIFIC COMMENTS

Comment-1: Section 1.2.1.1, Page 1-2, Paragraph 3: The MADEP recommends that the Army consider conducting a radiological survey of the yard on the east side of Cook Street due to the former use of the area as a motor vehicle scrap yard.

Response: A radiological survey has been performed, and the results have been included in Section 1 of the revised FS.

Comment-2: Section 1.2.1.3, Page 1-4, Paragraph 2: Arsenic concentrations in excess of screening values appear to be present in at least four subsurface soil samples as opposed to the one sample mentioned in the report. Samples with high arsenic concentrations include 32B-92-08X, 32B-92-09X, 32B-92-11X and 32B-92-12X. Please edit.

Response: The text is correct as written. Arsenic screening samples were exceeded in the 10-foot sample from 32B-92-08X and the 5-foot sample from 32B-92-15X. One test pit sample (32E-92-01X) in the UST area also had elevated arsenic.

Comment-3: Section 1.2.1.3, Page 1-6, Paragraph 4: The MADEP recommends that the report note that concentrations of TPH and dichlorobenzene were also analyzed in groundwater samples collected from 32M-92-06X and 32M-92-04X in excess of MCP reportable quantities. Trichloroethylene was noted in groundwater from 32M-92-06X in excess of MCP Method 1 standards.

Additionally, the MADEP notes that the most recent round of groundwater sampling from 32M-92-04X indicated a TPH concentration of 360,000 ug/l. This points to a substantial presence of organics in the area which would require remedial activity.

Response: This section has been revised to specifically mention these detections. However, please note that the EPA has determined that the MCP is not an ARAR.

Comment-4: Section 1.2.1.4, Page 1-9, Paragraph 2: The MADEP recommends that the report note the presence of arsenic in excess of background values in groundwater samples from 32M-92-06X and 32M-92-07X. Although the report states that any future use of area groundwater as drinking water is unlikely, the western portion of the site is immediately adjacent to the draft Zone II of the McPherson well based on the Preliminary Zone II Analysis for Production Wells at Fort Devens (ETA, January 20, 1994). The MADEP recommends a meeting to discuss all available Zone II data to determine if the site could have a potential impact on area drinking water supplies.

Response: Arsenic is discussed both in Section 1.2.1.3 (Nature and Extent of Contamination) and in Section 1.2.1.4 (Human Health Risk Assessment Summary). Arsenic

Massachusetts Department of Environmental Protection Comments (continued)

exceeded screening values and was primarily responsible for the estimates of risk due to the future usage of groundwater. However, as discussed in Section 1.2.1.3, as well as in Section 5.4.2 of the RI, arsenic is clearly related to particulate matter in the aquifer. Arsenic concentrations dropped dramatically in filtered samples, often by several orders of magnitude, to below the detection limit. Also, based on the correlation between aluminum, iron, and the other heavy metals, it appears that arsenic is naturally occurring. As discussed in Section 1.2.1.4, as well as in Section 8.5.2.2 of the RI, the human health risks are considerably lower when filtered data are used. Furthermore, Section 8.5.4 of the RI discusses risks associated with exposure to ambient levels of arsenic, which far exceed EPA acceptable risk thresholds.

A solute transport model was recently completed by Engineering Technologies Associates, Inc. (ETA) to assess the possibility that contamination from AOC 43A could impact the McPherson well. ETA's report is included as an appendix to the revised FS. The report analyzes the potential for xylene, the only contaminant confirmed in groundwater samples at AOC 43A, to impact the McPherson well. The analysis accounts for retardation, dispersion, and biodegradation. The model shows that all of the xylene will degrade before leaving the POL area, far upgradient of the well, using conservative decay rates. Even when retardation, dispersion, and biodegradation effects are ignored, the model predicts maximum xylene concentrations in McPherson well of only 1.29×10^{-3} $\mu\text{g/L}$, which is not even detectable. Moreover, the model is extremely conservative, using the highly unrealistic scenario of pumping McPherson well at 1,000 gallons per minute for 180 days without any aquifer recharge. Finally, the model would actually overestimate the impact of arsenic at AOC 32 on the McPherson well. AOC 32 is further from McPherson well than AOC 43A, and arsenic will be hindered by stronger sorption effects than xylene. Thus, the model clearly demonstrates that the contaminants at AOCs 32 and 43A cannot have any measurable impact on the McPherson well.

Comment-5: Section 1.3, Page 1-21, Paragraph 4: No remedial alternatives for UST 13 groundwater were noted in the Feasibility Study. Please note our general comments.

Response: Several remedial alternatives for UST 13 groundwater have been developed in Section 4.2 of the revised FS.

Comment-6: Section 1.3, Page 1-21, Paragraph 5: The MADEP does not concur with the recommendation for No-Remedial-Action at AOC 43A. The presence of heavy metals and organics in site soils as detailed in Section 1.2.2.3 of this report combined with an excess lifetime cancer risk (ELCR) of 1×10^{-4} , which exceeds the Massachusetts ELCR of 1×10^{-5} , requires development of remedial alternatives for site surface soils. The MADEP recommends nomination of 310 CMR 40.0993(6) as an ARAR, which states requirements for Massachusetts cumulative cancer risk limits.

Response: As stated in the comment, the excess lifetime cancer risk (ELCR) associated with AOC 43A soils was estimated at 1×10^{-4} . The 10^{-5} threshold was exceeded in two

Massachusetts Department of Environmental Protection Comments (continued)

other pathways at AOC 43A. The ELCR for all three were due entirely to arsenic and PAHs (detected in only one sample). (Similarly, the maximum health index (HI) calculated for AOC 43A soils was due to arsenic.) However, as previously stated, the detections of PAHs and arsenic were extremely sporadic. As discussed in the RI (FAII, Vol II, Section 8.5.3), arsenic is a naturally occurring metal, and estimated daily exposures to arsenic would correspond to an estimated cancer risk of up to 1×10^{-3} and a health index of 2.4. Arsenic was consistently detected in background samples and was detected at a high concentration (210 $\mu\text{g/g}$) in only one sample. PAHs are common in areas exposed to vehicular traffic and the maximum concentrations (2 to 4 ppm in only one sample) are similar to those found in other traffic areas and below the candidate cleanup goal of 7 $\mu\text{g/g}$ (based on 10^{-5} risk threshold). In summary, the detections of arsenic and PAHs are sporadic, and in most cases very slightly elevated. The presence of these compounds is clearly associated with ambient conditions and not a contaminant source. The time and expense required to implement a remedial program for a non-existent source is clearly unwarranted.

The subsurface screening samples indicated three plumes of TPHC and/or BTEX contamination. However, confirmatory sampling did not confirm any of the field screening for BTEX, and only two of the three TPHC plumes were confirmed. The lack of confirmation for TPHC in the other plumes was attributed either to a high "background" of TPHC during the field screening or to variability in the screening analysis. BTEX compounds were not detected at any concentration in any of the laboratory-analyzed surface or subsurface samples. Where TPHC and BTEX detected by the field screening were unconfirmed, the screening results were not considered usable for the risk assessment or the feasibility study. The screening samples were limited to assessing likely "hot spots," in order to place boreholes for laboratory analysis. At the eastern and western TPHC plumes, the screening samples appear to reflect site conditions, based on one laboratory analysis of samples from two boreholes. However, the plumes clearly are not migrating off site, and, as discussed in the response to Comment-4, the ETA model shows that contaminants will not impact McPherson well. Petroleum hydrocarbons are generally very degradable and sorb more strongly than xylenes. Even more importantly, all of the TPHC was encountered at depth, so the suggestion in the comment that remedial alternatives are required for surface soils is not accurate.

Comment-7: Section 2.7.1, Page 2-8, Paragraph 2: The MADEP continues to be concerned with the analyzed presence of BTEX, TPH, and arsenic in AOC 43A groundwater and recommends that the presence of these contaminants be addressed in the section.

Response: The detections of BTEX and TPHC at high concentrations in the field screening samples were not confirmed in groundwater samples taken from completed monitoring wells. Wells were completed in the "hot spots" as revealed by the field screening, but the well samples showed only very sporadic hits at concentrations much lower (by orders of magnitude) than those found in the screening samples. In fact, the groundwater screening samples were determined to not be representative of the groundwater conditions, based on sampling methodology. Borings were advanced with an auger

Massachusetts Department of Environmental Protection Comments (continued)

bit until the water table was reached. Groundwater filled the hole, and this water was sampled. Any contamination which may have been present in the soils would be free to fall down into the water in the bottom of the bore hole. Therefore, it is not possible to differentiate between contamination in the groundwater and contamination in the soils (BTEX was also not confirmed in soil samples) from field screening samples. Furthermore, it was not possible to purge the water samples obtained with field screening methodology, as is normal protocol for well sampling. Therefore, TPHC and BTEX were not found to be above cleanup goals after groundwater screening samples not confirmed in monitoring wells were eliminated from consideration.

Arsenic was detected above its screening value in approximately half of the unfiltered samples. However, the concentrations dropped dramatically, usually to below the detection limit, in all of the filtered groundwater samples. This clearly shows that the arsenic is naturally occurring and sorbed to mineral particles in the matrix. Further evidence to support this is provided by the high correlation between aluminum and iron and all of the heavy metals. Such correlation would be expected in environments with a significant mineral presence. There would be no reason to develop remedial alternatives for naturally-occurring metals, which are immobilized within the aquifer matrix.

These detections are discussed further in Section 1. Because the unconfirmed BTEX and TPHC detections are not useable for the risk assessment or feasibility study, it is not appropriate to discuss them in Section 2.7, where cleanup goals are discussed. Because arsenic does not exceed cleanup goals at POL, it is not discussed either. Moreover, the ETA model (see response to Comment-4) clearly indicates that contamination in the POL groundwater will not impact the McPherson well, or even migrate off site. Although the model was performed on xylenes, it is relevant for TPHC, which is also biodegradable and generally more sorbing.

Comment-8: Section 4.2.5, Page 4-9, Paragraph 4: Although AOC 32 UST Grave 13 groundwater treatment was dropped by the Army as an alternative in the screening document for FAs I and II, due to low expected yield, the MADEP continues to recommend that the Army consider analyzing the feasibility of potential remedial alternatives for the contaminated groundwater in the bedrock. The contaminant persistence and increased concentrations at this site exceed the Massachusetts upper concentration limits (UCL) of 100,000 ug/l. The MADEP recommends that 310 CMR 40.0996(5), which details UCLs be nominated as an Applicable or Relevant and Appropriate Requirement (ARAR).

Since the groundwater contamination is moving very slowly, a low yield recovery well may be quite acceptable. Therefore, the MADEP recommends that the Army retain remedial alternative B-4, Capping and Groundwater Extraction with Off-Site Treatment.

Response: Several remedial alternatives for UST 13 groundwater have been developed in Section 4.2 of the revised FS. The feasibility of these alternatives is discussed there. As stated above, EPA has determined that the MCP is not an ARAR. The alternatives were developed not because of the UCL exceedance but because the PCBs and chlorobenzenes

Massachusetts Department of Environmental Protection Comments (continued)

exceed cleanup goals, result in ELCRs exceeding 10^{-4} , and represent contamination from the former UST. For AOC 43A soils and groundwater, on the other hand, no source is present to explain the risks to human health due to arsenic and PAHs, which only slightly exceed the 10^{-5} threshold and reflect ambient conditions.